

TARGET SHEET

SITE NAME: RAY	WICHERT PROPERTY	
CERCLIS I.D.:	OKD987095049	
TITLE OF DOC.:	SITE INSPECTION PRE-SCORE ATTAC FOR SITE INVESTIGATION REPORT OF WICHERT PROPERTY	
DATE OF DOC.:	01/01/1111	
NO. OF PGS. THIS T	ARGET SHEET REPLACES:	UNKNOWN
SDMS #:9	76148	
CONFIDENTIAL?	MISSING PAGES ?	
ALTERN. MEDIA?	CROSS REFERENCE ?	
LAB DOCUMENT?	LAB NAME:	
ASC./BOX #:		
CASE #:	SDG #:	
_	DOCUMENT WAS SUBMITTED WITH A WHICH CONTAINS FILES IN AN UNKNO	_

Page 1 of 9

ATTACHMENT A WASTE CHARACTERISTICS

There are two primary waste sources known to be present on the Ray Wichert Property at the present time: (1) underground storage tanks (USTs) and their associated piping and motor fuel dispensers, which are lying on the ground surface in the southern half of the basin on site; and (2) numerous scattered waste piles of construction debris and other solid wastes, which are lying on the ground surface in the northern half of the basin. Some of the construction debris may be contaminated with radium (References 4, 24, and 25).

Four underground storage tanks, the piping (lines) for those tanks, and three fuel dispensers are lying on the ground surface in the southern end of the basin on site. Three of the USTs appear to be 10,000 to 12,000 gallon tanks, being approximately 8 to 10 feet in diameter by approximately 20 feet in length. The fourth UST is smaller, perhaps 1,500 gallons in volume, and may have been a waste oil tank. All four USTs are metal tanks that are completely rusted, and no labels, engravings, or other markings are visible on them to identify their age, construction, contents, volume, or ownership. At least half of the openings for piping on each UST are open, while the other half of the openings are plugged. Corrosion has eaten completely through each UST, leaving small holes which are located mostly along the seams at the ends of each tank. There was no odor of petroleum hydrocarbons around the tanks, and no hydrocarbon stains are present on the soil around the tanks. It is not known if petroleum hydrocarbons are still present in these tanks in the form of sludge, liquid, or vapor (Reference 4).

Piping for these four USTs is lying on the ground, immediately north of the tanks. Three motor fuel dispensers are lying on the ground, just south of the tanks. Metal poles and signs, including two Texaco signs, are lying on the ground near the fuel dispensers and USTs (Reference 4).

The four USTs, three dispensers, and piping appear to have been removed from the dispenser island area on the high, level ground at the south end of the site. The dispenser island clearly shows that three dispensers had once stood on it. Thus it is reasonable to assume that the three dispensers lying on the ground in the south end of the basin on site were removed from the dispenser island on site. No trace of fill pipes for USTs was seen on the ground around the dispenser island and buildings on site. Rusty scratches on the concrete pad around the dispenser island suggest that USTs may have been dragged across the pad after they were removed from the ground. Thus it is reasonable to assume that the four USTs lying on the ground in the southern end of the basin on site were removed from the ground in the vicinity of the dispenser island. No stains of petroleum hydrocarbons are present on the concrete pad or gravel around the dispenser island and buildings, but oily liquid is present in the grease trap outside the large door on the north side of the large building (Reference 4).

Page 2 of 9

ATTACHMENT A WASTE CHARACTERISTICS (Continued)

An aerial photograph shows that there was no development on the site in 1974 (Reference 16). Thus the USTs were not installed on the site until some time after 1974. The tanks were removed from the ground in December, 1998, and the tank closure report indicates that no hydrocarbon contamination of soil was discovered at the time of tank removal (Reference 26). Thus there is no evidence of hydrocarbon contamination in the soil or groundwater at the south end of the site.

Numerous waste piles of construction debris and other solid wastes are scattered around on the ground surface in the northern half of the basin (north of the dilapidated fence) on site. Almost all of the waste in these waste piles is construction (or demolition) debris. Several old hot water heaters, and possibly a few small oil field separator vessels, are also present at one location among the waste piles. Only a few buckets and other containers are present among the waste piles. One container appeared to have contained lubricating oil. The construction debris consists of bricks, concrete, asphalt, and minor amounts of scrap lumber and scrap metal. Traces of linoleum on flat slabs of concrete are the remains of interior floors of a building. Fragments of brick walls, concrete floors, and cinder block foundations are abundant, and one slab of concrete bears the date, "10-17-27". Shingles are present on roof fragments. These scattered waste piles cover a surface area of approximately 20,000 square feet. [The waste piles are scattered over a total area of approximately 100 feet by 800 feet, and are estimated to cover not more than 25% of that total 80,000 square foot area.] Some of the solid wastes from these piles are lying on the bed and banks of the intermittent stream on the eastern margin of the site. No stains are present on the soil around these numerous waste piles (Reference 4).

At least some of the demolition waste on the Ray Wichert Property was derived from the Sooner Dial site in Clinton, Oklahoma. Some of the Sooner Dial demolition waste may be contaminated with radium. Radiation surveys of soil and waste piles on the Ray Wichert Property were conducted by the Oklahoma State Department of Health and by the OES. These radiation surveys discovered that radioactivity exceeded background levels at certain locations among the soil and waste piles (References 4, 24, 25).

The preliminary assessment report for the Ray Wichert Property (Reference 6) said that six unmarked drums of unknown contents were present on the site near the present location of the four USTs. No traces of these drums or their spilled contents were seen during a reconnaissance of the site by OES personnel on May 1, 2003 (Reference 4).

The OSDH conducted two radiation surveys of the Ray Wichert Property and found radiation levels among the waste piles that ranged from approximately $100~\mu\text{R/hr}$ up to $350~\mu\text{R/hr}$. Soil samples collected among the waste piles during the radiation surveys were found to contain 18 to 385 pCi/gm of radium. Details of these OSDH radiation surveys and soil sampling events are described in References 25 and 27.

Page 3 of 9

ATTACHMENT A WASTE CHARACTERISTICS (Continued)

Four soil samples were collected at the time of UST removal and closure on the Ray Wichert Property on December 30, 1998 (Reference 26). The samples were collected at the east ends of the USTs, which is most likely the downgradient end for each tank with respect to the direction of groundwater movement. [Shallow groundwater most likely moves east-northeast across the site, moving from higher ground toward the intermittent stream on the eastern margin of the site.] However, the soil depth interval from which each sample was collected was not recorded in the closure report. The samples were sent to Isotek Laboratory Services in Oklahoma City for analyses. The samples were analyzed for benzene, toluene, ethylbenzene, total xylenes, volatile total petroleum hydrocarbons (gasoline range organics), and extractable total petroleum hydrocarbons (diesel range organics). None of these hydrocarbons were detected in the samples.

Analyses of the five surface soil samples collected among the waste piles by OES revealed that four inorganic analytes were present in one or more samples at a concentration of three or more times their concentrations in the background sample or at a concentration in excess of the sample quantitation limit (**Table 1** and Reference 6). These four analytes were arsenic, cadmium, calcium, and mercury. The concentrations of cadmium, calcium, and mercury in these samples did not equal or exceed the EPA's Region 6 Human Health Medium-Specific Screening Levels (Reference 28). Arsenic exceeded the screening levels for residential and industrial cancer risk in sample 4 (References 6 and 28). However, its concentration in sample 4 (4.7 mg/kg) is well within the normal concentration range of arsenic in uncontaminated soils (References 29, pp. 83 and 84, and 30), which suggests that the arsenic in sample 4 is derived from natural sources rather than from the waste piles on the Ray Wichert Property.

Analyses of the five surface soil samples collected among the waste piles revealed that fourteen semivolatile organic compounds were present in one or more samples at a concentration of three or more times their concentrations in the background sample or at a concentration in excess of the sample quantitation limit (**Table 2** and Reference 7). With the exception of carbazole, all of these compounds are polynuclear aromatic hydrocarbons (PAHs). Six of these PAHs are present in one or more samples at concentrations that exceed one or both of the following EPA Region 6 Human Health Medium-Specific Screening Levels: the residential risk-based screening level for contaminants in soil; and the industrial risk-based screening level for contaminants in soil (Reference 28). The six PAHs that exceed one or both of these screening levels are benzo (a) anthracene, benzo (b) fluoranthene, benzo (k) fluoranthene, benzo (a) pyrene, indeno (1,2,3-cd) pyrene, and dibenzo (a,h) anthracene. These PAHs are marked with one or two asterisks (* or **) in **Table 2**, depending on whether they exceed one or both of the risk-based screening levels (residential and industrial) in a given soil sample.

Page 4 of 9

ATTACHMENT A WASTE CHARACTERISTICS (Continued)

The presence of PAHs in the soil samples collected among the waste piles is difficult to explain. PAHs are commonly found in petroleum products, such as gasoline and lubricating oil (Reference 31). However, petroleum products and stained soils were not seen among the waste piles, and only a few containers were present among the piles (Reference 4). The soil samples were *not* collected from the vicinity of the underground storage tanks lying on site. Furthermore, no PAHs were present in the field and equipment blank samples collected at the site during the soil sampling event (Reference 7). Thus there is no obvious source among the waste piles for the PAHs present in the soil samples.

Analyses of the five surface soil samples collected among the waste piles revealed that seven pesticides were present in one or more samples at a concentration of three or more times their concentrations in the background sample or at a concentration in excess of the sample quantitation limit (**Table 3** and Reference 7). These seven pesticides were dieldrin, endrin, endosulfan II, 4,4'-DDD, 4,4'-DDT, endrin ketone, and alpha-chlordane. These pesticides did not exceed EPA Region 6 Human Health Medium-Specific Screening Levels in any sample (Reference 28).

RADIATION SURVEY

On May 1, 2003 the OES used a Ludlum Model 3A Survey Meter with a Ludlum model 44-9 pancake-type gamma ray detector to screen the surface soil and solid waste piles in the topographic basin of the Ray Wichert Property for radioactivity (Reference 4). Background radiation in the basin ranged from $10 \mu R/hr$ to $60 \mu R/hr$. The radioactivity of all surface soil surveyed in the basin ranged from $10 \mu R/hr$ to approximately $50 \mu R/hr$. The radioactivity of almost all solid waste (demolition debris, linoleum, asphalt, concrete, brick, scrap metal, scrap lumber) surveyed in the basin ranged from $10 \mu R/hr$ to $60 \mu R/hr$. Only one waste pile near the center of the northern half of the basin was found to contain debris with radioactivity exceeding the maximum background level of $60 \mu R/hr$. Two small slabs of concrete debris in this waste pile were found to have radioactivity of up to $600 \mu R/hr$, which is ten times the maximum background level on site. These high levels of radioactivity suggest that the demolition debris in this waste pile may have come from the Sooner Dial site in Clinton, Oklahoma (References 25 and 27).

Page 5 of 9

ATTACHMENT B GROUNDWATER PATHWAY

The surface rocks at the Ray Wichert Property, in descending stratigraphic order, consist of Quaternary terrace deposits of sand, silt, clay, and gravel; the Permian Cloud Chief Formation of reddish-brown shale, siltstone, and sandstone; and the Permian Rush Springs Formation of orange-brown, fine-grained sandstone. The total thickness of these formations may be approximately 400 feet in the Clinton area (Reference 8, sheet 1). Red sandstone bedrock is exposed on the floor of the basin within the Ray Wichert Property, which suggests that the overlying terrace deposits have been removed from the basin (Reference 4). Terrace deposits and the Rush Springs Formation serve as the principal aquifers in the Clinton area. The terrace deposits may be up to 120 feet thick, while the Rush Springs Formation is approximately 186 feet thick in the Clinton area. Water from the Rush Springs Formation in the Clinton area is very hard, containing calcium, magnesium, and sulfate, as well as more than 1000 mg/l of dissolved solids (Reference 8, sheets 1, 2, and 3).

Municipal and rural water systems supply drinking water to almost all residents within four miles of the Ray Wichert Property. Clinton Lake and Foss Lake are the sources of drinking water for the towns of Clinton and Arapaho (Reference 18). These lakes are located twelve to fourteen miles west of the Ray Wichert Property (References 11 and 12). Custer County Rural Water District 3 (RWD3) supplies drinking water to almost all rural residents within four miles of the site. RWD3 obtains its drinking water from three groundwater wells located approximately fifteen miles northeast of the site (References 11, 13, and 14). No private drinking water wells were seen within one mile of the site (Reference 4). Approximately 12 residences, located at least two miles south of the site in Washita County, lie outside both RWD3 and the City of Clinton municipal water system (References 11, 12, 13, and 14). These twelve residences are presumed to have private drinking water wells, but these wells are not hydraulically downgradient from the site. These twelve residences have a resident population of approximately 30 persons (Reference 23). Thus the secondary target population for the groundwater pathway is 30 persons. There is no primary target population for the groundwater pathway.

No groundwater samples were collected for this SI of the Ray Wichert Property.

Page 6 of 9

ATTACHMENT C SURFACE WATER PATHWAY

The waste piles and underground storage tanks on the Ray Wichert Property lie on level or gently sloping ground in a topographic basin immediately adjacent to the west bank of an intermittent stream (Reference 4). The waste piles and USTs are completely exposed to the weather (Reference 4) in an area that receives an annual average of 25 inches of precipitation (Reference 8, sheet 4). The intermittent stream bordering the northern half of the site lies within the 100-year floodplain, but the waste piles and USTs lie outside this floodplain (Reference 5). Surface water runoff from the site enters the intermittent stream and flows northward, then eastward toward the Washita River, which is the nearest perennial water body. The site is more than two miles upstream from the Washita River. Thus there is no 15-mile surface water pathway for this site.

The site constitutes a drainage area of approximately 5.9 acres. Analyses of soil samples collected by OES personnel during this SI suggest that insecticides and polynuclear aromatic hydrocarbons might be entering the site from alternate sources around the site margins (**Tables 2** and **3**).

There are no surface water receptors because there is no surface water pathway for this site. Clinton Lake and Foss Lake, which are the sources of drinking water for the towns of Clinton and Arapaho, are located upstream from the site (References 11, 12, and 18). The nearest HRS-defined wetland is more than two miles downstream from the site, as is the nearest perennial water body (Reference 20).

No surface water or sediment samples were collected for this SI of the Ray Wichert Property.

Page 7 of 9

ATTACHMENT D SOIL PATHWAY

Soils on the Ray Wichert Property are of the Woodward-Quinlan Association. These are shallow to deep, well drained, loamy soils over sandstone and which belong to hydrologic soil group B (References 1 and 16). Sandstone bedrock is exposed at a few places within the topographic basin on the site (Reference 4).

Approximately 25 people live in 10 homes that are located within 200 feet west and north of the site (References 4 and 23). No one works on the site, but at least twelve or more active businesses are located within 200 feet of the site (Reference 4). As many as 9 businesses are located along the eastern margin of the site; 2 businesses are located immediately south and southeast of the site; and several businesses are located near the northwestern corner of the site. The number of workers at these twelve or more businesses is unknown, but if the number of workers per business is assumed to be the same as the average number of residents per household in Custer County (Reference 23), then the total number of workers within 200 feet of the site would be approximately 29 persons. There are no daycare facilities within 200 feet of the site, but a school of gymnastics (Olympic Gold Gymnastics) is located immediately adjacent to the northeastern corner of the site. There is unrestricted access to the site from the gymnastics school parking lot. The number of students attending this school of gymnastics is unknown, but numerous young children were seen taking classes at the school (Reference 4). Although the SI sample data described at the end of this section document the presence of contamination in the soil on the Ray Wichert Property, such contamination is not known to extend onto the properties of the nearest residents, the nearest businesses, and the gymnastics school. Therefore, the nearest residents, workers, and gymnastics school students cannot be considered as targets for the site under hazard ranking system (HRS) guidelines (Reference 19).

Approximately 1341 persons live within one mile of the site (Reference 32). Although access to the site is unrestricted (Reference 4), there is little evidence that people frequently enter the site. For example, buildings on the southern end of the site are not vandalized, fresh trash is not strewn around the buildings or on other parts of the property, recreational vehicle tracks are not present on the property, and the waste piles in the northern half of the site show little or no evidence that dumping is an ongoing process that is still occurring.

The site is in an urban area (Reference 4). Thus there are no terrestrial sensitive environments on or within 200 feet of the site. Although there is a wetland immediately adjacent to the northeastern margin of the site, it probably does not meet the requirements (presence of emergent hydrophytic vegetation) for designation as an HRS-defined wetland (References 19, page A-30, and 20). None of the endangered or threatened species known to be present in Custer County are known to be present on the site (Reference 21).

Page 8 of 9

ATTACHMENT D SOIL PATHWAY (Continued)

The SI sample data indicate that arsenic, cadmium, calcium, mercury, carbazole, thirteen polynuclear aromatic hydrocarbons (PAHs), and seven pesticides are present in the soil among the waste piles at concentrations significantly above background concentrations (see Attachment A, **Tables 1**, **2**, and **3**; and References **6** and **7**). Of these 25 contaminants, only arsenic and 6 PAHs are present at concentrations that exceed EPA Region 6 Human Health Medium-Specific Screening Levels (Reference **28**). The arsenic may be derived from natural sources, while the source of PAHs in the soil among the waste piles is unknown. The radioactivity of surface soil in the basin on site does not appear to exceed background levels (Reference **4**). There is no soil sample data for the nearby residences, businesses, and gymnastics school.

Page 9 of 9

ATTACHMENT E AIR PATHWAY

The underground storage tanks and waste piles on the Ray Wichert Property are fully exposed to the weather (Reference 4). It is not known if the USTs still contain gasoline or diesel fuel, nor whether they are releasing volatile airborne contaminants to the atmosphere. The waste piles are not believed to be a source of volatile airborne contaminants. No air sampling was conducted by OES personnel during their SI activities at the site.

The nearest residents to the Ray Wichert Property live less than 200 feet west of the site (Reference 4). There are approximately 59 residents within 0.25-mile of the site and an additional 9561 persons living within four miles of the site (References 4, 11, 12, 17, 22, and 23).

Wetlands are the only sensitive environments located within four miles of the site. There is an approximate total of at least 43 acres of HRS-defined wetlands within four miles of the site, with the nearest wetland being 0.83-mile southeast of the site (Reference 20).

TABLE 1 INORGANIC CONTAMINANTS IN SURFACE SOIL AMONG WASTE PILES ON RAY WICHERT PROPERTY

ANALYTE	CONCENTRATIONS (mg/kg), with Sample Quantitation Limits in brackets []					
	DUPLICATES		SAMPLE 3 (MFJK52)	SAMPLE 4 (MFJK53)	SAMPLE 5 (MFJK54)	BACK- GROUND
	SAMPLE 1 (MFJK50)	SAMPLE 2 (MFJK51)			,	SAMPLE 6 (MFJK55)
ARSENIC	3.2 UC	4.1 UC	2.6 UC	4.7 J^ [2.5]	2.9 UC	3.4 UC [2.5]
CADMIUM	0.20 LUC	0.50 LUC	0.67 LJ^	0.22 LUC	3.3 [1.1]	0.25 LUC [1.2]
CALCIUM	78000 J [1220]	27800 J	88600 J [1100]	26400 J	56400 J [1070]	18000 J [1250]
MERCURY	0.076 L	0.075 L	0.096 L	0.058 L	0.18 [0.09]	0.064 L [0.10]

DATA FLAGS AND MEANINGS:

- L Reported concentration is between the Instrument Detection Limit (IDL) and the Contract Required Detection Limit (CRDL).
- J The result is an estimate.
- UC Reported concentration should be used as a raised detection limit because of apparent blank contamination.
- ^ High bias. Actual concentration may be lower than the concentration reported.

TABLE 2 POLYNUCLEAR AROMATIC HYDROCARBON CONTAMINANTS IN SURFACE SOIL AMONG WASTE PILES ON RAY WICHERT PROPERTY

ANALYTE	CONCENTRATIONS (µg/kg), with Sample Quantitation Limits in brackets []						
	DUPLICATES		SAMPLE 3 (FGG58)	SAMPLE 4 (FGG59)	SAMPLE 5 (FGG60)	BACK- GROUND	
	SAMPLE 1 (FGG56)	SAMPLE 2 (FGG57)				SAMPLE 6 (FGG61)	
ACENAPHTHENE	2300 J^ [1900]	1800 LJv	1100 LJ	21 LJ	400 LJ	400 U	
PHENANTHRENE	5400 J^	22000 Jv [9900]	11000 [1900]	130 LJ	4400 [1800]	40 LJ	
ANTHRACENE	1700 J^	5800 Jv [2000]	2600 [1900]	47 LJ	1000 LJ	400 U	
FLUORANTHENE	63000 [9700]	39000 [9900]	15000 [3800]	250 LJ	7700 [1800]	79 LJ	
PYRENE	52000 [9700]	29000 [9900]	16000 J [3800]	230 LJ	6700 [1800]	67 LJ	
BENZO (a) ANTHRACENE	** 32000 [9700]	** 19000 [9900]	* 7600 [1900]	120 LJ	* 3000 [1800]	34 LJ	
CHRYSENE	32000 [9700]	20000 [9900]	8500 [1900]	190 LJ	3500 [1800]	54 LJ	
BENZO (b) FLUORANTHENE	* 3500 J^	** 16000 J v [2000]	* 6800 [1900]	210 LĴ	* 2900 [1800]	75 LJ	
BENZO (k) FLUORANTHENE	* 15000 [9700]	8600 LJ	* 7900 [1900]	180 LJ	3500 [1800]	400 U	
BENZO (a) PYRENE	** 26000 [9700]	** 16000 [2000]	** 7600 [1900]	160 LJ	** 3200 [1800]	37 LJ	
INDENO (1,2,3-cd) PYRENE	** 13000 [1900]	** 8300 [2000]	* 4000 [1900]	100 LJ	* 1800 [1800]	26 LJ	
DIBENZO (a,h) ANTHRACENE	** 6900 [1900]	** 3600 [2000]	** 1900 [1900]	40 LJ	740 LJ	400 U	
BENZO (g,h,i) PERYLENE	13000 [1900]	8200 [2000]	4400 [1900]	110 LJ	2100 [1800]	29 LJ	
CARBAZOLE ‡	980 J^	2200 Jv [2000]	1700 LJ	31 LJ	710 LJ	400 U	

TABLE 2 (Continued) POLYNUCLEAR AROMATIC HYDROCARBON CONTAMINANTS IN SURFACE SOIL AMONG WASTE PILES ON RAY WICHERT PROPERTY

DATA FLAGS AND MEANINGS:

BOLD FACE	Concentration is equal to or greater than three times the background concentration of this same analyte; or concentration is equal to or greater than the detection limit (CRQL or SQL) when the background concentration of the same analyte is undetected (U) or below the sample quantitation limit (SQL).
L	Reported concentration is below the Contract Required Quantitation Limit (CRQL).
J	Estimated value.
U	Not detected at reported quantitation limit.
	High bias. Actual concentration may be lower than the concentration reported. Concentration shown in table has been corrected for high bias in accordance with EPA guidance for interpretation of Contract Laboratory Program data.
· v	Low bias. Actual concentration may be higher than the concentration reported.
* *	Concentration exceeds EPA's Region 6 residential risk-based screening level for this analyte in soil (Reference 19).
**	Concentration exceeds both the EPA's Region 6 residential risk-based screening level and industrial risk-based screening level for this analyte in soil (Reference 19).
‡	Carbazole is not a polynuclear aromatic hydrocarbon (PAH), but is included in this table because, like the PAHs, it is a semivolatile organic compound.

TABLE 3 PESTICIDE CONTAMINANTS IN SURFACE SOIL AMONG WASTE PILES ON RAY WICHERT PROPERTY

ANALYTE	CONCENTRATIONS (µg/kg), with Sample Quantitation Limits in brackets []					
	DUPLICATES		SAMPLE 3 (FGG58)	SAMPLE 4 (FGG59)	SAMPLE 5 (FGG60)	BACK- GROUND
	SAMPLE 1 (FGG56)	SAMPLE 2 (FGG57)		,	,	SAMPLE 6 (FGG61)
DIELDRIN	2.1 LJ	4.1 U	5.4 [3.8]	0.83 LJ	3.6 U	4.2 U
ENDRIN	4.7 J [3.9]	4.1 U	3.8 U	3.2 LJ	4.8 J [3.6]	1.0 LJ
ENDOSULFAN II	4.0 J [3.9]	4.1 U	3.8 U	0.58 LJ	3.6 U	0.94 LJ
4,4'-DDD	6.6 J [3.9]	4.1 U	3.8 U	0.95 LJ	3.6 U	4.2 U
4,4'-DDT	24 J^	29 Jv [4.1]	3.8 U	13 [1.3]	3.6 UJv	4.2 U
ENDRIN KETONE	14 [3.9]	16 [4.1]	3.8 U	4.2 U	3.6 U	4.2 U
ALPHA- CHLORDANE	1.1 J^	3.1 Jv [2.1]	2.0 U	2.2 U	1.9 U	0.84 LJ

DATA FLAGS AND MEANINGS:

BOLD FACE	Concentration is equal to or greater than three times the background concentration of this same analyte; or concentration is equal to or greater than the detection limit (CRQL or SQL) when the background concentration of the same analyte is undetected (U) or below the sample quantitation limit (SQL).
--------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

- L Reported concentration is below the Contract Required Quantitation Limit (CRQL).
- J Estimated value.
- U Not detected at reported quantitation limit.
- ^ High bias. Actual concentration may be lower than the concentration reported. Concentration shown in table has been corrected for high bias in accordance with EPA guidance for interpretation of Contract Laboratory Program data.
- v Low bias. Actual concentration may be higher than the concentration reported.

REFERENCES FOR RAY WICHERT PROPERTY SI PRE-SCORE PACKAGE

- 1. <u>Hazard Ranking System, Final Rule</u>. U. S. Environmental Protection Agency, 40 CFR, Part 300. Federal Register, Vol. 55, No. 241, Book 2, December 14, 1990.
- 2. U. S. Environmental Protection Agency. Prescore Software, Version 4.1, June, 1996.
- 3. U. S. Environmental Protection Agency, Washington, D. C. Superfund Chemical Data Matrix, June 19, 1996.
- 4. Cherokee Nation, Office of Environmental Services Field Logbook No. 1 of reconnaissance and sampling activities at Ray Wichert Property, April, 2000 to May, 2003.
- 5. Flood Insurance Rate Map for City of Clinton, Custer County, Oklahoma, panel number 400054 0005 D. Federal Emergency Management Agency, April 3, 1987. Map accessed through FEMA website at www.fema.gov.
- 6. U. S. Environmental Protection Agency, Region 6, Contract Laboratory Program Data for inorganic analyses of samples from Ray Wichert Property, June 16, 2000.
- 7. U. S. Environmental Protection Agency, Region 6, Contract Laboratory Program Data for organic analyses of samples from Ray Wichert Property, July 18, 2000.
- 8. Carr, Jerry E., and Bergman, DeRoy L. <u>Hydrologic Atlas 5: Reconnaissance of the Water Resources of the Clinton Quadrangle, West-Central Oklahoma</u>. Oklahoma Geological Survey, 1976.
- 9. Cherokee Nation, Office of Environmental Services. Site Health, Safety, and Sampling Plan for Ray Wichert Property, April, 2000.
- 10. Nielsen, David M., editor. <u>Practical Handbook of Ground-Water Monitoring</u>. Lewis Publishers, Chelsea, Michigan, 1991, x + 717 pages.
- 11. General Highway Map of Custer County, Oklahoma. Oklahoma Department of Transportation Planning Division, January, 1995.
- 12. General Highway Map of Washita County, Oklahoma. Oklahoma Department of Transportation Planning Division, January, 1992.
- 13. Communication Reference. Custer County Rural Water District 3. From: Linda Ray, Custer County Rural Water District 3. To: Kent Curtis, Environmental Specialist II, Cherokee Nation's Office of Environmental Services, June 18, 2003.
- 14. Rural Water Systems In Oklahoma. Oklahoma Water Resources Board, Planning and Management Division, Publication Number 138, January, 1998.

REFERENCES FOR RAY WICHERT PROPERTY SI PRE-SCORE PACKAGE

- 15. U. S. Department of Commerce, Weather Bureau, Technical Paper No. 40, Rainfall Frequency Atlas of the United States, May, 1961.
- 16. Henson, Odos G. <u>Soil Survey of Custer County, Oklahoma</u>. U. S. Department of Agriculture, Soil Conservation Service, April, 1978.
- 17. Bessie, Clinton, Stafford, and Dill City NE quadrangle maps, Oklahoma. U. S. Geological Survey, 7.5 minute topographic map series, 1983, downloaded from Maptech Terrain Navigator Pro software, version 5.04.
- 18. Communication Reference. Drinking water system for Clinton, Oklahoma. From: Alvin Knauf, Public Works Director, City of Clinton, Oklahoma. To: Kent Curtis, Environmental Specialist II, Cherokee Nation's Office of Environmental Services, June 18, 2003.
- 19. U. S. Environmental Protection Agency. <u>Hazard Ranking System Guidance Manual</u>, Interim Final. Publication 9345.1-07; PB92-963377; EPA 540-R-92-026, November, 1992.
- 20. U. S. Fish and Wildlife Service Wetlands Inventory maps; Bessie and Clinton 7.5 minute quadrangle maps, 1989.
- Oklahoma Biological Survey, Oklahoma Natural Heritage Inventory. <u>Federal and State Endangered</u>, Threatened, and Candidate Species in Oklahoma by County. May 5, 2003.
- 22. Aerial photo, U. S. Geological Survey digital orthophoto quads, circa 1996, from Oklahoma Corporation Commission aerial photo database and from Oklahoma GIS Council database.
- 23. 2000 Census data for Custer and Washita Counties, Oklahoma. U. S. Census Bureau website, www.census.gov.
- 24. Oklahoma State Department of Health. <u>Preliminary Assessment [of] Ray Wichert Property, Clinton, Oklahoma</u>. July 29, 1992.
- 25. Memorandum. Radium contamination on Ray Wichert Property in Clinton, Oklahoma. From: Robert L. Craig, Director, Radiation Protection Division, Oklahoma State Department of Health. To: Dale McHard, Chief, Radiation and Special Hazards Service, Oklahoma State Department of Health, April 23, 1986.
- 26. Oklahoma Corporation Commission, Petroleum Storage Tank Division. Closure report for underground storage tanks at Facility #2014103 [Ray Wichert Property] at 1401 Industrial Road in Clinton, Oklahoma, dated March 25, 1999.
- 27. Memorandum. Radiation survey of Sooner Dial. From: Paul H. Brown, Director, Radiation Protection Division, Oklahoma State Department of Health. To: H. A. Caves, Chief, Consumer Protection Service, Oklahoma State Department of Health, June 29, 1990.

REFERENCES FOR RAY WICHERT PROPERTY SI PRE-SCORE PACKAGE

- 28. U. S. Environmental Protection Agency, Region 6, Human Health Medium-Specific Screening Levels for contaminants in soil and other environmental media, July 12, 1999, including EPA and Nuclear Regulatory Commission risk-based screening levels for radionuclides in soil (from EPA/NRC Memorandum of Understanding).
- 29. Alloway, B. J., editor. <u>Heavy Metals In Soils</u>. John Wiley & Sons, New York, 1990, xiii + 339 pages.
- 30. Shacklette, Hansford T., and Boerngen, Josephine G. <u>Element Concentrations in Soils and Other Surficial Materials of the Conterminous United States</u>. U. S. Geological Survey Professional Paper 1270; 1984.
- 31. Verschueren, Karel. <u>Handbook of Environmental Data on Organic Chemicals</u>, Second Edition. Van Nostrand Reinhold, New York, 1983, vi + 1310 pages.
- 32. U. S. Environmental Protection Agency and U. S. Department of Commerce, Bureau of the Census. <u>LandView III Environmental Mapping Software</u>. CD-TGR95-LV3-6, December, 1997.

REFERENCE 1

12-14-90 Vol. 55 No. 241



Friday December 14, 1990

Book 2

HRS Rules

United States Government Printing Office SUPERINTENDENT


SUPERINTENDENT OF DOCUMENTS Washington, DC 20402

OFFICIAL BUSINESS Penalty for private use, \$300

SECOND CLASS NEWSPAPER

Postage and Fees Paid U.S. Government Printing Office (ISSN 0097-6326)

REFERENCE 2



REFERENCE 3

Superfund Chemical Data Matrix Database Manager
(Read-Only Version)
June, 1996

NOTE: See enclosed
instructions to install selfextracting file "ro-scdm.exe."

REFERENCE 4



FIELD

All-Weather Notebook No. 351

Ray Wichert Property
Logbook #1

4 5/8" x 7" - 48 Numbered Pages



Name			7.5.
Address			
Phone			
Project	 	 	

Yellow Polyethylene Protective Slipcovers (Item #31) are available for this style of notebook. Helps protect your notebook from wear & tear. Contact your dealer or the J. L. Darling Corporation.

	CONTENTS	
PAGE	REFERENCE	DATE
2	Site Sampling Site Reconnaissance Site Ownership	4/27/00
4	Site Reconnaissance	5/1/03
22	Site Ownership	5/2/03
1		

Ray Wichert Property 4-27-00 Ten Elken willeted Att tur plant # 10 12 pollows FGG65 VOA'S - 8:20 Sumples were collected in Furling lot of Best Wistern Hotel in Clinton, OK. Janon, White and Traver Walde me taking initial unsate sample # 7 as follows: FGG62 VOA'S - 9:10 BNA - 9711 9:12 Pest -TM-9112 Cy- 9/2 Melinda Simo Collected packground soil sample # 6 as follows: VOA'S 9:39 BNA /Pest-9:41 TM/cy - 9:42 Bould

Kay Wuhert Property 4-27-00 Melindu Sins collectico Sort Sample #4 as follows VOA'S - 10:03 BNA/POST - 10:04 TM/Cy - 10:05 Soil is neclum brown in color no odor present Soil is fine of loaning with some clay present. Melinda Sims collected sort sample # 5 as follows VOA'S- 10:10 BNA 18est - 10111 Soil is medium prown in lolor, no odor, and fine mained + loany. Some clay is present in soil. Travis Waldo collected and Rensate QA/QC Sample #8 ar follons: VOA'S-10;23 Pest-10:24 BNA + 10:25 7m-10:25 Cy-10:25 Brud Blell

Ray Wichert Property Rent Curtis 1 May, 2003 Kent Curtis and Paul Choudhury of Cherokee Nation Office of Environmental Services (OES) visited the Play Wichert Property from 1230 hrs. to 1415 hrs. with Damon Danban Ladonna Tall Bears and Calvin Underwood of Cheyenne Arapaho Tribe (Damon, Ladonna) and Indian Health Service [Clinton office] (Calvin). They conducted a reconnaissance of the entire site and observed the tollowing: (1) The Ray Wichert Property is currently abandoned and anoccu-(2) Access to the site is unrestoidely there being no fences on the west, south, and east sides of the property; a fence is located along the extreme northern end of the property (3) The site is rectangular in shape, being approximately 200 ft, wide (east to west) Kent Curtis 5/1/03

Ray Wichert Property Kent Curtis 1 May, 2003 and approximately 1600 ft. (0,3 mile) long (north to south) and approximately 320,000 sq.ft. in area (4) the site is bordered on the west by a railroad and imm old U.S. highway 66 lifes immediately west of this railroad. The site is bordered on the north by livestock pens and a pasture in which cattle were grazing (photo looking N-NE by Rent Curtis) (a private residence stands adjacent to the a livestock pens pasture approximately 200 feet to 250 ft, north of the fence along the north margin of the site The site is bordered on the east and south by active industrial facilities, with at least 8 such facilities located immediately adjacent to the Kent Curto 5/1/03

Ray Wichert Property

Kent Curtis 1 may, 2003

east margin of the site, and with

one such facility located across

Industrial Boulevard on the south

margin of the site.

Industrial Blvd. is a two-lane

street that forms the southern

border of the site

14th Street runs parallet to

the eastern margin of the site,

with active businesses lining both

sides of it, including the 8

facilities that are immediately

adjacent to the east margin of

the site.

(5) A interitted the site of the site.

(5) An intermittent stream forms the entire eastern margin of the site. No water was seen in this stream today (Photo by Kent Curtis, looking south). Water in this intermittent stream flows northward.

(6) Topography of the site:
The southern portion of the site—an area approximately

Kant Curtis 5/1/03

Kent Curtis 1 may, 2003 200ft, x 250ft in size is high, level ground. The railroad embankment on the western margin of the site is also high ground, Most of the site is a fairly level basin, with the railroad embankment sloping down into it on the west and with the southern end of the basin rising steeply to the high, level ground on the south end of the site, The eastern margin of the basin drops steeply into the intermittent stream bed. The northern margin of the basin rises gently to the pasture that borders the northern end of the site, (7) Vegetation on the site: Vegetation is thickest on the eastern and western margins of the site, where trees line the railroad embankment and where

Kent Curtis 5/1/03

Ray Wichert Property Kent Curtis 1 May, 2003 forest lines the intermittent stream tranks, Grass, brush, and patches of bare ground fill the basin of

the sife, The high, level ground on the southern end of the site is unvegetated, consisting of concrete and gravel. Vegetation on the site appears to be normal unstressed except for some dead trees along the railroad embankment,

(8) Wildlife on site: A live rabbit was seen on site. A dead rabbit was lying next to one of the USTs on site.

(1) The surface rock on the site is a reddish sandstone, and the soil is a reddish-brown, sandy loam,

(10) Buildings on site! Two a vacant buildings are located on the high, Tevel ground Kont Curta 5/1/03

Ray Wichert Property Kent Curtis 1 May, 2003 at the southern end of the site. The southernmost building is a large building that appears to contain offices and warehouse or garage space; large doors, capable of admitting trucks, are present on the Building, and a grease trap is present in the concrete pad outside the large door on the north side of the building; a sign on the south side of this building says that the property is for sale by the Oklahoma Bank and Trust Company of Clinton, Okla, The northermost of the two buildings is a car wash, with a roof and open stalls. A fuel dispenser island is located on a concrete pad between the car wash stalls and the southernmost building. Three dispensers had been present on this island, but these Kent Curtis 5/1/03

Ray Wichert Property Kunt Curtis 1 May, 2003 motor fuel dispensers have been removed. Kent and Paul did not see vents or filler ports for underground storage tanks on the concrete pad or among the gravel that covers the ground around the dispenser island and the two buildings. It appears that the USTs have been removed from the ground, Rust-colored scars on the concrete pad around the dispenser island (photo by Kent, looking NW) suggest that the USTs were dragged across it when they were removed from the groundi Photos by Rent Curtis (looking south, SW, NW, and north) show the two buildings and the motor tirel dispenser island.

(11) Wastes 'lying on ground surface of site: No stains of petroleum hydrocarbons Kont Curtis 5/1/03

Ray Wichert Property Kent Curtis 1 May, 2003 were seen on the concrete pad or gravel around the buildings or fuel dispenser island, but oily liquid was present in the grease trap on the north side of the southern most building. Four underground storage tanks (USTs), and three the piping for those tanks, and three fuel dispensers were seen lying in the southern end of the basin on site, just north of the two buildings at the southern end of the site. It appears that the USTS, UST piping, and fuel dispensers removed from the southern end of the site were dumped on the ground in the basin on the site rather than being disposed of properly. Three of the USTs are large, being approximately 6ft, in diameter by 20ft, in length; the fourth UST is smaller -

Kent Curtus 5/1/03

Ray Wichert Property Kent Curtis 1 may, 2003 perhaps half the size of the other three USTs, All four USTs are completely rusted, and no labels, engravings, or other markings are visible on them to identify their age, construction, contents, or ownership. At least half of the openings for piping on each UST are open, while the other half of the openings are plugged. Small holes are present on each UST - usually at seams on the ends of the tanks - showing that corresion has eaten completely through each tank, but it could not be determined if the corrosion opened these holes while the tanks were still in the ground, There was no odor of petroleum hydrocarbons around the tanks, and no hydrocarbon stains were seen on the soil around the tanks. No attempt Kent Curtu 5/1/03

Ray Wichert Property Kent Curtis 1 May, 2003 was made to determine if petroleum hydrocarbons were still present in these tanks, either in liquid or vapor form. The underground piping for these tanks was lying on the ground, immediately north of The four USTs, Photos by Kent Curtis (looking in all directions) show these USTs and their Piping, Three fuel dispensers were lying on the ground surface, just south of the four USTs (photo by Kent Chrttis, looking north). Metal poles and signs, including two Texaco signs, were lying on the ground near the favel dispensers and USTs (photo by Rent Curtis looking Niw). (12) Wastes lying on ground surface of site (continued): Adilapidated fence divides the basi topographic basin of the site Kent Curtis 5/1/03

Ray Wichert Property Kent Curtis 1 May, 2003 into north and south halves. Most of the solid waste lying on the ground surface of the site is Tocated in the north half of the topographic basin (north half of site). These solid wastes consist of scattered waste piles that consist almost entirely of construction debris (bricks, concrete, as phalt, and minor amounts of scrap lumber and scrap metal); traces of linoleum on flat slabs of concrete. are the remains of interior floors of a building; one slab of concrete bears the date "10-17-27"; shingles indicate fragments of root; fragments of brick walls, concrete floors, and cinder block foundations are abundant. Only a few buckets and other containers are present among the waste piles; one container appeared to have been for Kant Curtis 5/1/03

Ray Wichert Property Kent Curtis 1 may, 2003 lubricating oil. Some of these solid wastes are lying in the bed of the intermittent stream on the eastern margin of the site (photos by Kent) There were no stains on the soil around these solid waste piles, The approximate surface area covered by these numerous scattered waste piles was not estimated. Photos by Kent Curtis (looking in various directions) show these waste piles. (13) Radioactive screening survey of site! Rent Curtis used a Ludlum Model 3A Survey Meter with a Ludlum model 44-9 pancake-type gamma ray detector to screen the surface soil and solid waste piles in the topographic basin of the site for radioactivity. Kent Curtis 5/1/03


Ray Wichert Property Kent Curtis 1 May, 2003 ground level on site. These high levels of radioactivity suggest that the construction debris in this waste pile may have come from the Sooner Dial site in Clinton, Oklahomai (14) Human, tribal, & other targets in vicinity of Ray Wichert Property: Nearest residents to site: 9 occupied homes lie on the west side of old U.S. highway 66, immediately west, and within 200 ft, to 250 ft, of the site; another occupied home stands within 250 ft. of the northern margin of the site none of these 10 residences appears to have a private drinking water well, as determined from a windshield survey. Schools and daycares; No schools or daycare facilities were seen within 200 ft, of Kent Curtis 5/2/03

Ray Wichert Property Kent Curtis 1 may, 2003 the site. However, a school of gymnastics - Olympic Gold Gymnastics - was located af 1391 South 14th Street (at the northern end of 14th Street), approximately 250 ft. from the northeastern corner of the site. The parking lot of Olympic Gold Gymnastics is immediately adjacent to the northeastern corner of the site, and a jeep trail leads into the northern end of the site from this parking lot. [Numerous young children were seen taking gymnastics classes inside The Olympic Gold Gymnastics building after 1700 hrs. today.] Workers on or near site; The Ray Wichert Property is currently unoccupied, so there are no workers on the site itself. However, there are Kent Curtis 5/1/03

Ray Wichert Property Kent Curtis 1 May, 2003 numerous active businesses on all sides of the site! 9 businesses are located immediately adjacent to the east margin of the site 2 businesses are located immediately south and SE of the site; several businesses are located on the west side of old U.S. highway 66, within 200ft. to 250 ft. of the northwestern corner of the site; and a Howard Johnson's Motor Lodge is located approximately 400 ft, north of the site. The number of workers — and motel guests at these businesses is unknown. Tribal tamets: Four Indian homes are located just east of John Old Crow Cemetery, just under one mile east of the Ray Wichert Property; these homes are occupied but do not Kent Curtis 5/1/03

While conducting reconnaissance of the Ray Wichert Property today, Ladonna Tall Bear (Cheyenne Arapaho Tribe) used a handheld Global Positioning System (GPS) unit to map the perimeter and other features of the site. She will provide the GPS coordinates of the site to the OES.

Ront 5/2/03



Ray Wichert Property Kent Curtis 2 May, 2003

the southernmost and central parcels of land, and the USTs, piping, and dispensers lie on these parcels of the land. The northernmost parcel of land, on which the waste piles are located, is approximately 5 acres in size and is currently owned, as it appears to have been since at least 1980, by Earl Glen Smith. The dilapidated fence seen on the property appears to mark the boundary between the northernmost and central parcels of land.

Northernmost parcel is probably 2 to 3 acres in size, as total area of northernmost, central, & southernmost parcels combined is approximately 5 to 6 acres, (C)

Rev 5/2/03

Ray Wichert Property Kent Curtis 2 May, 2003 Kent Curtis and Paul Choudhung of OES checked property records in the Custer County Courthouse in Arapaho and found the following: The site that is referred to as the "Ray Wichert Property" actually consists of 3 parcels of land. The southernmost parcel is approximately 2 acres in size, being 160ft, (east-west) by 541ft, (north-south) in dimensions. This southernmost parcel was acquired from Earl G. Smith on Jan. 30, 1980 by Ervin Wichert, and Ray Wichert subsequently acquired the parcel from Ervin Wichert The central parcel of land is approximately 0.88 acre in size (approx, 160 ft, x 231ft) and was acquired from Earl G, Smith On Jan. 5, 1981 by Ray Wichert. Oklahoma Bank and Trust Co. is the current owner of the both Kent Curtin 5/2/03

REFERENCE 5

REFERENCE 6



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 6 HOUSTON BRANCH 10625 FALLSTONE RD. HOUSTON, TEXAS 77099

MEMORANDUM

	·
Date:	June 16, 2000
_	Contract Laboratory Program Data Review
From:	Marvelyn Humphrey, Alternate ESAT RPO, 6MD-Ho
To:	J. Enders, 6SF-RA
Site	: RAY WICHERT PROPERTY
Case#	: 28007
SDG#	: MFJK50

The EPA Region 6 Houston Branch ESAT data review team has completed a review of the submitted Contract Laboratory Program (CLP) data package for the referenced site. The samples analyzed and reviewed are detailed in the attached Regional data review report.

The data package is acceptable for regional use. Problems, if any, are listed in the report narrative.

If you have any questions regarding the data review report, please call me at (281) 983-2140.

Attachments

cc: R. Flores, Region 6 CLP/TPO
 M. El-Feky, Region 6 Data Coordinator
 Files (2)

LOCKHEED MARTIN SERVICES GROUP ESAT REGION VI 10101 SOUTHWEST FREEWAY, SUITE 500 HOUSTON, TEXAS 77074

MEMORANDUM

DATE: June 14, 2000

TO: Melvin Ritter/Marvelyn Humphrey, ESAT RPO/Alternate

RPO, Region VI

FROM: Tom Chiang, ESAT Team Manager, Region VI

SUBJECT: CLP Data Review

REF: TDF #6-0376A ESAT File No. I2429

ESAT Contract No. 68-D6-0005

Attached is the data review summary for Case # 28007

SDG # MFJK50

Site Ray Wichert Property

COMMENTS:

I. CONTRACTUAL ASSESSMENT OF DATA PACKAGE:

Hard copy review could not confirm the noncompliant items noted by CCS but detected the following contractually noncompliant item.

The laboratory analyzed the continuing calibration verification (CCV) standards for antimony at the same concentration as the initial calibration verification (ICV) standard. The SOW requires the analyte concentrations in the CCV to be different than the concentration used for the ICV (ILM04.0, Exhibit E, E-17, b). The sample results were not technically affected because other QC analyses such as the ICSAB with different concentrations from the ICV provided the missing QC information.

II. TECHNICAL/USABILITY ASSESSMENT OF DATA PACKAGE:

A total of 144 results were reviewed for this data package. Some results have been qualified because of technical problems. The significant problems are addressed below.

- A. Blank concentrations affected some arsenic, beryllium, cadmium, selenium, and thallium results.
- B. The antimony and selenium matrix spike recoveries were below the QC limits.
- C. Replicate instrument readings were inconsistent for one selenium analysis.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 6

HOUSTON BRANCH 10625 FALLSTONE ROAD HOUSTON, TEXAS 77099

INORGANIC REGIONAL DATA ASSESSMENT

CASE NO. 28007 LABORATORY LIBRTY CONTRACT# 68-W0-0082 SDG# MFJK50 SOW# ILM04.1 ACCT# 050102DJN70 SF# 50102DZ	SITE Ray Wichert Property NO. OF SAMPLES 6 MATRIX Soil REVIEWER (IF NOT ESD) ESAT REVIEWER'S NAME L. Hoffman Z COMPLETION DATE June 14, 2000
SAMPLE NO. MFJ-K50 MFJ-MFJ-K51 MFJ-MFJ-K52 MFJ-K53 DATA ASS	
IC	P HG CYANIDE
1. HOLDING TIMES O 2. CALIBRATIONS O 3. BLANKS M 4. MATRIX SPIKES M 5. DUPLICATE ANALYSIS M 6. ICP QC M	
7. FAA QC 8. LCS O 9. SAMPLE VERIFICATION O 10. OTHER QC M 11. OVERALL ASSESSMENT M	

O = Data had no problems.

M = Data qualified because of major or minor problems.

Z = Data unacceptable.

N/A= Not applicable

ACTION ITEMS:

AREAS OF CONCERN: The laboratory failed to analyze the antimony CCV's at contract-required concentrations. Laboratory blank concentrations affected some arsenic, beryllium, cadmium, selenium, and thallium results. The antimony and selenium matrix spike recoveries were below 75 percent. The calcium laboratory duplicate relative percent difference (RPD) was above 35 percent. The copper and potassium serial dilution differences were above 10 percent. One selenium analysis had a coefficient of variation greater than 20 percent. The calcium field duplicate RPD was greater than 80 percent.

NOTABLE PERFORMANCE: The laboratory submitted the data package four calendar days early.

COMMENTS/CLARIFICATIONS REGION 6 CLP QA REVIEW

Case 28007 SDG MFJK50 Site Ray Wichert Property Lab LIBRTY

COMMENTS: The SDG consisted of six soil samples for total metals and cyanide analyses by ILM04.1. The sampler designated sample MFJ-K50 as the QC sample and the field duplicate of sample MFJ-K51. The laboratory met the 21-day data package turnaround time requirement. The reviewer noted the following contractually noncompliant item.

The CCV concentrations for antimony were not contractually compliant.

Fifty-eight percent of the reported results were above the CRDL's. Some results were qualified because of problems with laboratory blank concentrations, matrix spike recoveries, laboratory and field duplicate differences, serial dilution differences, and replicate instrument readings. The technical usability of all reported results is indicated in the Data Summary Table (DST). An Evidence Audit was conducted for the Complete Sample Delivery Group File (CSF), and the results were recorded in the Evidence Inventory Checklist.

NOTE: THE FOLLOWING REVIEW NARRATIVE ADDRESSES BOTH CONTRACTUAL ISSUES (BASED ON THE STATEMENT OF WORK) AND TECHNICAL ISSUES (BASED ON THE NATIONAL FUNCTIONAL GUIDELINES). THE ASSESSMENT MADE FOR EACH QC PARAMETER IS SOLELY BASED ON THE TECHNICAL DATA USABILITY, WHICH MAY NOT NECESSARILY BE AFFECTED BY CONTRACTUAL PROBLEMS. THE ASSESSMENTS ARE DEFINED BELOW.

Acceptable = No results were qualified for any problems

associated with this QC parameter.

Provisional = Some results were qualified because of problems

associated with this QC parameter.

Unusable = All results are unusable because of major problems associated with this QC parameter.

- 1. Holding Times: Acceptable. All samples met contractual holding time criteria. Technical holding time criteria have not yet been established for soil samples. Sample preservation was acceptable.
- 2. Calibrations: Acceptable. All calibrations met contractual requirements. The CRDL standard recoveries indicated acceptable instrument performance near the CRDL's.
- 3. Blanks: Provisional. Preparation and calibration blanks met contractual requirements although the laboratory reported 18 analytes in the blanks. The reviewer qualified the arsenic result for sample MFJ-K53 as estimated and biased high and the following results as undetected because of laboratory blank concentrations:

the arsenic results for all samples except MFJ-K53;

Case 28007 SDG MFJK50 Site Ray Wichert Property Lab LIBRTY

3. Blanks, continued:

the beryllium results for samples MFJ-K50, MFJ-K52, and MFJ-K54:

the cadmium results for samples MFJ-K50, MFJ-K51, MFJ-K53, and MFJ-K55; and

all detected selenium and thallium results.

- 4. Pre-digestion/Pre-distillation Matrix Spike Recovery:
 Provisional. The reviewer qualified the antimony and
 selenium results as estimated and biased low because the
 associated matrix spike recoveries were below the QC limits.
- 5. **Duplicate Analysis:** Provisional. The reviewer qualified the calcium results as estimated because the calcium RPD was above the QC limit.

6. ICP Quality Control:

<u>Serial Dilution:</u> Provisional. The laboratory reported outlying serial dilution differences for copper and potassium, so the reviewer qualified as estimated the copper and potassium results. The serial dilution results were lower than the undiluted results, indicating that matrix interferences enhanced the signals for these analytes. Therefore, the reviewer also qualified the copper and potassium results as high biased.

<u>Interference Check Sample (ICS):</u> Acceptable. The reported ICS results indicated satisfactory interelement and background corrections.

<u>Coefficient of Variation:</u> Provisional. The reviewer qualified as estimated the selenium result for sample MFJ-K53 because replicate instrument readings were inconsistent.

- 7. Furnace Atomic Absorption Quality Control: Not Applicable.
- 8. Laboratory Control Sample (LCS): Acceptable. The laboratory reported acceptable LCS recoveries, indicating satisfactory sample preparation and analysis.
- 9. Sample Verification: Acceptable. The reviewer detected a few reporting errors that did not affect sample results. The laboratory was contacted for corrections (see FAX Record Log).

Case 28007 SDG MFJK50 Site Ray Wichert Property Lab LIBRTY

10. Other QC:

<u>Field Duplicates:</u> Provisional. The reviewer qualified the calcium results as estimated because of inconsistent field duplicate results.

11. Overall Assessment: Sample result qualifications are summarized below.

The reviewer qualified six arsenic, three beryllium, four cadmium, four selenium, and two thallium results because of laboratory blank effects.

The reviewer qualified all antimony, copper, potassium, and selenium results because of matrix related problems.

The reviewer qualified the calcium results because of poor laboratory and field precision.

The reviewer qualified one selenium result because of inconsistent instrument readings.

INORGANIC DATA QUALIFIER DEFINITIONS

The following definitions provide brief explanations of the ESAT-Region 6 qualifiers assigned to results in the inorganic data review process.

- Undetected at the laboratory reported detection limit (IDL).
- L Reported concentration is between the IDL and the CRDL.
- J Result is estimated because of outlying quality control parameters such as matrix spike, serial dilution, FAA spike recovery, etc.
- R Result is unusable.
- F A possibility of a false negative exists.
- UC Reported concentration should be used as a raised detection limit because of apparent blank contamination.
- ^ High bias. Actual concentration may be lower than the concentration reported.
- v Low bias. Actual concentration may be higher than the concentration reported.

INORGANIC DATA SUMMARY

Case No.:

28007

SDG:

MFJK50

Reviewer: L. Hoffman

Laboratory:

LIBRTY

Matrix:

Soil

Units:

mg/Kg

	FLAG	FLAG	FLAG	FLAG	FLAG	FLAG	FLAG
EPA Sample #=>	MFJ-K50	MFJ-K51	MFJ-K52	MFJ-K53	MFJ-K54	MFJ-K55	
•							
ALUMINUM	200	13400	7300	16600	7940	13400	
ANTIMONY	0.51 U.Jv	0.51 U Jv	4.2 LJv	0.53 U Jv	0.45 UJv	0.52 U Jv	
ARSENIC	3.2_UC	* * 1.1 UC.	2.6UC:-	4.7 10		3.4 ŪC2	
BARIUM	194	225	660	174	251	266	
BERYLLIUM	0:70 LUC	الـا 0.77	0:49_LÜC	البا 97!0:	0.52 LUC	20.82° ليا °0.82°	
CADMIUM	0.20 LUC	0.50 LUC	0.67 LJ^	0.22 LUC	3.3	0.25 LUC	
CĂLCIÚM	78000_J	27800 J	<u>3.</u> 88600 <u>.</u> J <u>.</u>	26400 J	<u> </u>	18000 J	
CHROMIUM	12.9	14.6	12.1	16.2	13.2	15.9	
COBALT	<u>1978</u> , 5:0 ° L	5:7-L	3.5; L C	6.5 L	3.6 ₺	2 6.0 ± L → 5	
COPPER	11.4 J^	12.8 J^	8.4 J^	15.0 J^	9.8 J^	16.4 J^	ation a representative property property of
IRON 1	11200	12600	7050	15100 ° V	7790	13000	
LEAD	27.0	36.1	41.6	15.7	49.9	48.1	· M der Williamsterner gegit IV Merste Wester et
MAGNESIUM	17900	19000	32100	19400	7750	16200	
MANGANESE	288	322	192	350	196	366	
MERCURY	0.076 L		0.096 <u>}</u> L 345	0.058 L	0.18	0.064 L	
NICKEL	12.5	13.5	8.5 L	16.2	8.8	15.5	- W
POTASSIUM	2340 JA	2500 J^*.		2940_J^	<u>1550.</u> J <u>↑</u>	3150 J^ W	
SELENIUM	0.75 LUCJv	0.77 LUCJv	0.48 U Jv	0.97 LUCJv	0.49 LUCJv	0.55 UJv	
SILVER.	°5.0.15.U.	0.14 U	ີ່ 0.13.ປ	<u></u>	<u>้ 0.13 ป</u>		
SODIUM	238 LJv	169 LJv	180 LJv	144 LJv	129 LJv	150 LJv	- **!**********************************
THALLIUM:	. 0.80 LUC	0.78 U	<u> </u>	0.97, LUC		. 😂 0.80, U	
VANADIUM	20.9	23.5	14.2	28.2	15.6	22.6	
ZINC	70.0	رُيْنِ 134 يَنْ حِيْنَ	69,1	<u>. 26€</u> 89.8	106.	80.4	
CYANIDE	0.080 L	0.066 L	0.072 L	0.081 L	0.051 U	0,14 L	
<u>% Solids :</u>	82.0	81.6	85.0	79.0	88.4	77.0	

Case No. :	28007		SDG: MFJK	50		Reviewer : L. Hoffman
l abaretan.		Dup. I				background
Laboratory :	LIBRTY	# 2	Matrix: Soil	# 7	#5	Units: mg/Kg H (p
	FLAG	FLAG	FLAG	FLAG	FLAG	1
EPA Sample #=>	MFJ-K50	MFJ-K51	MFJ-K52	MFJ-K53	MFJ-K54	MFJ-K55
	119 0				a contract to the contract of the	and the second of the second o
ALUMINUM	12100 48 3 0.51 U Jv }4	13400 48	7300T.	16600 56	7940 42	7 13400 50.0
ARSENIC	3.2 UC 2	4.1 UC	0 4 26 UC	2.2 (4.7 JA)	0.45 UJV	2.8 0.52 UJV 15.0
BARIUM	194 48	225		4.0 174 50		\ ~
BERYLLIUM	0.70 LUC	$\hat{\mathbf{a}}$ 0.77 L/ $\hat{\mathbf{J}}$. 2 0.49 LUC		1.3 0.52 LUC	7. / 266 SU.D 1.1 0.82 LI ² 1.2
CADMIUM	0.20 LUC)	2 0.50 LUC	.2 0.67 LJ^	1.1 0.22 LUC	1.3 3.3 1.	1 0.25 LUC 1. 2
CALCIUM	78000 J 12		The second secon	00 26400 J /2		167 ₁₈₀₀₀ J 1249
CHROMIUM	12.9	14.6 2.		2 16.2 J.	5 _{13.2} 2.	1 15.9 2.5
COBALT	5.0 L /a	. 2 ≤5.7 L 12	.] _13.5 L ∱	∮ 0 6.5 L]	S 36 L 1	The same of the sa
COPPER	11.4 J^ 6	. 1 12.8 Jr 'e	8.4 JA	5.5 15.0 JA	·3 9.8 m	5.3 16.4 Jr 6.2
IRON	11200	12600	ろ _7050_ <i>】。</i>	0 15100	7790 2	3 13000 25 O
LEAD	27.0 0.7	their Ministration of the section of the galaxy	73 41.6 0.1	o b 15.7 0,	75 49.9 0,	64 48.1 0.75
MAGNESIUM	17900 22	19000 2	3 _32100_≟√1	19400	7750 📆 🖸	6 16200 1 2 4 1
MANGANESE	288 3.	322 ડ	ک 192 ک	. 3 350 3.	8 196 3	366 3,7
MERCURY	0.076 L 0.1		1. 0.096 L	4	1 0.18 D	
NICKEL POTASSIUM	12.5 7.8	13.5 7.	7 8.5 L X	8 16.2 /0	.0 8.8 X	5 15.5 0.0
SELENIUM	0.75 LUCJv	2500 J	1.⊋ 0.48 U Jv		1.3 0.49 LUCJV	0 6 3150 JA 1 4 4
SILVER	0.15 U 2	J-0.14 U - 2	and your an individual contraction of the distribution of	0.97 EUCJV	.5 0.13 U 2	0.15 UJV 1. 2
SODIUM		220 169 LJv /		100 144 LJV 1		
THALLIUM	, chan't take district the time of themselves	and and the control of the local control of the first of the control of the contr	a demand a restriction of a local series of a 17 of 19 miles	. 0.97 LUC		0.80 U
VANADIUM	20.9 12.	2 23.5	1 14.2 11.	0 28.2 12	. \$ 15.6 10	7 22.6 12.5
ZINC	70.0 Y .	9 134 4.	9 69.1 4	. 4 89.8 5	<u>0</u> 106 4	.3 80.4 5.0
CYANIDE	0.080 L C.	0 0.066 L O.	6/ 0.072 L C.	59 0.081 L D.	0.051 U 5	.57 0.14 L D. 65
% Solids :	82.0	81.6	85.0	79.0	88.4	77.0
	02.0					
7	t s	1.01	1.07	1.01	1.06	1.04
,		22	O 04	0.24	6.26	6.27
cJ	s 30	•33	$O \cdot J^{\circ}$			
C		(C	10	10	(0	1.0
(6	. 0	(,)	1.0	' `		

greenic less than action level of 50 mg/kg, but

arsenic exceeds residential findustrial cancer risk

no other hits (Cd, Ca, Hg) exceed EPAG Human Health Medium-Specific Screening Levels

Page 7 of 11

INORGANIC/ORGANIC COMPLETE SDG FILE (CSF) INVENTORY CHECKLIST

Case No. 28007 SDG No. MFJK50 SDG Nos. To Follo	sas No.	Date R	ec <u>05/</u>	15/00
EPA Lab ID: LIBRTY	ORIGINALS	YES	NO	N/A
Lab Location: Cary, NC	CUSTODY SEALS			
Region: 6 Audit No.: 28007/MFJK50	Present on package?	x		
Re_Submitted CSF? Yes No X	2. Intact upon receipt?	X		
Box No(s):	FORM DC-2			
COMMENTS:	3. Numbering scheme accurate?	X		
4. The laboratory did not record the sample tags on Form DC-2	4. Are enclosed documents listed?		х	
and was notified about this omission.	5. Are listed documents enclosed?	Х		
	FORM DC-1			
	6. Present?	х		
	7. Complete?	X		
	8. Accurate?	X		
	CHAIN-OF-CUSTODY RECORD(s)			
	9. Signed?	_x		
	10. Dated?	x		
	TRAFFIC REPORT(s) PACKING LIST(s)			
	11. Signed?	x		
	12. Dated?	X		
	AIRBILLS/AIRBILL STICKER			
	13. Present?	x		1
	14. Signed?	1		х
	15. Dated?			X
•	SAMPLE TAGS			 ^
	16. Does DC-1 list tags as being included?	x		
	17. Present?	X		-
	OTHER DOCUMENTS	^		
	18. Complete?	l x		
	19. Legible?	X		+
	20. Original?		X	+
	20a.If "NO", does the copy indicate	X		
Over for additional comments.	where original documents are located?	1		
Audited by:	Linda Hoffman / ESAT Data Reviewer	Date	06/13	/00
Audited by:		Date		
Audited by:		Date		
Signature	Printed Name/Title			
TO RE CON	MPLETED BY CEAT	,		
	Date Entered: Date Reviewed:			
Entered by:				
Reviewed by:				
Signature	Printed Name/Title			
- Signature	111110011111111			

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 6 HOUSTON BRANCH 10625 FALLSTONE RD. HOUSTON, TEXAS 77099

MEMORANDUM

Date:	June 16, 2000
	Contract Laboratory Program Data Review
From:	Marvelyn (Humphrey, Alternate ESAT RPO, 6MD-HC
To:	J. Enders, 6SF-RA
Site	: RAY WICHERT PROPERTY
Case	#: <u>28007</u>
SDG#	: MFJK56

The EPA Region 6 Houston Branch ESAT data review team has completed a review of the submitted Contract Laboratory Program (CLP) data package for the referenced site. The samples analyzed and reviewed are detailed in the attached Regional data review report.

The data package is acceptable for regional use. Problems, if any, are listed in the report narrative.

If you have any questions regarding the data review report, please call me at (281) 983-2140.

Attachments

cc: R. Flores, Region 6 CLP/TPO
 M. El-Feky, Region 6 Data Coordinator
 Files (2)

LOCKHEED MARTIN SERVICES GROUP ESAT REGION VI 10101 SOUTHWEST FREEWAY, SUITE 500 HOUSTON, TEXAS 77074

MEMORANDUM

DATE:

June 13, 2000

TO:

Melvin Ritter/Marvelyn Humphrey, ESAT RPO/Alternate

RPO, Region VI n

FROM:

Tom Chiang, ESAT Team Manager, Region V.

SUBJECT:

CLP Data Review

REF:

TDF #6-0374A

ESAT File No. I2430

ESAT Contract No. 68-D6-0005

Attached is the data review summary for Case #__

SDG # MFJK56

Site Ray Wichert Property

28007

COMMENTS:

I. CONTRACTUAL ASSESSMENT OF DATA PACKAGE:

Hard copy review could not confirm the noncompliant items noted by CCS but detected the following contractually noncompliant item.

The laboratory analyzed the continuing calibration verification (CCV) standards for antimony at the same concentration as the initial calibration verification (ICV) standard. The SOW requires the analyte concentrations in the CCV to be different than the concentration used for the ICV (ILM04.0, Exhibit E, E-17, b). The sample results were not technically affected because other QC analyses such as the ICSAB with different concentrations from the ICV provided the missing QC information.

II. TECHNICAL/USABILITY ASSESSMENT OF DATA PACKAGE:

A total of 72 results were reviewed for this data package. Some results have been qualified because of technical problems. The significant problems are addressed below.

- A. The mercury CRDL standard recovery was high.
- B. Blank concentrations affected some antimony, arsenic, beryllium, cadmium, and thallium results.
- C. Replicate instrument readings were inconsistent for one selenium analysis.

LOCKHEED MARTIN SERVICES GROUP ESAT REGION VI 10101 SOUTHWEST FREEWAY, SUITE 500 HOUSTON, TEXAS 77074

MEMORANDUM, continued

Attached	is	the	data	review	summarv	for	Case	9	#	28007
1100001100					3		SI)G	#	MFJK56
						S	ite I	Ra	v V	Wichert Property

III. OTHER AREAS OF CONCERN:

The field blank was contaminated with concentrations above the CRDL's for calcium, potassium, and sodium.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY REGION 6

HOUSTON BRANCH 10625 FALLSTONE ROAD HOUSTON, TEXAS 77099

INORGANIC REGIONAL DATA ASSESSMENT

CASE NO. 28007 LABORATORY LIBRTY CONTRACT# 68-W0-0082 SDG# MFJK56 SOW# ILM04.1 ACCT# 050102DJN70 SF# 50102DZ	SITE Ray Wichert Property NO. OF SAMPLES 3 MATRIX Water REVIEWER (IF NOT ESD) ESAT REVIEWER'S NAME L. Hoffman COMPLETION DATE June 13, 2000				
SAMPLE NO. MFJ-K56 MFJ-K57 MFJ-K58					
DATA ASS	ESSMENT SUMMARY				
IC	P HG CYANIDE				
1. HOLDING TIMES 2. CALIBRATIONS 3. BLANKS 4. MATRIX SPIKES 5. DUPLICATE ANALYSIS 6. ICP QC PAGE 100	<u>'A N/A N/A</u>				
7. FAA QC 8. LCS	O O O N/A				

- O = Data had no problems.
- M = Data qualified because of major or minor problems.
- Z = Data unacceptable.
- N/A= Not applicable

ACTION ITEMS:

AREAS OF CONCERN: The laboratory failed to analyze the antimony CCV's at contract-required concentrations. The mercury CRDL standard recovery was 150 percent. Laboratory blank concentrations affected some aluminum, antimony, arsenic, beryllium, cadmium, thallium, vanadium, and zinc results. One selenium analysis had a coefficient of variation greater than 20 percent.

NOTABLE PERFORMANCE: The laboratory submitted the data package eight calendar days early.

COMMENTS/CLARIFICATIONS REGION 6 CLP QA REVIEW

Case 28007 SDG MFJK56 Site Ray Wichert Property Lab LIBRTY

COMMENTS: The SDG consisted of two rinsates, samples MFJ-K56 and MFJ-K57, and a field blank, sample MFJ-K58, for total metals and cyanide analyses by ILM04.1. Since the samples in this SDG were field QC samples, QC analyses were not required. The laboratory met the 21-day data package turnaround time requirement. The reviewer noted the following contractually noncompliant item.

• The CCV concentrations for antimony were not contractually compliant.

Fourteen percent of the reported results were above the CRDL's. Some results were qualified because of problems with instrument performance near the CRDL, laboratory blank concentrations, and replicate instrument readings. The technical usability of all reported results is indicated in the Data Summary Table (DST). An Evidence Audit was conducted for the Complete Sample Delivery Group File (CSF), and the results were recorded in the Evidence Inventory Checklist.

NOTE: THE FOLLOWING REVIEW NARRATIVE ADDRESSES BOTH CONTRACTUAL ISSUES (BASED ON THE STATEMENT OF WORK) AND TECHNICAL ISSUES (BASED ON THE NATIONAL FUNCTIONAL GUIDELINES). THE ASSESSMENT MADE FOR EACH QC PARAMETER IS SOLELY BASED ON THE TECHNICAL DATA USABILITY, WHICH MAY NOT NECESSARILY BE AFFECTED BY CONTRACTUAL PROBLEMS. THE ASSESSMENTS ARE DEFINED BELOW.

- Acceptable = No results were qualified for any problems associated with this QC parameter.
- Provisional = Some results were qualified because of problems associated with this QC parameter.
- Unusable = All results are unusable because of major problems associated with this QC parameter.
- 1. Holding Times: Acceptable. All samples met contractual and technical holding time criteria. Sample preservation was acceptable.
- 2. Calibrations: Provisional. All calibrations met contractual requirements. However, the laboratory reported a high mercury CRDL standard recovery (150%), which indicated poor instrument performance near the mercury CRDL. Therefore, the reviewer qualified the detected mercury result as estimated and biased high.
- 3. Blanks: Provisional. Preparation and calibration blanks met contractual requirements although the laboratory reported 17 analytes in the blanks. The reviewer qualified

Case 28007 SDG MFJK56 Site Ray Wichert Property Lab LIBRTY

3. Blanks, continued: zinc result for sample MFJ-K57 as estimated and biased low and the following results as undetected because of laboratory blank concentrations:

all aluminum, beryllium, and cadmium results;

the antimony and arsenic results for sample MFJ-K58;

the thallium results for samples MFJ-K57 and MFJ-K58; and

the vanadium result for sample MFJ-K57.

Field Blank: The laboratory reported concentrations of aluminum, antimony, arsenic, beryllium, cadmium, magnesium, manganese, thallium, and vanadium below the CRDL's and calcium, potassium, and sodium above the CRDL's in the field blank sample. The aluminum, antimony, arsenic, beryllium, cadmium, and thallium concentrations were due to laboratory blank concentrations. Because the associated soil samples (SDG MFJK50) have different matrix and reporting units than the field blank (water), the reviewer can not accurately flag the soil sample results for field contamination.

Rinsates: The laboratory reported concentrations of aluminum, antimony, barium, beryllium, cadmium, chromium, cobalt, iron, magnesium, manganese, mercury, nickel, selenium, thallium, vanadium, and/or zinc below the CRDL's and calcium, potassium, and sodium above the CRDL's in the rinsate samples. The zinc concentration in rinsate sample MFJ-K57 was above the CRDL. The aluminum, beryllium, cadmium, thallium, and vanadium concentrations were due to laboratory blank concentrations. Assessment for sampling equipment contamination can not be performed because information associating the samples with the rinsates is not available.

- 4. Pre-digestion Matrix Spike Recovery: Not Applicable.
- 5. Duplicate Analysis: Not Applicable.
- 6. ICP Quality Control:

Serial Dilution: Not Applicable.

<u>Interference Check Sample (ICS):</u> Acceptable. The reported ICS results indicated satisfactory interelement and background corrections.

Case 28007 SDG MFJK56 Site Ray Wichert Property Lab LIBRTY

6. ICP Quality Control, continued:

<u>Coefficient of Variation:</u> Provisional. The reviewer qualified the selenium result for sample MFJ-K57 because replicate instrument readings were inconsistent.

- 7. Furnace Atomic Absorption Quality Control: Not Applicable.
- 8. Laboratory Control Sample (LCS): Acceptable. The laboratory reported acceptable LCS recoveries, indicating satisfactory sample preparation and analysis.
- 9. Sample Verification: Acceptable. The reviewer detected a few reporting errors that did not affected sample results. The laboratory was contacted for corrections (see FAX Record Log).
- 10. Other QC: Not Applicable.
- 11. Overall Assessment: Sample result qualifications are summarized below.

The reviewer qualified one mercury result because of poor instrument performance near the CRDL.

The reviewer qualified one antimony, one arsenic, three beryllium, three cadmium, one vanadium, one zinc, and two thallium results because of laboratory blank effects.

The reviewer qualified one selenium result because of inconsistent instrument readings.

INORGANIC DATA QUALIFIER DEFINITIONS

The following definitions provide brief explanations of the ESAT-Region 6 qualifiers assigned to results in the inorganic data review process.

- U Undetected at the laboratory reported detection limit (IDL).
- L Reported concentration is between the IDL and the CRDL.
- J Result is estimated because of outlying quality control parameters such as matrix spike, serial dilution, FAA spike recovery, etc.
- R Result is unusable.
- F A possibility of a false negative exists.
- UC Reported concentration should be used as a raised detection limit because of apparent blank contamination.
- ^ High bias. Actual concentration may be lower than the concentration reported.
- v Low bias. Actual concentration may be higher than the concentration reported.

INORGANIC DATA SUMMARY

Case No.:

28007

SDG:

MFJK56

Reviewer: L. Hoffman

Laboratory:

LIBRTY

Matrix:

Water

Units:

ug/L

	FLAG	FLAG	FLAG	FLAG	FLAG	FLAG	FLAG
				FLAG	المحا	FLAG	FLAG
EPA Sample #=>	MFJ-K56	MFJ-K57	MFJ-K58				
ACUMINUM.	5 61 3 LUC	87.6 LUC	75.1 LUC				
ANTIMONY	2.1 U	2.2 L	5.3 LUC				
ARSENIC	2.3 U	2,3 U.S.	4.1 LUC 🚉				
BARIUM	7.9 L	6.1 L	5.1 L	AL METERS OF THE PROPERTY AND THE PROPER			
BERYLLIUM	0.46 LUC	0.48 LUC					
CADMIUM	0.33 LUC	0.25 LUC	0.26 LUC				
CAUCIUM	19400	20000	20100				
CHROMIUM	0.49 LJv	1.1 LJv	0.40 U				
COBALT	S + 0159 - 12	0.50 U /* #	0.50° U				
COPPER	0.60 U	0.60 U	0.60 U				
IRON	143 U	25.3 L	14.3. U				24976
LEAD	1.3 U	1.3 U	1.3 U				
MAGNESIUM	1860 1	1940 L	1900 L				
MANGANESE	0.95 L	1.4 L	0.51 L				
MERCURY	0.10 U	0.11 1.17	0.10 U				
NICKEL	1.3 L	0.87 L	0.70 U				
POTASSIUM	7100	7290	7530				
SELENIUM	2.2 ∪	3.4 LJ	2.2 U				
SILVER	0.60 U	0.60 U	0.60_U			de la companya de la	
SODIUM	26500	27300	27300				
THAI BUM	20000	21300 43.LUC	5,3 LUC				
VANADIUM	0.97 LUC	0.40 U	0.40 U				
ZINC	12.2 LJy	THE RESERVE THE PARTY OF THE PA	3.6° LJv				
CYANIDE	0.90 U	0.90 U	0.90 U				
CIANIDE	0.80 0	0.90	0.90 0				

No. <u>28007</u> SDG No. <u>MFJI</u>	SDG Nos. To Follow	y SAS No	Date R	ec <u>05/</u>	/11/0
PA Lab ID: LIBRTY		ORIGINALS	YES	NO	N
ab Location: Cary, NC		CUSTODY SEALS			Ť
	28007/MFJK56	1. Present on package?	x		
e_Submitted CSF? Yes	No X	2. Intact upon receipt?	х		Г
ox No(s):		FORM DC-2			
OMMENTS:		3. Numbering scheme accurate?	x		
The laboratory did not record the s	ample tags on Form DC-2	4. Are enclosed documents listed?		х	
and was notified about this omissi	on.	5. Are listed documents enclosed?	X		П
		FORM DC-1			Γ
		6. Present?	x		
		7. Complete?	X		
		8. Accurate?	X		
		CHAIN-OF-CUSTODY RECORD(s)			
		9. Signed?	l x.		
		10. Dated?	X		十
		TRAFFIC REPORT(s) PACKING LIST(s)			
		11. Signed?	l x		
		12. Dated?	х		T
		AIRBILLS/AIRBILL STICKER			T
		13. Present?	x		
		14. Signed?	X		T
		15. Dated?	х		\top
		SAMPLE TAGS			T
		16. Does DC-1 list tags as being included?	x	<u> </u>	
		17. Present?	х		1
		OTHER DOCUMENTS			T
		18. Complete?	x		
		19. Legible?	х		T
		20. Original?		х	Π
ver for additional comments.		20a.If "NO", does the copy indicate where original documents are located?	х		
idited by:	office .	Linda Hoffman / ESAT Data Reviewer	Date	06/11	/00
idited by:			Date		
adited by:			- Date	•	
Signat	ure	Printed Name/Title	-		
	TO BE COM	PLETED BY CEAT		 	
Date Recvd by CEAT:	D	rate Entered: Date Reviewe	d:		
Entered by:					
Reviewed by:					

REFERENCE 7



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 6 HOUSTON BRANCH 10625 FALLSTONE RD. HOUSTON, TEXAS 77099

MEMORANDUM

Date:	July 18, 2000
Subject:	Contract Laboratory Program Data Review
From:	Marvelyn Humphrey, Alternate ESAT RPO, 6MD-HC
To:	J.Enders, 6SF-RA
Site	: RAY WICHERT PROPERTY
Case	#: 28007
SDG#	: FGG56

The EPA Region 6 Houston Branch ESAT data review team has completed a review of the submitted Contract Laboratory Program (CLP) data package for the referenced site. The samples analyzed and reviewed are detailed in the attached Regional data review report.

The data package is acceptable for regional use. Problems, if any, are listed in the report narrative.

If you have any questions regarding the data review report, please call me at (281) 983-2140.

Attachments

cc: R. Flores, Region 6 CLP/TPO
 M. El-Feky, Region 6 Data Coordinator
 Files (2)

LOCKHEED MARTIN SERVICES GROUP ESAT REGION VI 10101 SOUTHWEST FREEWAY, SUITE 500 HOUSTON, TX 77074

MEMORANDUM

DATE:

July 17, 2000

TO:

Melvin Ritter/Marvelyn Humphrey, ESAT RPO/Alternate

RPO, Region VI

FROM:

Tom C.H. Chiang, ESAT Team Manager, Region VI

SUBJECT:

CLP Data Review

REF:

TDF # 6-0380A

ESAT # 0-2194

ESAT Contract No. 68-D6-0005

Attached is the data review summary for Case # 28007

SDG # FGG56

Site

Ray Wichert

Property

COMMENTS:

I. CONTRACTUAL ASSESSMENT OF THE DATA PACKAGE

A. The data package contained the following contractually noncompliant item that was detected by the hardcopy review and CCS audit.

BNA sample FG-G58DL had low internal standard (IS) responses, but the laboratory failed to perform the contract-required reanalysis to confirm the matrix effect (SOW OLMO4.2, p. D-53/SVOA, 11.4.3.2.1). The undiluted analysis, FG-G58, could not be used to satisfy the contractual requirement because it had acceptable IS performance. The outlying IS areas caused the qualification of one result for sample FG-G58DL.

B. The hardcopy review detected the following contractually noncompliant item that CCS did not report.

The laboratory submitted two sets of data for Pest/PCB sample FG-G61. However, the diluted analysis, FG-G61DL, is not contractually required. Neither the target compound peak responses nor the matrix interferences could justify the dilution (SOW OLM04.2, p.D-57/PEST, Sec. 10.2.3.2).

LOCKHEED MARTIN SERVICES GROUP ESAT REGION VI 10101 SOUTHWEST FREEWAY, SUITE 500 HOUSTON, TX 77074

MEMORANDUM

Attached	is	the	data	review	summary	for	Case	#	28007
					_		SDG	#	FGG56
							Site	<u> </u>	Ray Wichert
									Property

COMMENTS:

II. TECHNICAL USABILITY ASSESSMENT OF THE DATA PACKAGE

The total number of results reviewed was 1,317 for this data package. Some results were qualified because of technical problems, and the significant technical problems are summarized below.

- 1. The instrument for VOA water sample analysis had extremely poor sensitivity for acetone.
- 2. Field duplicate results were inconsistent for several PAH's, DDE, DDT, and α -chlordane.
- 3. BNA sample FG-G58DL had two low IS responses.
- Coeluting matrix interferences obscured the DDT identification in Pest/PCB sample FG-G60.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 6

HOUSTON BRANCH 10625 FALLSTONE ROAD HOUSTON, TEXAS 77099

ORGANIC REGIONAL DATA ASSESSMENT

CASE NO	28007	SITE Ray Wichert Property
LABORATORY	SWOK	NO. OF SAMPLES10
CONTRACT#	68-W99-079	MATRIX4 Water / 6 Soil
SDG#	FGG56	REVIEWER (IF NOT ESD)ESAT
SOW#RAS	SOW OLM04.2	REVIEWER'S NAME Gene Zhu
ACCT#	050102DJN70	COMPLETION DATE July 17, 2000
SF#	50102DZZ	
SAMPLE NO.	FG-G57 FG- FG-G58 FG-	G60 FG-G64 G61 FG-G65 G62 G63

DATA ASSESSMENT SUMMARY

1. 2. 3. 4. 5. 7. 8. 9.	HOLDING TIMES GC/MS TUNE/INSTR. PERFORM. CALIBRATIONS BLANKS SMC/SURROGATES MATRIX SPIKE/DUPLICATE OTHER QC INTERNAL STANDARDS COMPOUND ID/QUANTITATION PERFORMANCE/COMPLETENESS	VOA	BNA O O M O O O M O O O O O O O O O O O O	PEST O O O M O O M O M O O M M O O O M N/A M O
10.	PERFORMANCE/COMPLETENESS OVERALL ASSESSMENT	<u>O</u>	<u>O</u> <u>M</u>	O M

- O = Data had no problems.
- M = Data qualified due to major or minor problems.
- Z = Data unacceptable.
- NA = Not applicable.

ACTION ITEMS: The laboratory failed to perform the contract-required reanalysis for BNA sample FG-G58DL.

AREA OF CONCERN: Acetone and benzaldehyde failed technical RSD or D calibration criteria. One VOA instrument had extremely low sensitivity for acetone. Laboratory contamination resulted in raised quantitation limits for some analytes in five VOA and five Pest/PCB samples. BNA and Pest/PCB field duplicates had inconsistent results. BNA sample FG-G58DL had low IS responses. Matrix interferences obscured the DDT detection for Pest/PCB sample FG-G60. Some pesticides had two-column quantitation results differing by more than 25 percent. Pest/PCB sample FG-G61DL was not contractually required.

NOTABLE PERFORMANCE:

Page 3 of 27

COMMENTS/CLARIFICATIONS REGION VI CLP QA REVIEW

CASE 28007 SDG FGG56 SITE Ray Wichert Property LAB SWOK

The following is a summary of sample qualifiers used by Region 6 in reporting this CLP data:

No.	Acceptable	Provisional	<u> Unacceptable</u>
VOA	1	9	
BNA	5	4	
PEST	3	6	

COMMENTS: This SDG contained six soil samples, two rinsates, and one field blank for complete RAS organics analysis and one trip blank for VOA analysis by OLM04.2. The OTR/COC Records designated samples FG-G56 and FG-G57 as field duplicates, sample FG-G56 as the laboratory QC sample, samples FG-G62 and FG-G63 as rinsates, sample FG-G64 as a field blank, and sample FG-G65 as a trip blank. All soil samples were analyzed at the low level. At the Agency's request, the laboratory performed additional clean up for all soil Pest/PCB extracts using silica gel following SW-846 Method 3630. The CRQL's required %moisture correction for the soil samples. The corrected CRQL's were reported by the laboratory and are referred to as sample quantitation limits (SQL's) in this report. The data package arrived on time for the 21-day contractual turnaround time but contained the contractually noncompliant items below.

- The laboratory failed to reanalyze BNA sample FG-G58DL with outlying IS responses.
- Pest/PCB sample FG-G61DL was not contractually required.

VOA/BNA Four BNA samples were diluted (up to 25X) and analyzed or reanalyzed because of high concentrations of PAH's (up to 63,000 µg/Kg). One other BNA sample contained benzaldehyde at a concentration above the SQL. No target analytes were detected at concentrations above the SQL's/CRQL's in the VOA samples except for the laboratory contaminant methylene chloride. The VOA instrument for water analysis had extremely poor sensitivity for acetone. Many PAH's had inconsistent field duplicate results. BNA sample FG-G58DL had low IS responses.

Pest/PCB Samples FG-G56 and FG-G57 were diluted (10X) and reanalyzed because of high peak responses (up to 180 μ g/Kg) for DDE, DDT, and chlordanes on one or both columns. Four other soil samples also contained some pesticides at concentrations above the SQL's. Rinsate sample FG-G63 contained γ -chlordane at a concentration above the CRQL. DDE, DDT, and α -chlordane had inconsistent field duplicate results. Matrix interferences obscured the DDT detection in sample FG-G60.

CASE 28007 SDG FGG56 SITE Ray Wichert Property LAB SWOK

COMMENTS: (continued) Some data are provisional for nine VOA, four BNA, and six Pest/PCB samples because of problems with calibration, laboratory contamination, inconsistent field duplicate results, IS performance, matrix interference, and compound quantitation. The technical usability of all reported sample results is indicated by ESAT's final data qualifiers in the Data Summary Table. An Evidence Audit was conducted for the Complete Sample Delivery Group File (CSF), and the audit results were documented in the Inventory Checklist.

NOTE: THE FOLLOWING REVIEW NARRATIVE ADDRESSES BOTH CONTRACTUAL ISSUES (BASED ON THE STATEMENT OF WORK) AND TECHNICAL ISSUES (BASED ON THE NATIONAL FUNCTIONAL GUIDELINES). THE ASSESSMENT MADE FOR EACH QC PARAMETER IS SOLELY BASED ON THE TECHNICAL DATA USABILITY, WHICH MAY NOT NECESSARILY BE AFFECTED BY CONTRACTUAL PROBLEMS. THE ASSESSMENTS ARE DEFINED BELOW.

Acceptable = No results were qualified for any problem associated with this QC parameter.

Provisional = Some results were qualified because of problems

associated with this QC parameter.

Unusable = All results are unusable because of major problems associated with this QC parameter.

- 1. Holding Times: Acceptable. All samples met the contractual holding time criteria. The water samples met the technical holding time criteria (40 CFR Part 136). The laboratory reported elevated cooler temperatures (7.6°C to 9.3°C) that exceeded the contract-specified limit of 6°C. In the reviewer's opinion, the effect of the elevated shipping temperatures is insignificant.
- 2. Tuning/Performance: Acceptable. All analyses met instrument tuning and performance criteria. All Pest/PCB sample analyses met instrument performance guidelines.
- 3. Calibrations: Provisional. TCL compounds met contractual calibration criteria. Some VOA and BNA analytes failed technical %RSD and/or %D calibration criteria, but only results for the following analytes were affected and qualified as estimated:

methylene chloride in VOA samples FG-G56, FG-G57, FG-G58, FG-G59, and FG-G60 and

benzaldehyde in BNA sample FG-G61.

Despite the acceptable RRF's, acetone had an extremely low response (near the noise level) at the CRQL for the water analysis as demonstrated by the manual integration chromatogram submitted with the low point initial calibration standard. The reviewer, therefore, qualified all acetone CRQL's as estimated and biased low for the VOA water samples.

CASE 28007 SDG FGG56 SITE Ray Wichert Property LAB SWOK

4. Blanks: Provisional. The method, storage, and instrument blanks met contractual QC guidelines. The laboratory reported the following target analytes at concentrations below the CRQL's in the BNA and Pest/PCB method blanks: di-n-butylphthalate, bis(2-ethylhexyl)phthalate, heptachlor, and γ -chlordane. The laboratory also reported methylene chloride at a concentration below the CRQL for the VOA storage blank. The effects of the laboratory contamination are summarized below.

The y-chlordane results are biased high in Pest/PCB samples FG-G56, FG-G59, FG-G60, and FG-G61.

The remaining laboratory "B"-flagged sample results should be considered as undetected (U) because the concentrations were less than 5X or 10X the associated storage/method blank values. Among the affected results, the heptachlor result in Pest/PCB sample FG-G56, the γ -chlordane result in Pest/PCB sample FG-G57, and the methylene chloride results in VOA samples FG-G56 through FG-G60 were above the SQL's and should be used as raised quantitation limits (M).

Trip blank The VOA trip blank, sample FG-G65, contained chloroform at a concentration below the CRQL. The reviewer recommends that the chloroform results be considered as undetected (U) for rinsate samples FG-G62 and FG-G63 because the chloroform concentrations in these samples were identical to that in the trip blank.

<u>Field blank</u> The field blank, sample FG-G64, contained diethylphthalate, di-n-butylphthalate, and several laboratory contaminants at concentrations below the CRQL's. Since none of the field samples contained diethylphthalate and di-n-butylphthalate, results were unaffected.

Rinsates Some laboratory contaminants were detected in the rinsates, samples FG-G62 and FG-G63. The laboratory also reported BNA analyte di-n-butylphthalate (<CRQL) and pesticide γ -chlordane (>CRQL) for rinsate sample FG-G63. The reviewer did not qualify any sample results because information associating the field samples with the rinsates is unavailable.

5. System Monitoring Compounds (SMC's)/Surrogates: Acceptable. SMC and surrogate recoveries were within the QC limits with some exceptions. BNA sample FG-G60 had one surrogate recovery exceeding the QC limit, but data qualification was not required. The DCB recovery was marginally below the QC limit for Pest/PCB sample FG-G59. Since this recovery was within the expanded Region 6 limit, no results were qualified.

CASE 28007 SDG FGG56 SITE Ray Wichert Property LAB SWOK

6. Matrix Spike/Matrix Spike Duplicate: Acceptable. MS/MSD results generally met QC guidelines for precision and %recovery. Exceptions are discussed below. The laboratory could not recover acenaphthene and pyrene from the BNA MS/MSD samples because the native sample concentrations for these two analytes were much higher than the spiked concentration. The laboratory reported a high MS recovery for pesticide DDT. The MS/MSD results for the above-mentioned analytes were not used to assess the matrix effects because they were calculated using analyte concentrations that exceeded the upper calibration limits and may not be accurate.

7. Other QC:

Field Duplicate: Provisional. The field duplicate results were generally consistent with the following exceptions.

BNA Many PAH's had much higher concentrations in sample FG-G56 than in its field duplicate, sample FG-G57. The reviewer qualified the reported concentrations for the following analytes as estimated and biased high in sample FG-G56(DL) and estimated and biased low in sample FG-G57(DL): acenaphthene, dibenzofuran, fluorene, phenanthrene, anthracene, and carbazole.

Pest/PCB The concentrations were up to 10% different for DDE, DDT, and α -chlordane in field duplicate samples FG-G56 and FG-G57. The reviewer qualified the results for these pesticides as estimated and biased high in sample FG-G56(DL) and estimated and biased low in sample FG-G57.

- 8. Internal Standards (IS): Provisional. Internal standard performance was acceptable for the VOA and BNA samples with one exception. BNA sample FG-G58DL had low responses for IS5 and IS6, but the laboratory failed to perform the contract-required reanalysis. The undiluted analysis could not be used to demonstrate matrix effect because it had acceptable IS performance. The reviewer qualified the pyrene concentration as estimated for sample FG-G58DL because of the low IS5 response.
- 9. Compound Identity/Quantitation: Provisional. All reported results met compound identification criteria.

VOA The only target compound reported at concentrations above the SQL's was the laboratory contaminant methylene chloride in five soil samples.

BNA The laboratory diluted (up to 25%) and analyzed or reanalyzed samples FG-G56, FG-G57, FG-G58, and FG-G60 because of high PAH concentrations (up to 63,000 $\mu g/Kg$). Sample FG-G61 contained benzaldehyde at a concentration above the SQL. The remaining samples did not contain any target analytes with concentrations above the SQL's/CRQL's.

CASE 28007 SDG FGG56 SITE Ray Wichert Property LAB SWOK

9. Compound Identity/Quantitation: (continued)
Pest/PCB Samples FG-G56 and FG-G57 were diluted (10X) and reanalyzed because of high concentrations (up to 180 µg/Kg) of DDE, DDT, chlordanes, and several other pesticides. Samples FG-G58, FG-G59, FG-G60, and FG-G61 also contained pesticides at concentrations above the SQL's. Water sample FG-G63 contained y-chlordane at a concentration above the CRQL. The laboratory diluted (10X) and reanalyzed sample FG-G61 for no apparent reasons. GC/MS confirmation was not required for the reported analytes.

DDT was detected at about 2X the SQL on one column for sample FG-G60. However, a broad coeluting matrix peak obscured the DDT confirmation on the other column. The reviewer qualified the reported DDT SQL as estimated and biased low for sample FG-G60 because of the interference. Sample FG-G58 also had coeluting matrix interferences on one column. Since no target compounds were detected on the other column, result qualification was unnecessary.

- All laboratory "P"-flagged results that were above SQL's or CRQL's were qualified as estimated because two-column quantitation results differed by more than 25 percent.
- 10. Performance/Completeness: Acceptable. The data package was complete but had some reporting errors. The laboratory response to CCS (dated 6/6/00) was reviewed. This response has no effect on the sample results. The resubmission was placed at the beginning of the data package and should be used for references only. The laboratory was contacted for other necessary corrections and resubmissions (see Fax Record Log).
- 11. Overall Assessment: Data are acceptable for one VOA, five BNA, and three Pest/PCB samples.
- **VOA** Some results were qualified for the following samples because of problems with calibration and laboratory blank contamination: FG-G56, FG-G57, FG-G58, FG-G59, FG-G60, FG-G62, FG-G63, FG-G64, and FG-G65.
- BNA Some results are provisional for the following samples because of problems with calibration, IS performance, and inconsistent field duplicate results: FG-G56(DL), FG-G57(DL), FG-G58(DL), and FG-G61.

Pest/PCB Some results are provisional for the following samples because of problems with laboratory blank contamination, inconsistent field duplicate results, matrix interference, and compound quantitation: FG-G56(DL), FG-G57, FG-G59, FG-G60, FG-G61, and FG-G63.

ORGANIC DATA QUALIFIER DEFINITIONS

The following definitions provide brief explanations of the ESAT-Region 6 qualifiers assigned to results in the Data Summary Table.

- U Not detected at reported quantitation limit.
- N Identification is tentative.
- J Estimated value.
- L Reported concentration is below the CROL.
- M Reported concentration should be used as a raised quantitation limit because of interferences and/or laboratory contamination.
- R Unusable.
- [^] High biased. Actual concentration may be lower than the concentration reported.
- v Low biased. Actual concentration may be higher than the concentration reported.
- F+ A false positive exists.
- F- A false negative exists.
- B This result may be high biased because of laboratory/field contamination. The reported concentration is above 5X or 10X the concentration reported in the method/field blank.
- UJ Estimated quantitation limit.
- Identification is questionable because of absence of other commonly coexisting pesticides.
- * Result not recommended for use because of associated QA/QC performance inferior to that from other analysis.

Case No. :

28007

SDG:

FGG56

Reviewer: Gene Zhu

Laboratory:

SWOK

Matrix:

Soil

Units: ug/Kg

VOLATILE	FLAG	FLAG	FLAG	FLAG	FLAG	FLAG	FLAG
EPA SAMPLE NUMBER :	FG-G56	FG-G57	FG-G58	FG-G59	FG-G60	FG-G81	
Dichlorodifluoromethane	12 'U "	276-35-12 U 35-	K9# +312 U ***	20 21 31 3 AU 20 20 A	11 เป	13 U	er avrigue traevile
Chloromethane	12 U	12 U	12 U	13 U	11 U	13 U	- Caracine
/inyl Chloride		77.12 U 🔩	″a= €12.U	2 33 (U±)≥		13 U	
3romomethane	12 U	12 U	12 U	13 U	11 U	13 U	and a state of the
Chloroethane	12 U €		/ 12 U	13 U	5 11 U	25 13 U	0.80 40.854 -56
Trichlorofluoromethane	12 U	12 U	12 U	13 U	11 U	13 U	
1,1-Dichlorcethene	3-12°U (5	12 U		35 35 10 U.S.	920 0 11 U 190	13 Ú	
1,1,2-Trichloro-1,2,2-trifluoroethane	12 U	12 U	12 U	13 U	11 U	13 U	
Acetone	12 U	. 12 U	`_(i = 12_U	(a.g. 13, U. a)	30; 311 U	5 13 U FE	
Carbon Disulfide	12 U	12 U	12 U	13 U	11 U	13 U	
Methyl Acetate	。 第二十12 · U ,第二十	32.U = 3.	5.0512_U (5.			Control of the Party of the Par	
Methylene Chloride	17 UJM	17 UJM	14 UJM	16 UJM	15 UJM	13 U	
rans-1.2-Dichlorcethene	12-U	12 U	12 U	13 U	11 U	3. 13. U.≗ ∵ 13. U	
Methyl tert-Butyl Ether	12 U			PER LIBERT		13 U	
1,1-Dichloroethane	12 U	12 U	12 U	13 U	11 U	13 U	
2-Butanone	350 542 117652	99-1-112 Us =					1982
Chloroform	12 U	12 U	12 U	13 U	11 U	13 U	
1.1.1-Trichloroethane	22020	752 122 U 52			ASSESSED USES	38.25 313 U.S.	
Cyclohexane	12 U	12 U	12 U	13 U	11 U	13 U	والمتحالة المتحددة والمتحددة والمتحدد والمتحدد والمتحدد والمتحدد والمتحددة و
Carbon Tetrachloride	3 6 12 U 3	. 12 U	PAR UP	13 U	K - KINDES	13 -U - 18	
Benzene	12 U	12 U	12 U	13 U	11 U	13 U	
1.2-Dichloroethane	12 U = E	: 12 U :::	12 U		e ii U	⁄4.05 (4.13 U	
Trichloroethene	12 U	12 U	12 U	13 U	11 U	13 U	
Methylcyclohexane	12 U	(12 U)	. 7 M2 U	13.U		2413 U	
1,2-Dichloropropane	12 U	12 U	12 U	13 U	11 U	13 U	
Bromodichloromethane 🖘 🛸 🛒	S € 12 U		12-U			13 .U	
cis-1,3-Dichloropropene	12 U	12 U	12 U	13 U	11 U	13 U	
4-Methyl-2-pentanone			SE SIZEULI		and the Court of t	34-43 AU 34-34	
Toluene	12 U	12 U	4 LJ	13 U	6 LJ	13 U	
trans-1,3-Dichloropropene		12 U	12 U	13 U	11 U	23 U	
1,1,2-Trichloroethane	12 U	12 U			24 24 11 U S 12	13 U 5302 13 U	
Tetrachloroethene	12 U	12 U	12 U	13 U	11 U	13 U	
2-Hexanone					* A SHED KA		
Dibromochloromethane 1,2-Dibromoethane	12 U	12 U	12 U	13 U	11 U	13 U	
Chlorobenzene	32.U 32.U		12.0	24-35-413-1U-4-5	255 - 111 U 225	3 13 U	
The state of the s	12 U	12 U	12 U	13 U	11 U	13 U	and the state of t
Ethylbenzene Xylenes (total)	2 0 5 F		122 U		A 2862 11 - U S.S.		
Styrene	12 U	12 U	12 U	13 U	11 U	13 U	The state of the s
Bromoform	742 U	25 12 U 2	12 Ú	13 U T	SUPERIOR DESCRIPTION	77 13 U	
Isopropyibenzene	12 U	12 U	12 U	13 U	11 U	13 U	
1,1,2,2-Tetrachloroethane	35-0-12 -U		72 U	== 213°U°==	- 11 U	₹\$25 13 U	
1,3-Dichlorobenzene	12 U	12 U	12 U	13 U	11 U	13 U	
1.4-Dichlorobenzene	A 2 2 12 10 10 10 10 10 10 10 10 10 10 10 10 10	12 -U		2 C13 U		- 3 U	
1,2-Dichlorobenzene	12 U	12 U	12 U	13 U	11 U	13 U	
1,2-Dibromo-3-chloropropane		12 U			€ 11 ° U 7 '§		
1,2,4-Trichlorobenzene	12 U	12 U	12 U	13 U	11 U	13 U	
] .	_		_	_	_	
Sample wt (g) :	5	5	5	5	5	5	
		40	40	24	4.4	22	
%Moisture :	16	19	16	21	11	23	
		4	1	1	1	4	
Dilution Factor :	1	1	ı	ı	•	1	
1	1000	Low	Low	Low	Low	Low	
Level:	Low	50W	-24	204	25#	LUW	
Number of TIC's:	1	0	С	o	o	0	
		•					

Case No. :

28007

SDG:

FGG56

Reviewer: Gene Zhu

Laboratory:

SWOK

Note:

Matrix:

Water

Units: ug/L

VOLATILE EPA SAMPLE NUMBER ·	FLAG FG-G62		FLAG	ı	FLAG	i e	FLAG	FLAG	FLAG	FLAG
		FG-G63		FG-G64		FG-G65		-		
	1 0-002	1.00				L				
Dichlorodiffuoromethane	3 10 U	₹30€10	U PER	5 20	U Z	3.7. 10	UTIS			war in in die
Chloromethane	10 U	10	U	10	U	10	U	vaddalaksov lovaksi 46. 14. 11. 11. 11. majuraja	the hours, with the time the second transfer of the second street of the	प्रकारी के । प्रशासकी प्रशासक देवी
Vinyl Chloride	X77/10 U	7.10	U to	2 10	U See	10	Ū.			6485484833
Bromomethane	10 U	10	U	10	U	10	U	HOMESCHIMAL MINISTER (217 1 2 745	and a second or with the second of the secon	e etilogistis i i i Merit (mediasi) e u sisset
Chloroethane	10 U	₹ 10	U S	KR 24-10	U 🤧	(10)	ับ 💆			
Trichlorofluoromethane	10 U	10	U	10	U	10	Ü		The second second second second	Marie Commission Company
1,1-Dichloroethene	3.55.10 U	,10	U	- 10	Ū 📆	10	U			
1,1,2-Trichloro-1,2,2-trifluoroethane	10 U	10		10	U	10				
Acetone	10 UJV	10	UJv 🔊	10		_				
Carbon Disulfide	10 U		<u>u</u>	10		10		an annual of the second se	A Total Cartinate Control	College and and a second second
Methyl Acetate	6 05 10 U (#	The Contract Spiritual Contract of					'U 1 1		A. Dillerall	المناه فالمستسددة المتناه
Methylene Chloride	10 U		U		U	10	U	المائات فالمعارض المائية المائية	~ X * 20 X * * * * * * * * * * * * * * * * * *	وراد درووه الإمام والرواد المسادر والموارية
trans-1,2-Dichloroethene	10 U			- 5 P 10						
Methyl tert-Butyl Ether	10 U €0 €10 U 7	10	U Tracea	10		10				Sant Ser Production to State State of
1.1-Dichloroethane				10		10				
cis-1,2-Dichloroethene	10 U	10	ा कार्य	10 242 210						Selection of the Selection
2-Butanone		10	-		U	2		4.546.		ل هاششته در ده
Chloroform 1,1,1-Trichloroethane	10 U			10			บริเ			
)	10 U	10		10		10		ك شيخش كسيدان الدور	A A A A A A A A A A A A A A A A A A A	and the second second second second second
Cyclohexane Carbon Tetrachloride	37 E 10 U S				បាន		ับได้เรา	HEETT FU		
Benzene	10 U		U	-	U	and residents of .	U	المناكلات يستان المدينية بمناهد المناسك المحاصد فيا		er aller Maria Production and American and
1.2-Dichloroethane	310 U		U Com		U	- 10	บ ี:			
Trichloroethene	10 U		U	10	Ü	10	Ū	and the second second second second second		ak 27. Abba ya ni mbadhadhali i domi ndi abid
Methylcyclohexane	10 U 52	7 7 10	UZX	¥¥\$-€10	U	- 10	U 📆			
1,2-Dichloropropane	10 U	10	U	10	U	10	U			
Bromodichloromethane	÷ (310 U 3	10	U	10	(U.etile	10	U =			
cis-1,3-Dichloropropene	10 U	10			U	10	U			
4-Methyl-2-pentanone		c ≥ √ €10	U.se	** < VIO	فالمرا تسبيب	-	U ca			
Toluene	10 U	10		10			U		inga wakana ni banna ni banyi. ''''nyinga ar	
trans-1,3-Dichloropropene	÷ ;= 10 (U \)						U			
1,1,2-Trichloroethane	10 U	10		10		10				erprografier in die egeneraties verschieder
Tetrachloroethene	30 #±10 ₹U 37			3 Sept. 10			UNE			
2-Hexanone	10 U		U	10			U			a danas e e es tado de estado s.
Dibromochloromethane	ે10 U ∴ે	- 310		Maria de la composición dela composición de la composición de la composición dela composición dela composición dela composición de la composición de la composición dela composición de la composición dela	U S	10		- 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1		الإن المالي والمالية والمالية المالية المالية المالية المالية المالية المالية المالية المالية المالية المالية المالية المالية المالي
1,2-Dibromoethane	10 U		U TO SEE	10	U	10	ັບ ທີ່			
Chlorobenzene vs-5	manufacture was a substitute of the substitute o	10		10			U			Lille Sim & Baker Bakille
Ethylbenzene	10 U	10			U			y the more production of the control		
Xylenes (total)	10 U 10 U	10		10		10		aan dhaa ah dhaada ah	سن أن والمُنْفُلُةُ كُلُونُونَا الْمُنْفِينَ الْفُونِينَ الْفُونِينَ الْفُونِينَ الْفُونِينَ	الأنفائقش والأراب والمعليمة
Styrene	700	ा <u>ः</u> इ.स. इ.स. १०	U	10		10	** ** ********		A CONTRACTOR OF THE STATE OF TH	
Bromoform	10 U	10		10	سنحسنده U	د. 10	*****	e make in the common of the large of the field	حيواد الجعمور علم مميوان يوسيام مثل	والمعاقبة أموادي المحادث
isopropylbenzene 1,1,2,2-Tetrachloroethane	30 U 3	10		10	<u> </u>		Ü		energy and the second of the s	e de la companya de La companya de la co
1,3-Dichlorobenzene	10 U	10	:::	10			U	as to the minimum and the same	فأعم المسجيد لكسيعات فالمتاب عمومنا	galismatini — a a gandersiia
1,4-Dichlorobenzene		10				10	U	en arm ganemaren gane Garata agar garatata		
1,2-Dichlorobenzene	10 U	10		10	U		U		THE R P. LEWIS CO. P. LANSING.	* *************************************
1,2-Dibromo-3-chloropropane	7 10 U 3			10			Ú 📆			manus and second of the second
1,2,4-Trichlorobenzene	10 U	10			U		ับ	participation of the second control of the	The Hill He state is a fitting	•
	' -									
Volume (mi) :	5	5		5		;	5			
(,,,,,										
Dilution Factor :	1	1		1			t			
	}						_			
Number of TIC's :	0	0		Q	}	•	0			

For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

Case No. :

28007

SDG:

FGG56

Reviewer : Gene Zhu

Laboratory:

SWOK

Note:

Matrix:

Sail

Units:

ug/Kg

SEMIVOLATILE	T FLAG	FLAG	FI	AG FLAG	FLAC	51 7.5	
EPA SAMPLE NUMBER :	FG-G56	FG-GS6DL	FG-G57	FG-G57DL	FG-G58	1	FLAG
E. A GAMI EE HOMBER.	FG-G38	1 3-33000	1. 0.007	11 0-03700	LG-030	FG-G58DL	FG-G59
Senzaldehyde	120 JLJ	9700 U •	160 L	J 722,≈9900 U• €	190 ALJ		Sing many management
Phenol	والمصاب المصيرة الكاكات وجريون	9700 U	2000 U			3800 U	170 LL
7 47 4 7 5 7 TO 10	1900 U	9700 U			1900 U	3800 U	410 U
bis-(2-Ch/oroethyl) ether	1900 U	9700 U	2000 U		्रिक्ट 1900 ÷U े		410 U
2-Chlorophenol	1900 U			9900 U*	1900 U	3800 U *	410 U
2-Methylphenol	1900 U	9700 U		9900 U	1900 U	3800 U • · ·	410 °U
2.2'-oxybis(1-Chloropropane)	1900 U	9700 U	2000 U	9900 U •	1900 U	3800 U *	410 U
Acetophenone	1900 U	9700 U 🔭		and the same and are one of the same and	. 1900 U →	and the state of t	410 U
4-Methylphenol	100 LJ	9700 U *	2000 U	9900 U •	1900 U	3800 U*	59 LJ
N-Nitroso-di-n-propylamine	1900 U	9700 U		9900 U			410 nU 🤭
Hexachloroethane	1900 U	9700 U°	2000 U	9900 U •	1900 U	3800 U *	410 U
Nitrobenzene Zaz Zaz		9700 LU 30		9900 U n		3800 U •	410 · U
Isophorone	1900 U	9700 U*	2000 U	9900 U •	1900 U	3800 U*	410 U
2-Nitrophenol	1900 U	his little harmon and the second		9900 U	v ← 1900 U.S.	3800 U 🐪	410 U
2,4-Dimethylphenol	1900 U	9700 U*	2000 U	9900 U*	1900 U	3800 U *	410 U
bis(2-Chloroethoxy)methane	1900 −U ≉,55			9900 U		≲* ≧3800 ·U * ∷	410_U
2,4-Dichlorophenol	1900 U	9700 U *	2000 U	9900 U •	1900 U	3800 U *	410 U
Naphthalene.	1400 - LJ	1500	200 企	9900 U	220 FUS	200	23 EU'
4-Chloroaniline	1900 U	9700 U*	2000 U	9900 U *	1900 U	3800 U *	410 U
Hexachlorobutadiene	1900 U	9700 U 🍰	2000 · U	9900 U	1900 U	**************************************	410-0 4-
Caprolactam	1900 U	9700 U°	2000 U	9900 U *	1900 U	3800 U	410 U
4-Chloro-3-methylphenol	1900 U	9700 U	2000 U	9900 U	1900 U.	3800 U •	410 U
2-Methylnaphthalene	1000 LJ	1500	2000 U	9900 U •	1900 U	3800 U*	28 LJ
Hexachlorocyclopentadiene	1900 U	. 5 9700 U 🚭	2000 U	- 29900 U	#¥1900 U ¥		410 U \$3
2,4,6-Trichlorophenol	1900 U	9700 U °	2000 U	9900 U •	1900 U	3800 U *	410 U
2,4,5-Trichlorophenol	4900 U	24000 U -	5000 U	25000 U	4800 U	9500 U ·	-1000 U
1,1'-Biphenyl	540 LJ	810	2000 U	9900 U •	1900 U	3800 U	410 U
2-Chloronaphthalene	1900 U	9700 U	2000 · U	9900 U 3	1900 U	3800 U •	.410 U 🚍
2-Nitroaniline	4900 U	24000 U *	5000 U	25000 U *	4800 U	9500 U	1000 U
Dimethylphthalate	1900 U	9700 U 🐣	2000 U	9900 U 🗬	1900 U	3800 Ú	410 U 2
2,5-Dinitrotoluene	1900 U	9700 U	2000 U	9900 U •	1900 U	3800 U	410 U
Acenaphthylene -	- 370 LJ	€ €9700 U · 2	7300 ⊐L	J :: 9900 U : 7	240 EL		92 11
3-Nitroaniline	4900 U	24000 U	5000 U	25000 U	4800 U	9500 U	1000 U
Acenaphthene	7000 J^	7900	1800 · L	V 2000	1100 a LI		6 1 2 2 2 1 A LU A
2.4-Dinitrophenol	4900 U	24000 U	5000 U	25000 U *	4800 U	9500 U	1000 U
4-Nitrophenol	3 4900 U	24000 U 😘	5000 U	25000 -U	4800 JU	8500 U ·	1000 U
Oibenzofuran	5000 J^	5500	750 L	<u>ئۇلۇرىن سىنلىنىسىمىسىمىلىنىسى</u>	410 LJ	480	30 LJ
2,4-Dinitrotoluene	1900 U	9700 U	2000 U	9900 U	1900 U	3800 U * `	S 7/410 1U € 5
Diethylphthalate	1900 U	9700 U	2000 U	9900 U °	1900 U	3800 U	
Flucrene	8100 J^			THE RESERVE THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.	THE RESERVE THE PERSON NAMED IN COLUMN TWO IS NOT THE PERSON NAMED IN COLUMN TWO IS	3800 0	410 U 410 U
4-Chlorophenyi-phenyi ether	1900 U	9700 U *	2000 U	9900 U	1900 U	3800 U	410 U
4-Nitroaniline	4900 U	24000 U * 3		25000 U			1000 U
4,6-Dinitro-2-methylphenol	4900 U	24000 U	5000 U	25000 U *	4800 U	9500 U *	1000 U
N-Nitrosodiohenylamine	1900 U	9700 U				9500 U	410 U 6
4-Bromophenyl-phenylether	1900 U	9700 U	2000 U	9900 U *	1900 U	3800 U*	and the second second second
Hexachlorobenzene	1900 U	9700 U • 7			1900 U	Comments of the Comments of the Section of	410 U
Atrazine	A finish in the management of the contract	9700 U	2000 U	9900 U	habaniariasin +	Call Committee C	410 U
The street of th		9700 U • ₹			1900 U	3800 U	410 U
Pentachlorophenol			22000		4800 U	9500 U	- 1000 U
Phenanthrene	54000			22000 Jv	11000	11000	130 LJ
Anthracene	17000	نالله مسعودينية أأحياه بالم	5800 J\ 2200 J\	بەرنىنى كانونادە سى . سىنۇلىد كاسىسىلىنىلىك	2600	2500	47 ELJ
Carbazole	1 9800 J^	10000 *	2200 J\	/ 2100 *	1700 LJ	1400 *	31 LJ

For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

Case No.:

28007

SDG:

Reviewer: Gene Zhu

Laboratory:

SWOK

Matrix:

FGG56 Soil

Units: ug/Kg

SEMIVOLATILE	i	FLAG :		FLAG	1	FLAG	1	FLAG	Τ	FLAG	T	FLAG		FLAG
EPA SAMPLE NUMBER :	FG-G56		FG-G56DI	-	FG-G57		FG-G57D	L	FG-G58		FG-G58DL		FG-G59	, 4.0
						**								
Di-n-butylphthalate	1900	U	9700	U•		U	et Wilder of California and a	U •.	1900	U To	3800	U·	~~~~ ¥10	ַ בַּיַ עַ
Fluoranthene	65000	•	63000		39000	•	39000		19000	•	15000		250	LJ
Pyrene Company	52000		52000	3.5	\$419.76 , r sugaren		en reliensen a se a	نسمد تنداد	Maria de la casa de la	= 3 7 M	16000	[J]	230	.}U ÷
Butylbenzylphthalate	1900	U	9700		2000		9900		1900		3800	u·	410	U
3,3'-Dichlorobenzidine	1900	U	9700	U	2000	<u>u</u>		U .	1900	U	3800	U •	410	U
Benzo(a)anthracene	29000	•	32000		18000	*	19000		7600		7200	•	120	LJ
Chrysene	.30000		32000			۰۰ پ معنفتک ۱۹۸۰			8500		∌: ⇒:7500		190	LJ 🟅
bis(2-Elhylhexyl)phthalate	1900	U	9700		2000		9900		1900		3800	-	410	U
Di-n-octylphthalate	1900	Ú	9700	U ·				U	1900	U .	3800	U .	410	U.S
Benzo(b)fluoranthene	25000	•	35000	J^	16000		24000	•	6800		9900	•	210	니
Benzo(k)fluoranthene	24000		A 15000					ت لاق	7900				- ≥ 180	يدلي
Benzo(a)pyrene	25000	•	26000		16000		16000	•	7600		6900	•	160	LJ
Indeno(1,2,3-cd)pyrene	13000			1		70 × × ×			4000			e	₹ ₹ ≥100	<u> 4</u> U 4
Dibenzo(a,h)anthracene	6900		3500	•	3600		2400	•	1900		1100	•	40	LJ
Benzo(g.h.i)perylene	313000		13000		8200		8700	30.4	4400		5200		110	LU3
Sample wt (g) :	30.5		30.5		30.8	3	30.8	:	30.9	ı	30.9		30.4	
%Moisture :	16		16		19)	19)	16		15		21	
Dilution Factor:	5		25			5	25	5	5	i	10		1	
Level:	Low		Low		Lov	,	Low	,	Low	•	Low		Low	1
Number of TIC's :	30		22		30)	14	ŀ	30	ı	16		30	1

Case No.:

28007

SDG:

FGG56

Soil

Reviewer: Gene Zhu

Units:

Laboratory:

SWOK

Matrix:

ug/Kg

SEMIVOLATILE	T FLAG	FLAG	FLAG	FLAG	FLAG	FLAG I	
EPA SAMPLE NUMBER :	FG-G60	FG-G61	, , , ,	, 5,0	15.0	المحاد	FLAG
CIA GAMPLE NOMBER.	FG-G00	110-001					
Carallelando de Santa de Carallelando			FIRE CAY S ASSESSMEN		فمنسد التعمد مشيا ليشافرون في	استاف ما الشافلات الماراتين بمعالك	
Benzaldehyde	1800 U	400 U	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4			يان در دور در	And the state of t
·		400 U 342			دهم فالمنافئة وتحتر والمنافع و	and in the second of the second of the second	Personal Activities and American American Company
bis-(2-Chloroethyl) ether		400 U				de la company de	
2-Chlorophenoi	1800 U			distriction of the Commission and Parlies on St.			-
2-Methylphenol	The state of the s	400 U					
2,2'-oxybis(1-Chloropropane)	1800 U	400 U					
Acetophenone Acetophenone	1800 U 🦠	248 ° U					
4-Methylphenol	1800 U	400 U					
N-Nitroso-di-n-propylamine							
Hexachloroethane	1800 U	400 U			e galangen, eggig 30,30 men a fra gengeneen naggar		
Nitrobenzene		÷ ₹400 U				e-called and a second	
Isophorone	1800 U	400 U	27. ALS 20				
2-Nitrophenol		100 U			E 4		
2,4-Dimethylphenol .	1800 U	400 U					
bis(2-Chloroethoxy)methane		< 400 Ub <	and the state of t				
2.4-Dichlorophenol	1800 U	400 U			,		
Naphthalene :		#=#400±U+					
4-Chloroaniline	1800 U	400 U					***************************************
Hexachlorobutadiene	31800 ×U≥ 1	400 U					
Caprolactam	1800 U	400 U					
4-Chloro-3-methylphenol	1800 U 4	400 U Se	STATE OF THE STATE		2012		
2-Methylnaphthalene	1800 U	400 U					
Hexachlorocyclopentadiene	1800 U See	400 U					
2,4,6-Trichlorophenol	1800 U	400 U					
2,4,5-Trichlorophenol	4500 U	- 1000 U		Commence of the	是被结果的 。		
1,1'-Biphenyl	1800 U	400 U					and the second second second
2-Chloronaphthalene	1800 U	400 U					
2-Nitroaniline	4500 U	1000 U					and the same transfer and the same and the s
Dimethylphthalate	1800 U	400 1U >#		15 7 7 7 7 F	Commence of the Comment	2002	Care de Season de
2,6-Dinitrotoluene	1800 U	400 U			1	and the contract of the contra	e i selle per l'Endemon TEMens, divisi di
Acenaphthylene	160 EU	- C 44 - 0 L	6.14.				
3-Nitroaniline	4500 U	1000 U				Comment Carlottering Co. 61. 67	Carried and and A.A. A.A. Speciments of many
Acenaphthene	38-400 ELL	400 U Sit					
2,4-Dinitrophenol	4500 U	1000 U				management of the same and the first of the same and	n 1996 () più mar i di Calabelli dei Printe Malinia d'Al-A
4-Nitrophenol	4500 U	1000 U					
Dibenzofuran	180 LJ	400 U				elements and an inferior of the first the first help the f	Electric and additional Plant The decade advised vibral is
2.4-Dinitrotoluene	==1800.4U 3.5≅	400 ∜U **=			- 4.002	State of the state of	
Diethylphthalate	1800 U	400 U					Parity Co.
Fluorene	400 SLJ	400 U					
4-Chlorophenyl-phenyl ether	1800 U	400 U			Committee and the committee of the commi	the the star seems of the	್ರಾವ್ ೨ ಹಂಪಿಕ್≎ಳ ಬಡಳಿಸುವ
4-Nitroaniline	4500 U	1000 U	4-10-10-10-10-10-10-10-10-10-10-10-10-10-				
4.6-Dinitro-2-methylphenol	4500 U	1000 U		The second secon	of manager address of the same of the adjustice of	The English Assessment of the Control of the Contro	ar in inggræsse gamen stam for Tager, her men nå
N-Nitrosodiphenylamine	1800 U	400 U					A Company of the Comp
4-Bromophenyl-phenylether	1800 U	400 U		ermer room man 975 "A van Vanha Festiva HAP (1944) Turn	and the second section of the second section is	n - 45 Sampiteldin Jiji, market in jir ili miljiğ	interes, a e communite l'accid
Hexachlorobenzene	1800 U == 2	2	. 10.00				roman garaga garaga Vilida da sanaga
Atrazine	1800 U	400 U		The second of the second secon	n new states to the first of new tenters, with the	ي نيدا - الأدراء الدراء (- الأناء الأوهاد فالمديد	್ ನಿರ್ವಿಗ್ ಚಿತ್ರವೇ ನಿನ್ನಿ ಕ್ಷಾಗ್ರೆ ಕ್ಷಾಗ್ರೆ ಕ್ಷಾಗ್ರೆ
Pentachlorophenol		1000 U					
Phenanthrene	4400	40 LJ		mark the Mark the Mark The	The second secon	and the season of the second control of the season of the	14 كالمائلية (خالد مدالاتها
Anthracene		⇒ 400 U					لهن داهه المنظم المنظم عاد المدارس المدارسية والمنطقة والمنطقة المنطقة المنطقة المنطقة المنطقة المنطقة المنطقة
Carbazole	710 LJ	400 U	الشيالة الشيالة المستحدد المست	n angarta 19 mai rajandhaga 129 kili 2 2 a	ar vital allottellar variety (12)	للكلكة أستواده وبهوان الكله بأستهار بالاستخار	al serve - Sala James Milale Sugar
· · · · · · · · · · · · · · · · · · ·	1	-					

Note: For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

Case No.:

28007

SDG:

Reviewer: Gene Zhu

Laboratory :

SWOK

Note:

Matrix:

FGG56 Sail

Units:

ug/Kg

SEMIVOLATILE		FLAG		FLAG	FLAG	FLAG	1	FLAG	FLAG	FLAG
EPA SAMPLE NUMBER :	FG-G60		FG-G61				<u> </u>			
								-		
li-n-butylphthalate	1800	U								
luoranthene	7700		79			Property of the Control of the Contr				
yrene	6700							i deci.		
lutyibenzyiphthalate	1800		400							
3'-Dichlorobenzidine	-3×1800	U×33	400	U 5.			-			
lenzo(a)anthracene	3000		34	LJ						
hrysene	3500		54	LU.	and the same of th					
is(2-Ethylhexyl)phthalate	1800	U	400							
i-n-octylphthalate	1800	U	400	U .						
lenzo(b)fluoranthene	2900		75							
enzo(k)fluoranthene	3500		400	برند ∪.				3:9:02		
lenzo(a)pyrene	3200		37	LJ						
ndeno(1(2,3-cd)pyrene	1800		26	LU 🔀	10 - 10 min 20 - 10 min		Party July			
Dibenzo(a,h)anthracene	740	W	400							
lenzo(g.h.l)perylene	2100	9-12-17-15	∰ <u>129</u>	新口类						
Sample wt (g) :	31.2		32.2	!						
%Moisture :	11		23	1						
MINISTRIE.	'''									
Dilution Factor :	5		1	1						
Level :	Low		Low	•						
Number of TIC's :	30		30)						

For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results. Case No. :

28007

SDG:

FGG56

Reviewer : Gene Zhu

Laboratory:

SWOK

Note:

Matrix:

Water

Units: ug/L

SEMIVOLATILE	FLAG	FLAG	FLAG	FLAG	FLAG T	FLAG T	FLAG
EPA SAMPLE NUMBER .	FG-G62	FG-G63	FG-G84			. 2.0	100
		1				<u>-</u>	
		5.55510 (U.S.)	ESECTION UNDER	24.44	TO SECURE OF SECURE	in a Carlotte of Commission of the	
Benzaldehyde	10 U	10 U	10 U		and the second second second second		
Phenol	- 10 U			THE PROPERTY OF	The state of the s	المائية الارد المائة مرم فالمناس والاثارة	
bis-(2-Chloroethyl) ether	المامعية ومالساسيطينيات	10 U	10 U	to the state of th			
2-Chlorophenol	10 U	10 U		Salar a Salar arribrar.	والجواد والمستران والمستوان والمستراة والم	e compresa de la compresa del compresa de la compresa del compresa de la compresa del la compresa de la compresa del la compresa de la compre	an anticological participation of
2-Methylphenol	10 U	التبعضان ومطالته ومستاب الإرابيل ويوسون	10 U	المرابعة المحتمدة المستعددة المستعدد المستعددة المستعدد المستعد المستعدد المستعدد المستعدد المستعدد المس	ساستكاما ماككامتان كمششة وس	ج أمري الرشاعيد والوالوا بعدمات	
2,2'-oxybis(1-Chloropropane)	10 U	10 U			أرار المعاد فعمد معادين للأرابي والماسخون	المأم والأفائد أكافأ مالحالب المعار وعالمنا أكبحار يتاري	
Acetophenone	10 U	The training in which with the state of	10_U				
4-Methylphenol	10 U	10 U	10 U	is-morrow-s -morrishing-s-s	- Marie Marie Marie - Anna - A	taring are suppressed to the suppression of the superior of the supe	
N-Nitroso-di-n-propylamine	10 U	10 U	., og 20 10 U		والمستعدد المشتعد المستعدد		
Hexachloroethane	10 U	10 U		-		بمستربيت مسييات	
Nitrobenzene		10 U	10 U			_ in the first to the con-	
Isophorone	10 U		10 U	Spines and the State of the Sta			****
2-Nitrophenol	, 10 U €		10 U				
2,4-Dimethylphenol	10 U	10 U	10 U	and the same of th			
bis(2-Chloroethoxy)methane	20 JU 30	10 U	10 U				100
2,4-Dichlorophenol	10 U		₹₽.₩.\$10±U#.\$₽			Control of the Contro	Karanga managaran
Naphthalene	The second residence of the second	10 U	10 U				
4-Chloroaniline	10 U	10 -U	32-32-340 (U st -				
Hexachlorobutadiene	10 U	10 U	10 U				
Caprolactam 4-Chloro-3-methylphenol	10 U	10 U 80	200 U 300			~TEX STO	
and the second s	10 U	10 U	10 U				
2-Methyinaphthalene	10 U 3		∕a εα≅010 .U -((α))				
Hexachlorocyclopentadiene 2,4,6-Trichlorophenol	10 U	10 U	10 U				
2,4,5-Trichlorophenol	25 U		.554 3 25 U				775-78-22-22-24
1,1'-Biphenyl	10 U	10 U	10 U				
2-Chloronaphthalene			C 6 C 5 10 U 7 5			्रमञ्जूष ्ठ ्या ।	
2-Nitroaniline	25 U	25 U	25 U	Made and the second of the sec		and the second second	
Dimethylphthalate	10 0		10 U				
2,3-Dinitrotoluene	10 U	10 U	10 U	illi sani i ipailit kiin kii sa		المفتلف سنحرب ليهانا فالتفاقكسي سيما	المراجعة والمحسدات المارات
Acenaphthylene	10 0		∴ 4.5-10 U	Sa Charles			
3-Nitroaniline	25 U	25 U	25 U	والمستقل المستناف الم		ى ئەدەكىرىسىكىكىرى ئ ىكىگەر ىك كىكىگە	
Acenaphthene	10 U %	•2 a 20 ∉U = €		Sekoloman a			
2.4-Dinitrophenol	25 U	25 U	25 U	a decimal and decimal and the second	And the second s	alah merikan dalah dan dalam berbuah dalam berbuah dalam berbuah berbu	
4-Nitrophenol	25 U	° 125 °U 32	5/418/20125 U 148€	egas egases	Street Section 1	PERSONAL STATE	
Dibenzofuran	10 U	10 U	10 U	To be have and of his resid of the office of the	Control of the second s		
2,4-Dinitrotoluene	10 U	10 U	10 U				
Diethylphthalate	10 U	10 U	0.5 LJ	The second secon			ar i vergi. He are is killed discontinuity which
Fluorene	10 U	10 - U	10 U				
4-Chlorophenyl-phenyl ether	10 U	10 U	10 U			The state of the s	- 2- 2-0
4-Nitroaniline	25 Ü	25 U	25 U				
4,6-Dinitro-2-methylphenol	25 U	25 U	25 U				
N-Nitrosodiphenylamine	10 U	10 U	10 U				
4-Bromophenyl-phenylether	10 U	10 U	10 U				
Hexachlorobenzene	10 U	10 U	10 U 15	*****			
Arraine	10 U	10 U	10 U				
Pertachlorophenol	25 U	25 U 🕠	25 U		The same of the sa		
Phenanthrene	10 U	10 U	10 U				
Anthracene	10 U	10 U	∵ 10 U				
Carbazole	10 U	10 U	10 U				
Di-n-butylphthalate	10 U	and the state of	7-5-50.7 LJ		A STATE OF THE PARTY OF THE PAR		
Fluoranthene	10 U	10 U	10 U		****		
Pyrene	10 U	10 U	10 U		The second secon	دوريون بهدما هو معاطرات استخوات درگاه ماهارات این اگریات داد	And the second s
Burylbenzylphthalate	"10 U "	10 U	10 U				
	•						

For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

Case No. :

28007

SDG:

FGG56

Water

Reviewer: Gene Zhu

Laboratory:

swok

Matrix:

Units: ug/L

SEMIVOLATILE	FLAG	FLAC	F	LAG	FLAG	FLAG	FLAG I	FLAG
EPA SAMPLE NUMBER :	FG-G62	FG-G63	FG-G64					
3,3'-Dichlorobenzidine	rt of 10 U -	🚣 ب 10 U ڪريند				32.5		
Benzo(a)anthracene	10 U	10 U	10 U					
Chrysene	10 U 45	10 U	U					
bis(2-Ethylhexyl)phthalate	10 U	10 U	10 U					
Di-n-octylphthalate	10 U	10 U	10 U					
Benzo(b)fluoranthene	10 U	10 U	10 U					
Benzo(k)fluoranthene	10 U	10 U	10 · U					12 12 12 12 12 12 12 12 12 12 12 12 12 1
Benzo(a)pyrene	10 U	10 U	10 U					
Indeno(1,2,3-cd)pyrene	- 2 - 10 U		∵i10 U					
Dibenzo(a,h)anthracene	10 U	10 U	10 U					
Benzo(g,h,l)perylene	30 U	10 U =	20 € 110 × U	- 5/2				
Volume (mi) :	1000	1000	1000					
Dilution Factor :	1	1	1					
Number of TiC's :	3	3	7					

Note:

For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

Case No. :

28007

SDG:

FGG56

Soil

Reviewer: Gene Zhu

Laboratory:

SWOK

Matrix:

Units:

ug/Kg

PESTICIDES/PCBs	FLAG	FLAG	FLAG	FLAG	FLAG	FLAG	FLAG
EPA SAMPLE NUMBER :	FG-G56	FG-G56DL	FG-G57	FG-G57DL	FG-G58	FG-G59	FG-G60
			······································				7. 0-000
alpha-BHC	2.0 U 35	- 20 U •	2.1 U	21.0 •	2.0 U	22-0	7.9 U 65
beta-BHC	2.0 U	20 U *	2.1 U	21 U •	2.0 U	2.2 U	1.9 U
delta-BHC	2.0 U	20 U	- 21 U	21.U°	2.0 U 5	22 U	3 - 4 - 1.9 U 3 5
gamma-BHC (Lindane)	2.0 U	20 U *	2.1 U	21 U	2.0 U	2.2 U	1,9 U
Heptachlor	3.0 UM -	20 U		21 U *	2.0 U 🔆	2.2 U	1.9 U
Aldrin	2.0 U	20 U *	2.1 U	21 U •	2.0 U	2.2 U	1.9 U
Heptachlor epoxide	0.90 LJ	20 ,∪ •	2.1 U -	21 U •	20 U.3	2.2 U	27-19 U 32
Endosulfan I	2.0 U	20 U *	2.1 U	21 U *	2.0 U	2.2 U	1.9 U
Dieldrin	2.1 LJ	39 U	4.1 U	41 U*	5.4	0.83 LJ	3.6 U
4,4'-DDE	91	86 J^	7.9 Jv	84	3.8 U	4.2 U	5.7 J
Endrin	2.24.7 aJ 5	₹ 939 U •	4.1 U	41 .U *	ਤੌੜ 3.8 U ਤ	3.2 ÷LJ	ري ل _ا 4.8 مين
Endosuifan II	4.0 J	10 *	4.1 U	41 U °	3.8 U	0.58 LJ	3.6 U
4.4-DDD	્રેફે 6.6 ે J .~ે		4.1 U	41 eU *	3.8 U 💥	~ 0.95 FLJ	3.6 U.S
Endosulfan sulfate	3.9 U	39 U •	4.1 U	41 U *	3.8 U	4.2 U	3.6 U
COOK STATE OF STATE OF	170	180 - J^	29 Jv 7	190	ન્દ્રું ે.∵3.8 U કેંિ	S-7 13 (2006)	3.6 UJV
Methoxychlor	2.7 LJ	200 U *	21 U	210 U*	20 U	22 U	19 U
Endrin ketone	3 CO (4) 6 3 6 6	₩ #39 U *	16	41 U	3.8 U 🦖	4.2 U	3.6 U -5
Endrin aldehyde	1.8 LJ	39 U *	2.1 LJ	41 U °	3.8 U	4.2 U	3.6 U
alpha-Chlordane	3 (11 SJ)	9.9	3.1 Jv	11.5	2.0 U	22 U s	::::1.9 · U :
gamma-Chlordane	7.0 B	6.9	3.8 UM	8.5	2.0 U	7.8 B	7.0 JB
Toxaphene	ු ව 200 U ිම	,2000 U 🖜	210 -U	2100 U •	200 U	્રે. 220 U ેં	190 U
Aroclar-1016	39 U	390 U •	41 U	410 U*	38 U	42 U	36 U
Arodor-1221	78 U	∵ 780 U °		820 U *	78 Ù	85 U .	74 U. 45
Aroclor-1232	39 U	390 U °	41 U	410 U*	38 U	42 U	36 U
Arodor-1242	~ 439 U	୍ଟି 390 U 🎎	41 U	410 U	ු 38 U බ්	.42 U 🦠	36 U 📡
Araciar-1248	39 U	390 U •	41 U	410 U *	38 U	42 U	36 U
Arodor-1254	39 U	390 U	- 41 U	410 U •	38 U	42 U	36_U
Arodor-1260	39 U	390 U •	41 U	410 U	38 U	42 U	36 U
Samala wa (n)	30.6	30.6	30.1	30.1	20.2		
Sample wt (g) :	30.0	30.0	30.1	30.1	30.8	30	30.6
%Moistur e :	16	16	19	19	16	21	11
Dilution Factor :	1	10	1	10	1	1	1

Note:

For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

Case No. :

28007

SDG:

FGG56

Reviewer: Gene Zhu

Laboratory:

SWOK

Matrix:

Sail

Units:

ug/Kg

PESTICIDES/PCBs	FLAG	FLAG (FLAG T	FLAG	FLAG	FLAG I	FLAG
EPA SAMPLE NUMBER :	FG-G61	FG-G61DL		100	1550	المحاد	FLAG
EPA SAMPLE NOMBER.	FG-G01	1 3-30100					
alpha-8HC	2271	€ \$227U - 657					
beta-8HC	2.2 U	22 U *		بالمنافعة والمتحدث والمتحدث والمتحدد		مسترسين المستوانية والمستوانية	
delta-BHC		22 U 7					
gamma-BHC (Lindane)	2.2 U	22 U °					
Heptachlor		22 ·U	The second second				
Aldrin	2.2 U	22 U •		Admin Ties Darkel a <u>ssisted by Maria 1998</u> , y		The Price of the Price of Land Control of the Price of th	
Heotachlor epoxide	22 U	= 22 U • 30 •					
Endosulfan I	2.2 U	22 U •				- Paradian In il Sin Indonesia ancienza di Carata	ريد يكانيك بيكن أشاه من مصور مدا
Diekdrin		5 42 U 3		ordina va daj Stat			
4,4'-DDE	6.8 J	8.8					
Endrin	10.0 US	22 US	一口以外共工程				
Endosulfan II	0.94 LJ	42 U *					
4.4'-DDD (1995)	3.2.U	42 U	"对外,但是多少。 "		1000		
Endosulfan sulfate	4.2 U	42 U*					
4.4-DDT estation in the second	75542 U.S.	42.U					
Methoxychlor	22 U	220 U*					
Endrin ketone	30-4-424U 0				7 20 7 12 1	THE RESERVE	
Endrin aldehyde	4.1 LJ	42 U *					
alpha-Chlordane		22 JUNE			Service Control		
gamma-Chlordane	9.3 JB	8.0 *				·	
Toxaphene (A)	-220 U -	2200. U - W		Marine Land			
Arodor-1016	42 U	420 U *					
Arodor-1221	285÷U	្នា ន្ត850 ្ហ ្វ ន្ត្រ		7.0			
Arodor-1232	42 U	420 U *					
Arodor-1242	543 A 2 7 U → 1						
Arodor-1248	42 U	420 U *					
Aroclor-1254	42 U =						
Arodor-1260	42 U	420 U *					
Sample wt (g) :	30.6	30.6					
%Moisture :	23	23					
		40					
Dilution Factor :	<u> </u> 1	10					

Note:

For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

Case No. :

28007

SDG:

FGG56

Reviewer: Gene Zhu

Laboratory:

swok

Matrix:

Water

Units: ug/L

PESTICIDES/PC8s	FLAG	I FLA	G FLA	GT FLAG	FLAG	I FLAG	FLAG
EPA SAMPLE NUMBER :	FG-G62	FG-G63	FG-G64		i ·		
CANAGE EL NOMBER.	FG-G02	17-3-33	1. 0-004	<u>, </u>	<u>.l</u>	<u></u>	
alpha-BHC	500.050 U (E)	0.050 ·U	₩ 0.050 U	South a type II on a distance			Section of the second
beta-BHC	0.050 U	0.050 U	0.050 U	ه د مصاحه دهم است من ۲۵ داخگشتر داشتیم		THE RESERVE TO A PROPERTY AND A PARTY OF THE	And the second s
delta-BHC		0.050 U					
gamma-BHC (Lindane)	0.050 U	0.050 U	0.050 U		المالات المالية	ar Madami varandillika kita sami kirabyi Mindesi	رُول جون ن المسلم سيفيطوه كانه ما ١٠٥٠
Heptachlor	0.050 U	0.050 U	0.050 U			1.50	
Aldrin	0.050 U	0.050 U	0,050 U	Terretoria and the major and a ferre and the ferre			
Heptachlor epoxide	0.050 U 3		0.050 U	20 TO 10 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			
Endosulfan I	0.050 U	0.050 U	0.050 U	المستاجه فلأنث مبسه فرمسته أو الانتخاصة	<u> </u>	ريال پيدال جنديد ب بنگاه اطاق "است. الساد به	والمراجع والمستناد والمستناء والمستناد والمستاد والمستناد والمستناد والمستنا
Dieldrin	0.10 U		0.10 U		THE THE REAL		-:
4.4'-DCE	0.10 U	0.10 U	0.10 U		and the second s	te un municipalità di	
Endrin			0.10 U				
Endosuifan II	0.10 U	0.10 U	0.10 U	And the second s	Marian Chairle Sides Williams and Marian	the section and child statement to the said and the said	
4.44DDD	32 0.10 U		0.10 U.				
Endosulfan sulfate	0.10 U	0.10 U	0.10 U				
442DDD:				Carryon Carryon			
Methoxychlor	0.50 U	0.50 U	0.50 U				
Endrin ketone		0.10 U					5-20-20-20-20-20-20-20-20-20-20-20-20-20-
Endrin aldehyde	0.10 U	0.10 U	0.10 U			er. enderski, mannet	THE STATE OF THE PARTY OF THE P
alpha-Chlordane	0.050 dU		1200 A O .050 FU				
gamma-Chiordane	0.050 U	0.054 J	0.050 U				
Toxaphene			50212020	- In the Market Control			
Arodor-1016	1.0 U	1.0 U	1.0 U	Marrie L'Allerin, and in the second			
Arodor-1221	2.0 U		- 22 20 U	TOWN TAX BEAUTY IN THE			Contract Contract Contract
Aroclor-1232	1.0 U	1.0 U	1.0 U	de la companya de la			
Arodor-1242	1	1.0 .U	1.0 U				
Aroclor-1248	1.0 U	1.0 U	1.0 U	early intelligent into a second			
Aroclor-1254		1.0 U €					
Arodor-1260	1.0 U	1.0 U	1.0 U				
	""	•					
Volume (mi) :	1000	1000	1000				
(,							
Cilution Factor :	1	1	1				

Note:

For the results listed in the Data Summary Table, ESAT has replaced the laboratory assigned flags with ESAT Organic Data Qualifiers. The ESAT flags indicate the technical usability of the reported results.

INORGANIC/ORGANIC COMPLETE SDG FILE (CSF) INVENTORY CHECKLIST

ase No.	28007	SDG No.	FGG56	SDG N	os. To Follow		SAS No.	Date R	.ec <u>(</u>)5/19/00
EPA Lab	D:	SWOK				ORIGINALS		YES	МО	N/A
Lab Loc	ation:	1700 West Alban	v, Broken A	rrow, OK	74012	CUSTODY SEALS				_
Region:	_	6 Audit No	.: 28007	/FGG56		1. Present on package?		x		
Re-Subm	nitted CSF?	Yes		No	X	2. Intact upon receipt?		х		
Box No(s):	1				FORM DC-2				_
COMME						3. Numbering scheme ac	curate?	x		
						4. Are enclosed documer	nts listed?	X		_
<u>.em</u>	<u>Descripti</u>	<u>ion</u>				5. Are listed documents	enclosed?	х		+
3	Two sect	ions of Form DC	-1, p. 1423,	reported i	nconsistent	FORM DC-1				+
	cooler te clarificat	mperatures. The	laboratory w	as contacte	ed for	6. Present?		x		
	ciarificat	ion.				7. Complete?		x	 -	+
						8. Accurate?			Х	_
						CHAIN-OF-CUSTODY RECORD(s)				1
						9. Signed?		x		
						10. Dated?		X	******	
						TRAFFIC REPORT(s) PACKING LIST(s)		7		
						11. Signed?		x		
						12. Dated?		x		-
						AIRBILLS/AIRBILL ST	TICKER			-
						13. Present?	· · · · · · · · · · · · · · · · · · ·	\mathbf{x}		
						14. Signed?		x		+
						15. Dated?		x		
						SAMPLE TAGS				+
						16. Does DC-1 list tags as	s being included?	x		
						17. Present?	<u> </u>	x		+
						OTHER DOCUMENTS	· · · · · · · · · · · · · · · · · · ·			
						18. Complete?	• •	x		
						19. Legible?		$\frac{x}{x}$		+
						20. Original?		1-	x	+-
						20a.If "NO", does the cop	v indicate	x		
Over for	additional c	omments.				where original docume				
ا في مثلين ۾			7			Tong View Earl ECAT	Data Pavious-		05:-	10000
Audited b		to un	The			Tseng-Ying Fan/ ESAT	Data Reviewer	Date	07/1	4/2000
Audited b	y:							Date		
Audited b	y: _	. •						Date		
	•—————————————————————————————————————		Signature			Printed Nam	ne/Title		•	
]	ГО ВЕ СОМР	LETED BY CEAT				
Date I	Record by C	EAT:			Da	ite Entered:	Date Reviewed:			
	Entere	d by:					_		·· ·· ·· ·· ·· ·· ·· ·· ·· ·· ·· ·· ··	
	Reviewe	<u> </u>								
			Signature	 3		F	Printed Name/Title			

REFERENCE 8

OKLAHOMA GEOLOGICAL SURVEY Charles J. Mankin, *Director*


HYDROLOGIC ATLAS 5

RECONNAISSANCE OF THE WATER RESOURCES OF THE CLINTON QUADRANGLE WEST-CENTRAL OKLAHOMA

By

JERRY E. CARR and DEROY L. BERGMAN U.S. Geological Survey

Prepared in cooperation with UNITED STATES GEOLOGICAL SURVEY



Scale 1:250,000

The University of Oklahoma Norman 1976 Second Printing, 1992

The stratigraphic nomenclature and age determinations used herein are those accepted by the Oklahoma Geological Survey and do not necessarily agree with those of the U.S. Geological Survey.



DUNE SAND

Wind-blown sand; thickness ranges from a thin veneer to about



ALLUVIUM

Stream-laid deposits of sand, silt, clay, and gravel; thickness ranges from 0 to about 170 feet.



TERRACE DEPOSITS

Stream-laid deposits of sand, silt, clay, gravel, and volcanic ash; thickness ranges from 0 to about $120~{\rm feet}.$

UNCONFORMIT



OGALLALA FORMATION

Gray to light-brown, fine- to medium-grained sand with some clay, silt, gravel, volcanic ash, and caliche beds; locally cemented by calcium carbonate. Thickness ranges from 0 to about 320 feet. The formation thins eastward.

UNCONFORMITY



KIOWA FORMATION and DAKOTA GROUP

Outliers of the Kiowa Formation, Kk, dark-gray shale with some thin beds of fossiliferous tan limestone, range in thickness from a few feet to about 20 feet. Associated in some places is a 5- to 10-foot, gray to brown, coarse-grained sandstone and conglomerate assigned to the overlying Dakota Group, Kd (lower sandstone part). Several hundred outliers occur (generally too small to show on map) west of U.S. Highway 183, resting on units ranging from the Rush Springs Formation to the Elk City Sandstone.

JNCONFORMITY



ELK CITY SANDSTONE

Reddish-brown, fine-grained sandstone with minor amounts of silt and clay, weakly cemented by iron oxide, calcium carbonate, and gypsum; maximum thickness 185 feet, top eroded.



DOXEY SHALE

Reddish-brown, silty shale and siltstone; thickness, about 190 feet.



CLOUD CHIEF FORMATION

Reddish-brown to orange-brown shale, interbedded with siltstone and sandstone in the middle part and some dolomite and much gypsum in lower part; thickness about 400 feet, thinning northward to about 175 feet. The Moccasin Creek Gypsum Member is at the base.




WHITEHORSE GROUP


Predominantly orange-brown, fine-grained sandstone, the White-horse Group is mapped as Pwh where separate formations have not been distinguished and as the Rush Springs Formation and the Marlow Formation where identified.

Rush Springs Formation, Pr, orange-brown, cross-bedded, fine-grained sandstone with some dolomite and gypsum beds. Thickness, about 300 feet, thinning northward to about 186 feet. The Weatherford Gypsum Bed, Prw, is about 30 to 60 feet below the ton (manned in southeastern part only)


the top (mapped in southeastern part only).

Marlow Formation, Pm, orange-brown, fine-grained sandstone and siltstone, about 100 to 130 feet thick, thinning northward. This formation has 2 gypsum and (or) dolomite beds in upper 20 feet—the Emanuel Bed (at top) and the Relay Creek Bed (20 feet below top). Two thin, pink shales occur; the first is 1 foot below the top (Gracemont) and the second is 55 feet above the base (unnamed). The Verden Sandstone Lentil, Pmv, is a coarse-grained, calcareous, fossiliferous sandstone (2 to 10 feet thick) that occurs in the middle of the Marlow, about 25 feet below the Relay Creek Bed and 85 to 95 feet above the base.





CONTOUR INTERVAL 100 FEET
WITH SUPPLEMENTARY CONTOURS AT 50-FOOT INTERVALS
DATUM: MEAN SEA LEVEL



Major Aquifers



Alluvium and terrace deposits

Along large streams, deposits consist of clay and silt at the surface, grading downward into coarse sand and gravel at the base. Water is available from saturated layers of sand and gravel, and yields are highest where the coarse sand and gravel layers are thickest. In areas where an alluvium or terrace aquifer overlies the Rush Springs Sandstone, water is available from either aquifer.



Ogallala Formation

Semiconsolidated layers of fine to medium sand, clay, silt, and gravel. Average thickness is probably about 100 feet.



Elk City Sandstone

Mainly fine-grained sandstone with minor amounts of silt and clay. Maximum thickness is about 185 feet; formation thins toward the edges.



Rush Springs Sandstone and Marlow Formation

The Rush Springs Sandstone, which has a maximum thickness of about 300 feet, consists mainly of fine-grained sandstone with some dolomite, shale, and gypsum beds. The Marlow Formation has a maximum thickness of about 100 feet and consists of fine-grained sandstone with much gypsum and shale.



Blaine Formation

Mainly shale, interbedded with gypsum and dolomite. Maximum thickness is about 200 feet. Water is available from erratically occurring solution channels in the gypsum.

YIELD OF MAJOR AQUIFERS, RANGE IN GALLONS PER MINUTE



More than 300



150 to 300



25 to 150

Yield of Remaining Areas, in Gallons per Minute



Generally less than 25

Note: Evaluation of yield areas assumes that drilled wells will be completed in aquifer's total thickness. Locally, individual wells in any of the areas shown on the map may yield more or less than is indicated for that area.

Area boundary; dashed where approximately located

Information unknown

e Estimated yield

Well yield less than amount shown

• \frac{28}{5}
73

Well

Upper number is depth of well, in feet; middle number is depth to water, in feet below land surface; lower number is yield of well, in gallons per minute. Where only two numbers are shown, they are well depth and depth to water; where only one number is shown, it is well depth.



Well field

Upper number is number of wells in field; second number is average depth of wells, in feet; third number is average water level, in feet below land surface; fourth number is average well yield, in gallons per minute.

å 400 30


Flowing well

Upper number is depth of well, in feet; lower number is rate of flow, in gallons per minute.

2 , 2 ,

Spring

Number beside spring symbol is yield in gallons per minute.





Chemical quality of water generally good

These areas generally yield water containing 500 mg/l (milligrams per liter) or less of dissolved solids, which is satisfactory for most uses. In a few local areas, dissolved solids may exceed 500 mg/l. The presence of an undesirable constituent or excessive hardness may make the water unsuitable for some purposes.



Chemical quality of water generally fair

These areas generally yield water containing 500 to 1,000 mg/l of dissolved solids, although in a few local areas dissolved solids may exceed 1,000 mg/l. The presence of an undesirable constituent or excessive hardness may make the water unsuitable for some purposes.



Chemical quality of water generally poor

These areas generally yield water containing more than 1,000 mg/l of dissolved solids. Excessive amounts of dissolved minerals limit the use of this water for most purposes.

Area boundary; dashed where approximately located

Source of Ground Water for Chemical-Quality Evaluation



Alluvium and terrace deposits


Pattern indicates that source of ground water used in chemical-quality evaluation is alluvium and terrace deposits; absence of pattern generally indicates Ogallala and older formations as source. Note: alluvium and terrace deposits may overlie Ogallala and older formations in any area, but only one source is evaluated for chemical quality within a given area.

WATER-QUALITY DIAGRAMS

These diagrams show the general chemical character of ground water and are based on analyses of water samples from wells or springs at the indicated points. The size of a diagram is an indication of dissolved-solids content—the larger the area the greater the dissolved-solids content—and the numbers above the diagrams reflect the quantity of dissolved solids in milligrams per liter.

reflect the quantity of dissolved solids in milligrams per liter.

Variations in diagram's shape show variations in chemical character and in relative proportions of chemical constituents. Ionic concentrations are plotted for sodium plus potassium (Na + K), calcium plus magnesium (Ca + Mg), chloride (Cl), bicarbonate (HCO₃), and sulfate (SO₄). Anions (negatively charged ions) are plotted to the right of the center line, and cations (positively charged ions) are plotted to the left. The scale below can be used to read the value of milliequivalents per liter of a particular ion. Once the value is obtained in milliequivalents per liter, ionic concentrations can be converted to milligrams by using the factors given in parentheses (23, 50, 35, 61, and 48) beside the ions. The number derived by multiplying the appropriate factor by the milliequivalents per liter of the Cl, HCO₃, or SO₄ ion is the concentration as expressed in milligrams per liter, and the resulting number for Na + K is the concentration as Na. The resulting number for Ca + Mg is the hardness as CaCO₃.



MILLIEQUIVALENTS PER LITER





Figure 7. Map showing distribution of precipitation and runoff.

(Precipitation data from the National Oceanic and Atmospheric Administration)

24

Line of equal mean annual precipitation, in inches, based on normal annual precipitation, 1931–60



Graph of normal monthly precipitation

Figure in upper right of graph is normal annual precipitation, in inches

◆ Cheyenne Weather station

Average yearly runoff, in inches



0.5 to 1.0



1.0 to 1.5



1.5 to 2.0



> 2.0

REFERENCE 9

SITE SAFETY PLAN FOR RAY WICHERT PROPERTY SITE INVESTIGATION LEVEL D PERSONNEL PROTECTIVE EQUIPMENT OPERATIONS

The Ray Wichert Property (CERCLIS No. OKD987095049) is approximately 2 acres in size and occurs on an urban tract of land located in Custer County, Oklahoma. The legal description for the site is the SW/4, NE/4, NE/4, Section 27, T12N, R17W, and the coordinates are west longitude 98° 58' 41" and north latitude 35° 29' 24". There are several rubble piles located on-site that were from the Sooner Dial Company site, which was an airplane instrument dial refurbishing plant. The purpose of this sampling event is to determine if there is contaminated soil attributable to the rubble piles.

The entry objective is to collect 6 surface soil samples. The samples are anticipated to be of low concentration. Sampling is scheduled for April, 2000.

The site has been identified by the OES as a Type I site requiring Level D protective clothing. A Type I site is one at which there is no apparent hazard or at least no hazard posing an immediate danger to life and health. Specifically, it is a site at which:

- (a) The wastes are in an unconfined area with good air circulation;
- (b) There are no unknown odors or odors of known hazardous materials;
- (c) There are no chemical disposal lagoons or leachate ponds, and surface water appears natural and clean;
- (d) Plants and animals appear normal;
- (e) There is visible or historical evidence of accessibility to humans without ill effects.

Such a site can be entered and visually appraised without use of respirators or skin protection. The contaminated soil and sediment at the site is in an open, well ventilated area which should not pose an immediate or delayed threat to respiratory organs or to exposed skin. No leachate ponds are present on the site. Level D clothing, which may include cotton coveralls, safety boots, safety glasses, hard hat, work gloves, and a Robertshaw escape mask, should provide adequate protection to workers on the site. The level of protection will be increased should conditions warrant additional respiratory or skin protection.

If the OES field team encounters upexpected chemical hazards, such as containers of unknown liquids or substances, it will evacuate the site, re-evaluate site conditions, increase the level of protection, then re-enter the site and attempt to identify the hazardous substance. If the OES field team determines that it cannot safely manage the hazardous substance, work on the site will be suspended until after the National Response Center has removed the hazardous material.

Control boundaries delineating an Exclusion Zone, Contamination Reduction Zone, and Support Zone will not be established on-site during the sampling activities because the Ray Wichert Property is a Type I site. A Gastech model GX-82 HS combustible gas/oxygen/hydrogen sulfide detector will be available on-site and will be used if unexpected chemical hazards are encountered or if buildings must be entered.

A map showing the boundaries of the site and the sampling locations is included with the site sampling plan.

A Site Emergency Route Map shows the route from the site to the nearest hospital, which is located 10 minutes away from the site in Clinton, Oklahoma. A first-aid kit, snake bite kit, and emergency eye wash will be provided to each sampling crew/vehicle on-site. The eye wash at the field base camp will be kept within arm's reach of the sample preservation station where nitric acid and sodium hydroxide are used. A cell phone or two-way radio will be provided to each sampling crew/vehicle for communication on-site.

Specific aspects of the site safety plan dealing with the OES medical program, health and safety training of OES personnel, standard operating procedures and safety practices at hazardous waste sites, and the development of specific site safety plans are covered in detail in Chapter 4 of the OES Quality Assurance Project Plan which is on file with the EPA/CERCLA Region 6 office in Dallas.

All OES field team members will review the site safety plan before work begins. Certain aspects of this plan may be modified by the OES Project Manager whenever warranted by on-site conditions.

CHEROKEE NATION OF OKLAHOMA LEVEL D SITE SAFETY PLAN

A. SITE DESCRIPTION

DATE: April, 2000

LOCATION:

Ray Wichert Property: SW/4, NE/4, NE/4, Section 27, T12N, R17W, North Latitude 35° 29' 24" and West Longitude 98° 58' 41" in Custer County, Oklahoma.

HAZARDS:

Possible soil/sediment contamination.

WASTE CHARACTERISTICS/HAZARDS:

No apparent chemical hazards that are immediately dangerous to life and health.

PHYSICAL HAZARDS:

Concrete blocks, bricks, and rubble piles may present tripping hazard.

AREA AFFECTED:

Up to 2 acres

SURROUNDING POPULATION:

0 persons within 200 feet of the site; 1,341 people within 0-1 mile.

TOPOGRAPHY:

The Ray Wichert Property site lies in the Western Redbed Plains in the Anadarko Basin. This area is characterized by gently rolling hills of flat-lying red Permian sandstones and shales. Rock formations include Quaternary alluvium and terrace deposits that consists of streamlaid deposits of sand, silt, and clay; and the Cloud Chief Formation and Rush Springs Formation. These formations consist of shale, siltstone, and sandstone of Permian age.

WEATHER CONDITIONS:

The climate of Custer County is a warm, temperate climate. The temperature the day of sampling is expected to be 74° Fahrenheit. Average annual rainfall is 27.8 inches. About 80 percent of the rainfall occurs during the frost-free season from April to September. May is the wettest month and the driest is January.

ADDITIONAL INFORMATION:

The Oklahoma Bank and Trust Company of Clinton, OK has owned the property since 1987, although they are not the producers of the rubble piles located on-site. The site contains rubble from the Sooner Dial plant, which was an airplane instrument refurbishing plant located one mile from the site. The plant used radium-containing paint due to its luminous characteristics. Although sampling for radium contamination was performed in the past by the State of Oklahoma, a Site Investigation was not performed. The Cherokee Nation OES believes that there may be additional contamination from heavy metals or other chemicals on site that were used by the plant. Access to the site is unrestricted and heavy vegetation is present.

B. ENTRY OBJECTIVES

Collect 6 surface soil samples.

C. ON-SITE ORGANIZATION AND COORDINATION

Project Manager:

Kent Curtis

Assistant Project Manager:

Vacant

Field Team Leader:

Tom Elkins

Field Team Members:

Brad Asbill, Jason White, Randall Gee,

Travis Waldo, Melinda Sims

Public Information Officer:

Tom Elkins

Tribal Representative:

Landowner/Neighbors:

Oklahoma Bank and Trust Company

Contractors:

N/A

All personnel arriving or departing the site should log in and out with the Field Team Leader. All activities on site must be cleared through the Project Manager and/or Assistant Project Manager.

D. ON-SITE CONTROL

Brad Asbill has been designated to coordinate access control and security on-site.

The on-site Command Post and staging areas have been established at a meeting place at an abandoned parking lot 300 feet south of the rubble piles.

The prevailing wind conditions are: variable

Control boundaries have been established, and the Exclusion Zone (the contaminated area), hotline, Contamination Reduction Zone, and Support Zone (clean area) have been identified and designated as follows: Control boundaries will be established during sampling on the site only if the Project Manager and the Field Team Leader concur that certain site specific conditions (for example, waste sources within buildings, electrical or explosion hazards, leachate ponds) warrant the establishment of such boundaries. Such boundaries will be marked with fencing (when practical), yellow tape, and/or with signs. A map showing these boundaries will be included with this site safety plan, and a map showing the locations of sampling sites is included with the site sampling plan. These boundaries are identified by (describe): N/A

The on-site command post/field base camp will be established upwind of on-site waste sources or at a safe distance from such sources. When practical, the command post will be within sight of all parts of the site at which field sampling crews will be active. One or more OES field team members/leaders will be present at the command post at all times during field sampling activities and will maintain custody of all samples collected on-site. A cell phone and/or two way radio will be present at the command post along with a first aid kit, snake bite and insect bite kits, emergency eye wash, hand washing station, tool kit, a combustible gas/oxygen/hydrogen sulfide monitor, and, if necessary, other monitoring equipment (e.g., Geiger counter). Copies of the site safety plan will be at the command post and will be provided to each sampling crew/vehicle on site.

E. HAZARD EVALUATION

í

The following substance(s) are known or suspected to be on site. The primary hazards of each are identified.

Substances Involved Concentrations (If Known) Primary Hazards

organics/inorganics low physical

The following additional hazards are expected on site: N/A

Have hazardous substance information form(s) for the involved substance(s) been completed and attached: No

The following physical hazards are expected on site (describe):

Rubble piles may present tripping hazard.

F. PERSONAL PROTECTIVE EQUIPMENT

Based on evaluation of potential hazards, the following levels of personal protection have been designated for the applicable work areas or tasks:

Location	Job Function	Level of Protection
Exclusion Zone	Collect samples	A B C D Other
Contamination	Decontaminate	A B C D Other
Reduction Zone	sampling equipment	A B C D Other

Specific protective equipment for each level of protection is as follows:

Level A	Level C
Fully-encapsulating suit	Splash gear (type) &
SCBA	Tyvek suits
(disposable overalls)	Full-face canister respirator
	boots & boot covers
	hard hat
	protective gloves (2 pairs)
. <u>Level B</u>	<u>Level D</u>
Splash gear (type)	tyvek suits
Nomex inflammable coveralls or	protective boots & covers
100% cotton coveralls	safety glasses (clear lens)
SCBA	hard hat
	protective gloves
-	Robert Shaw Escape Mask

In certain site specific situations, with the approval of the OES Project Manager and the OES Field Team Leader, OES personnel may use modified Level C (tyvek suits in place of splash gear) or modified Level D (use of only protective boots and gloves, without tyvek suits, hard hat, and glasses) during on-site activities.

OES safety glasses will provide front and side protection and will have clear lenses that will not interfere with the perception of colors. Protective gloves may be silvershield, nomex, or vinyl.

The following protective clothing materials are required for the involved substances at this site:

<u>Substance</u> <u>Material</u>

Organics/inorganics

protective gloves

If air-purifying respirators are authorized, <u>Wilson T45 Combination Cartridges</u> are the appropriate canister for use with the involved substances and concentrations. A competent OES individual has determined that all criteria (OSHA PELs) for using this type of respiratory protection have been met and that all OES personnel who will wear respirators during on-site activities have been properly fit tested with full-face canister respirators.

NO CHANGES TO THE SPECIFIED LEVELS OF PROTECTION SHALL BE MADE WITHOUT THE APPROVAL OF THE FIELD TEAM LEADER AND THE PROJECT MANAGER AND/OR ASSISTANT PROJECT MANAGER.

G. **ON-SITE WORK PLANS**

Work party(s) consisting of 2 or 3 persons will perform the following tasks:

Field Team Leader: Tom Elkins

Support &

Jason White

Decontamination

Zones

Work Party #1:

Melinda Sims

Sampling

Brad Asbill

Work Party #2:

Travis Waldo

Sampling

Randall Gee

Other:

*Rescue Team:

Field Team Leaders or

one of the work parties

*(required for entries to IDLH environments)

Procedure for handling any hazardous wastes encountered: Evacuate site, evaluate level of personnel protection, re-enter site to identify waste; call National Response Center if conditions warrant.

The work party(s) were briefed on the contents of this plan: YES

H. COMMUNICATION PROCEDURES

A cell phone and/or two-way radio is provided to each field sampling team/vehicle on site. Each team/vehicle must be provided with the cell phone numbers of all other teams/vehicles. When radios are used, channel 1 has been designated as the Tribal radio frequency for personnel in the Exclusion Zone. All other onsite communications will use channel 2.

Personnel working in the Exclusion Zone in Levels A, B, or C personal protective equipment should remain in constant telephone/radio communication or within sight of the Project Team Leader. Any failure of telephone/radio communication requires an evaluation of whether personnel should leave the Exclusion Zone. Personnel working in the Exclusion Zone in Level D personal protective equipment need not be in constant communication with the Project Team Leader but must have quick access to telephone, radio, and/or visual communication with the Project Team Leader.

Verbal warning or four blasts of a vehicle horn are the emergency signals to indicate that all personnel should leave the Exclusion Zone.

The following standard hand signals will be used in case of failure of radio communications:

Hand gripping throat Out of air, can't breathe Grip partner's wrist or both hands around waist Hands on top of head Thumbs up Thumbs down

Leave area immediately Need assistance OK, I am all right, I understand No, negative

Telephone communication to the Command Post	should be es	stablished as soon a	s practicable.	The
telephone number is (check one): 453-7434	_; 453-7441	; 453-7475	_; 453-7497_	
other				

I. **DECONTAMINATION PROCEDURES**

Personnel and equipment leaving the Exclusion Zone shall be thoroughly decontaminated. The standard level 4 decontamination protocol shall be used with the following decontamination (OTHER) The work parties leaving the (2)____(3)____ stations: (1) exclusion zone or sampling areas will remove their protective gloves, tyvek suits, and other singleuse-only personal protective equipment and dispose of these items in the decontamination zone. Also, the sampling equipment will be decontaminated in the decontamination zone. When necessary, a Decontamination Zone crew of 2 to 3 persons will be assigned to assist crews entering and leaving the exclusion zone with the donning, doffing, and decontamination of personal protective equipment, sampling equipment, and sample bottles.

Emergency decontamination will include the following stations:

An initial wash with liquinox detergent in deionized/HPLC grade water and two subsequent rinses with deionized/HPLC grade water.

The following decontamination of equipment is required:

Field team members will wash equipment, etc., with Liquinox detergent and deionized/HPLC grade water, using an initial wash with detergent in water and two subsequent rinses with water only.

Procedures for disposing of decontamination solutions and non-reusable sampling equipment:

When the used decontamination and rinse solutions are believed to contain medium to high concentrations of contaminants, they will be collected in 10-gallon or 55-gallon drums for proper labeling, short-term (less than one year) storage at OES or Cherokee Nation facilities in Tahlequah, and eventual disposal in accordance with RCRA and DOT regulations. An equipment blank sample of the combined decontamination and rinse solutions will be collected at the end of sampling operations on-site. Analysis of this sample will document the contaminant concentrations of the combined decontamination and rinse solutions and facilitate proper labeling and disposal of the 10-gallon or 55-gallon drums.

When the used decontamination solutions are believed to contain low concentrations of contaminants, the solutions and rinses will not be collected but will be poured onto the ground onsite. (Sample data obtained from 48 Site Investigations conducted by OES since 1992 indicate that this method of disposal is safe.) Immediately prior to disposal the decontamination and rinse solutions will be combined, then a final equipment blank sample of the combined solutions will be collected. Analysis of this sample is intended to document the low concentrations of any contaminants in the combined solutions.

Non-reusable sampling equipment (protective gloves, tyvek suits, towels, etc.) that are believed to have low-level contamination will be placed in heavy duty trash bags for household trash disposal. (Sample data obtained from 48 Site Investigations conducted by OES since 1992 indicate that this method of disposal is safe.) If such non-reusable equipment is believed to have medium to high-level contamination, it will be sealed in 55-gallon drums for proper labeling, short-term (less than one year) storage at OES or Cherokee Nation facilities in Tahlequah, and eventual disposal in accordance with RCRA and DOT regulations.

Other site specific disposal procedures (describe):

J. SITE SAFETY AND HEALTH PLAN

1. Tom Elkins will be the designated Field Team Leader and is directly responsible for safety recommendations on-site.

2. Emergency Medical Care

A qualified EMT is not on site. A qualified First Responder is not on site. In the event of an emergency, the local ambulance service and hospital will be contacted as outlined below.

<u>Clinton Regional Hospital</u>, in <u>Clinton, Oklahoma</u>, phone <u>(580)</u> 323 - 8353 is located <u>10</u> minutes from the site. The hospital was not contacted and briefed about the on-site situation, the potential hazards, and the substances involved. A map of emergency route(s) to this facility is attached as the last page of this site health and safety plan.

Local ambulance service is available from <u>Clinton</u>, <u>Oklahoma</u> at telephone number <u>911 or (580)</u> <u>323 - 1978</u>. Their response time is <u>6</u> minutes. Whenever possible, arrangements should be made for on-site standby.

First-aid equipment is available on site at the following locations:

First-aid, snake bite, & insect bite kits

Emergency eye wash

Command post & each field truck

Command post & each field truck

N/A

Emergency medical information for substances present:

SUBSTANCE	EXPOSURE SYMPTOMS	FIRST-AID INSTRUCTIONS
Inorganic/organic	general	general
	P. W. I.	

Material Safety Data Sheets (MSDS) or other information sheets (from ATSDR, NIOSH, etc.) for the substances listed in the table above are attached to this site health and safety plan. Additional references (e.g., NIOSH Pocket Guide to Chemical Hazards) will be at the Command Post on site.

List of emergency phone numbers:

AGENCY/FACILITY	PHONE NUMBER	CONTACT PERSON
Ambulance	911 or (580) 323 - 1978	
Civil Defense		,
Custer County Sheriff	1-800-894-2677	
Fire Department	911 or (580) 323-1313	
Hospital (Clinton)	(580) 323 - 8353	Clinton Regional Hospital
Poison Control	1-800-522-4611	
Toxic Chemical	1-800-424-8802	
Highway Patrol (Clinton)	(580) 323-2424	
Police (Clinton)	911 or (580) 323-2323	
U.S. Marshall Service		
Gas Company		
Electric Cooperative		
Water Plant		
Communities		
Towns		
Roads		
Highway Department		
Railroads		·
Local Emergency Planning Committee	í	
Other		
Cherokee Nation	918-456-0671	
State Health Department		
National Response Center	1-800-424-8802	
Cherokee Superfund	918-458-5496	

3. Environmental Monitoring

The following environmental monitoring instruments shall be used on-site (cross out if not applicable) at the specified intervals.

Combustible Gas Indicator 0 ₂ Monitor Hydrogen sulfide monitor Colorimetric Tubes	 continuous/hourly/daily/other <u>if necessary</u> continuous/hourly/daily/other <u>if necessary</u> continuous/hourly/daily/other continuous/hourly/daily/other 		
HNU/OVA	- continuous/hourly/daily/other		
Other:	- continuous/hourly daily/other		

4. Emergency Procedures (should be modified as required for incident)

The following standard emergency procedures will be used by on-site personnel. The Project Manager and/or Assistant Project Manager shall be notified of any on-site emergencies and be responsible for ensuring that the appropriate procedures are followed.

<u>Personnel Injury in the Exclusion Zone</u>: Upon notification of an injury in the Exclusion Zone, the designated emergency signal <u>four blasts on vehicle horn or verbal alert</u> shall be sounded. All site personnel shall assemble at the decontamination line. The rescue team will enter the Exclusion Zone (if required) to remove the injured person to the hotline. The Field Team Leader and Assistant Project Manager should evaluate the nature of the injury, and the affected person should be decontaminated to the extent possible prior to movement to the Support Zone. The on-site EMT and/or First Responder shall initiate the appropriate first aid, and contact should be made for an ambulance and with the designated medical facility (if required). No persons shall re-enter the Exclusion Zone until the cause of the injury or symptoms is determined.

<u>Personnel Injury in the Support Zone</u>: Upon notification of an injury in the Support Zone, the Project Manager/Assistant Project Manager and Field Team Leader will assess the nature of the injury. If the cause of the injury or loss of the injured person does not affect the performance of site personnel, operations may continue, with the on-site EMT and/or First Responder initiating the appropriate first aid and necessary follow-up as stated above. If the injury increases the risk to others, the designated emergency signal <u>four blasts on vehicle horn or verbal alert</u> shall be sounded and all site personnel shall move to the decontamination line for further instructions. Activities on-site will stop until the added risk is removed or minimized.

<u>Fire/Explosion</u>: Upon notification of a fire or explosion on-site, the designated emergency signal four blasts on vehicle horn or verbal alert shall be sounded and all site personnel assembled at the decontamination line. The fire department shall be alerted and all personnel moved to a safe distance from the involved area.

<u>Personal Protective Equipment Failure</u>: If any site worker experiences a failure or alteration of protective equipment that affects the protection factor, that person and his/her buddy shall immediately leave the Exclusion Zone. Re-entry shall not be permitted until the equipment has been repaired or replaced.

Other Equipment Failure: If any other equipment on-site fails to operate properly, the Project Manager/Assistant Project Manager and Field Team Leader shall be notified and then determine the effect of this failure on continuing operations on-site. If the failure affects the safety of personnel or prevents completion of the Work Plan tasks, all personnel shall leave the Exclusion Zone until the situation is evaluated and appropriate actions taken.

The following emergency escape routes are designated for use in those situations where egress from the Exclusion Zone cannot occur through the decontamination line (describe): Unrestricted exit routes in all directions.

In all situations, when an on-site emergency results in evacuation of the Exclusion Zone, personnel shall not re-enter until:

- 1. The conditions resulting in the emergency have been corrected.
- 2. The hazards have been reassessed.
- 3. The Site Safety Plan has been reviewed.
- 4. Site personnel have been briefed on any changes in the Site Safety Plan.

5. Personal Monitoring

The following personal monitoring will be in effect on site:

Personal exposure sampling: None

Medical monitoring: The expected air temperature will be 74° F. If it is determined that heat stress monitoring is required (mandatory if over 70 degrees Fahrenheit) the following procedures shall be followed (describe): Sufficient drinking water and rest breaks will be provided. Level D clothing reduces probability that heat stress will occur.

6. Special site equipment, facilities, or procedures (sanitary facilities, lighting, etc.): NONE

All site personnel have read the above plan and are familiar with its provisions.


TITLE	NAME	SIGNATURE
Field Team Leader		
Field Team Leader, Public Information Officer	Tom Elkins	Tom Dles
Field Team Member (FTM)	Brad Asbill	3 rad arhill
FTM	Jason White	Oson Witte
FTM	Randall Gee	Hell Der
FTM	Travis Waldo	Frants Wade
FTM	Melinda Sims	Melinda Suns
FTM		



RAY WICHERT PROPERTY


SITE INVESTIGATION - EMERGENCY ROUTE MAP USGS 7.5 MINUTE QUADRANGLES BESSIE, OK AND CLINTON, OK SECTION 27, T12N, R17W - CUSTER COUNTY FIGURE

DATE APRIL 2000



DIRECTIONS

From site, drive 1.5 miles north on Neptune Drive, then 1.25 miles west on Modelle Ave., then .5 miles north on 30th street. Hospital is on west side of 30th street.



HOSPITAL

Clinton Regional Hospital 100 North 30th Street Clinton, OK 73601 (580) 323-2363



RAY WICHERT PROPERTY

Sample Location Number	Sample Matrix	Type Sample
1	Surface Soil, low concentration	Judgmental Grab
2	Surface Soil, low concentration, duplicate of 1	Judgmental Grab
3	. Surface Soil, low concentration	Judgmental Grab
4	Surface Soil, low concentration	Judgmental Grab
5	Surface Soil, low concentration	Judgmental Grab
6	Surface Soil, low concentration, background	Judgmental Grab
7	Equipment blank, initial rinsate	deionized/HPLC H2O
8	Equipment blank, final rinsate	deionized/HPLC H2O
9	Field blank	deionized/HPLC H2O
10	Trip Blank, VOA only	deionized/HPLC H2O

SAMPLE NUMBER 1	SAMPLE LOCATION AND RATIONALE Soil (0-6 inches). Low concentration grab sample collected around the rubble piles. Rationale: Identify a contaminated area and determine if there is contaminated soil attributable to the rubble piles.
2	Soil (0-6 inches). Low concentration grab sample collected around the rubble piles. <u>Rationale</u> : Duplicate of sample number 1. Assess the CLP sampling and measurement error, quality control sample.
3	Soil (0-6 inches). Low concentration grab sample collected around the rubble piles. Rationale: Identify a contaminated area and determine if there is contaminated soil attributable to the rubble piles.
4	Soil (0-6 inches). Low concentration grab sample collected around the rubble piles. Rationale: Identify a contaminated area and determine if there is contaminated soil attributable to the rubble piles.

- Soil (0-6 inches). Low concentration grab sample collected around the rubble piles.

 Rationale: Identify a contaminated area and determine if there is contaminated soil attributable to the rubble piles.
- Soil (0-6 inches). Low concentration grab sample collected two miles northeast of the site.

 Rationale: Establish a background baseline for comparison to the low concentration soil samples.
- Eqipment blank. Initial rinsate from the soil/sediment sampling equipment decontamination process, utilizing deionized/HPLC grade water.

 Rationle: Quality control sample. Identify any contamination introduced during the decontamination of sampling equipment.
- Equipment blank. Final rinsate, grab sample collected on-site after all other samples have been collected and all sampling equipment has been decontaminated in liquinox detergent and deionized/HPLC grade water.

 Rationale: Quality control sample. Quantify contaminant concentrations in combined wash and rinsate solutions.
- Field blank, deionized/HPLC-grade water.

 <u>Rationale</u>: Quality control sample. Identify any contamination introduced during the on-site sample collection and storage.
- Trip blank, VOA only, deionized/HPLC grade water.

 <u>Rationale:</u> Quality control sample. Identify any volatile organic contamination introduced during the sample handling, storage, and transport.





INTER-TRIBAL ENVIRONMENTAL COUNCIL

CHERCICE NATION OF CICLAHOMA OFFICE OF ENMRONMENTAL SERVICES TAHLEQUAH, OKLAHOMA

RAY WICHERT PROPERTY


SITE INVESTIGATION - SAMPLE PLAN USGS 7.5 MINUTE QUADRANGLES CLINTON, OK AND BESSIE, OK SECTION 27, T12N, R17W-CUSTER COUNTY FIGURE 1 DATE APRIL 2000





LEGEND

- Rubble Piles
- Soil Sample Location
- Site: Ray Wichert Property





Practical Handbook of Ground-Water Monitoring

Edited by

David M. Nielsen



Practical handbook of ground-water monitoring/David M. Nielsen, editor.

p. cm.

Includes bibliographical references and index.

1. Water, Underground—Quality—Measurement. I. Nielsen, David.

TD426P73 1991 628.1'61—dc20 90-36848 ISBN 0-87371-124-6

Second Printing, 1991

COPYRIGHT © 1991 by LEWIS PUBLISHERS, INC. ALL RIGHTS RESERVED

Neither this book nor any part may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, microfilming, and recording, or by any information storage and retreival system, without permission in writing from the publisher.

LEWIS PUBLISHERS, INC. 121 South Main Street, Chelsea, MI 48118

PRINTED IN THE UNITED STATES OF AMERICA

PREFACE

Ground-water monitoring is by no means a new field because hydrogeologists, engineers, and other professionals have been monitoring ground water for decades. Yet, much of the technology used today to perform such basic tasks as water-level measurement, water-quality characterization, and aquifer tests is less than a decade old. Indeed, the decade of the 1980s was a period of explosive growth for the field of ground-water monitoring, and a time of great achievement for those involved in conducting ground-water investigations. During this time, we developed a basic understanding of how our ground-water resources were being impacted by many of our everyday activities, what we needed to do to prevent further degradation, and how we could clean up ground water that had already been detrimentally impacted.

Passage of the Resource Conservation and Recovery Act (RCRA) by Congress in 1976 and subsequent promulgation of the first of the regulations authorized under RCRA by the U.S. Environmental Protection Agency (EPA) in May 1980 provided the primary impetus for the growth of the field of ground-water monitoring. RCRA, which is EPA's main tool for managing hazardous waste from generation through disposal, included provisions for establishing ground-water or vadose-zone monitoring systems at all of this country's hazardous waste treatment, storage, and disposal facilities, which include hundreds of thousands of sites. More recent provisions of RCRA specify similar monitoring systems for each of the country's solid waste landfill facilities (sanitary landfills), which number in the thousands. Still other provisions of recent amendments to RCRA (the Hazardous and Solid Waste Amendments of 1986) call for the installation of ground-water or vadose-zone monitoring systems at many underground storage tank locations, which number in the hundreds of thousands across the country.

Passage of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), better known as "Superfund," by Congress in December 1980 addressed the national threat caused by so-called "uncontrolled" hazardous waste sites, which probably number in the tens of thousands. Cleanup of these sites requires the installation of monitoring devices to investigate the extent of environmental contamination and to monitor the progress of the cleanup. Ground-water monitoring is also done under other environmental regulatory programs, and for a variety of nonregulatory purposes, creating a tremendous demand for knowledge in this field.

Like most fields that experience such tremendous surges in growth, the groundwater monitoring field, if it can truly be called that, has seen periods of disorder The porosity used in Equation 10.8 is the effective porosity, \bar{n} , which always has a lower value than the total porosity. Some water in pore spaces may be held onto soil particles by molecular binding forces (Mitchell, 1976). The soil may contain dead-end pores or unconnected pores which contain water, but through which no water flow is occurring. Therefore, caution should be exercised in selecting effective porosities. Effective porosity is difficult to measure and is typically selected by intuition or experience. Tracer experiments can be used to estimate effective porosities but the procedure is fraught with difficulties. When porosity is very low, laboratory errors may become significant. Field variation in porosity, however, may exceed laboratory errors and suggests multiple in situ test sites.

HYDRAULIC CONDUCTIVITY AND PERMEABILITY

The rate of water movement through a soil was first described mathematically by Darcy (1856). By studying the flow of water through sand columns, Darcy developed a relationship between the filtration velocity, the hydraulic gradient, and a coefficient, K, which has come to be known as the hydraulic conductivity. K is a function of both the medium through which the fluid is moving, and of the fluid itself. In many engineering texts, K is also known as the coefficient of permeability. As a result, the two terms are used interchangeably in hydrogeologic applications. Hydraulic conductivity is expressed in units of length per time, such as meters per second (m/s) or feet per day (ft/day).

Another term, intrinsic permeability, k, is used to describe the part of K that depends only on the medium in which a fluid is flowing. Intrinsic permeability has the units of length squared, such as cm² or mm², or the darcy $(0.987 \times 10^{-12} \text{m}^2 = 1 \text{ darcy})$.

For granular porous media, Darcy's law can be written as:

$$v_s = Ki ag{10.9}$$

where:

v_s = specific discharge in units of length per time,

K = the hydraulic conductivity in units of length per time, and

 $i = dimensionless hydraulic gradient in the direction of <math>v_s$.

This definition has been modified to describe flow in a fracture (Louis, 1974). Table 10.4 presents typical hydraulic conductivity values for various geologic materials. Generally, the finer the soil particle size, the lower the hydraulic conductivity value. The difference in K ranges between silts or clays and sands is a result of the smaller effective pore sizes in clays and silts than in sands. Soils which contain a broad range of grain sizes, such as a glacial till, typically have lower K values than a uniformly sized soil, such as a beach sand. Darcy's law

Table 10.4. Typical Hydraulic Conductivities.

Geologic Material	Range of K (m/s)
Coarse gravels	10-1-10-2
Sands and gravels	10-2-10-5
Fine sands, silts, loess	10 ⁻⁵ -10 ⁻⁹
Clay, shale, glacial till	10-5-10-13
Dolomitic limestones	10-3-10-5
Weathered chalk	10-3-10-5
Unweathered chalk	10-6-10-9
Limestone	10 - 3_10 - 9
Sandstone	10-4-10-10
Unweathered granite, gneiss, compact basalt	10 ⁻⁷ -10 ⁻¹³

is the cornerstone for evaluating ground-water flow behavior. However, the relationship is valid only as long as the velocity remains within a particular range of values. As the hydraulic gradient is increased, the water velocity increases and friction loss within the pores or fractures correspondingly increases. This phenomenon is analogous to flow through a pipe. Above a critical velocity, frictional losses are no longer linearly related to i, and Darcy's law must be modified or it becomes invalid. Some authors have suggested that an upper limit to the applicability of Darcy's equation for porous media be established by relating the velocity to a Reynold's Number (Bear, 1972). Reynold's Number for a porous medium can be defined as:

$$R_{\rm e} = \bar{v} d\rho/\mu \tag{10.10}$$

where:

 \bar{v} = mean velocity of water in pores in units of length per time,


 ρ = fluid unit density in units of mass per volume,

 μ = the viscosity of the fluid in units of mass per time-length, and


d = mean diameter of the pores as estimated from the effective grain size diameter in units of length.

In porous media, d is typically selected as the particle size for which 10% of the sample is smaller. In fractured media, d becomes the fracture width. Darcy's law is considered valid up to an R_e of between 1 and 10. Between an R_e of 10 to 100, turbulent flow begins, and beyond 100, turbulence predominates and Darcy's law is invalid.

There also appears to be evidence, although some is conflicting, that for clay or other fine-grained materials Darcy's law may be invalid for very low gradients (Jacquin, 1965a, b). Desaulniers et al. (1986) performed a field investigation in a thick clayey glacial till that supports the concept of threshold gradients. A relationship for Darcy's law incorporating a threshold gradient is suggested as shown



NOT FOR RESALE



COMMUNICATION REFERENCE

From:

Linda Ray Custer County Rural Water District 3 580-593-2561

To:

Kent Curtis, Environmental Specialist II Cherokee Nation's Office of Environmental Services (OES) P. O. Box 948 Tahlequah, Oklahoma 74465 918-458-5498

Date and Time: Telephone conversation at 1125 hours on 18 June, 2003

Subject: Custer County Rural Water District 3

Linda told Kent the following:

Custer County Rural Water District 3 obtains its water from three groundwater wells located five miles north of the city of Weatherford, Oklahoma. These wells are protected by a wellhead protection area, but Linda did not know the diameter or boundaries of the wellhead protection area. Custer County Rural Water District 3 provides drinking water to most of central Custer County and to a small portion of Washita County just southeast of the city of Clinton. The number of private wells within the service area is unknown. Residences outside the RWD3 service area to the west and southwest of Clinton obtain their drinking water from private wells or from the Frontier Development Authority Rural Water District.

RURAL WATER SYSTEMS IN OKLAHOMA

Planning and Management Division

Oklahoma Water Resources Board

J. Ross Kirtley, Chairman Richard McDonald, Vice Chairman Dick Seybolt, Secretary

Bill Secrest Ervin Mitchell Lonnie L. Farmer Wendell Thomasson Richard C. Sevenoaks Grady Grandstaff

Duane A. Smith, Executive Director
Michael R. Melton, Assistant to the Director

Publication Number 138



January 1998


Main Office: 3800 N. Classen Blvd. Oklahoma City, Oklahoma 73118 Phone: (405) 530-8800 Fax: (405) 530-8900

Branch Offices:

Lawton Phone: (405)248-7762 Fax: (405)248-0737 McAlester Phone: (918)426-5435 Fax: (918)426-6144 Tulsa Phone: (918)581-2924 Fax: (918)581-2754 Woodward Phone: (405)256-1014 Fax: (405)256-1015

Rural Water Systems in Ok	dahoma			CHS	TER COUNTY				
RURAL WATER SYSTEM NAME	Custer Co. RWD #3								Water System Information
RURAL WATER STOTEM NAME	Custer Co. KWD #3	Arapaho PWA	Butler PWA	Custer City PWA	Frontier Dev Auth	Thomas PWA	Weatherford PWA	City of Clinton	
Year Survey Completed	1995	1995	1995	1995	1995	1995	1995	1995	
Year Map Completed	1995	1995	ALCL	1995	1995	1995	1995	1995	
Manager Name	Mike Harris	Buford McDow	Vernon K. Raper	Ron Fergason	Vernon K. Raper	Bill Haney	Arnold Miller	Alvin Knauf	
Manager Phone Number	(405) 593-2561	(405) 323-4376	(405) 664-3915	(405) 593-2312	(405) 664-3915	(405) 661-3687	(405) 772-7451	(405) 323-0217	
Year System Began Operation	1978	1911	1976	1974	1979	1975	1903	1926	
Population Served	960	801	300	900	1,200	1,246	15,000	12,500	
Master Meters	3	0	1	1	1	0	0	12,300	
Residential Meters	354	323	160	232	250	448	4.000	4,008	
Commercial Meters	9	20	0	13	0	54	200	4,000	
Industrial Meters	7	Ō	Ö	0	Õ	3	3	0	
Other Meters	0	Ö	ō	ō	Ď	0	Ŏ	U A	
Percentage of System Metered	100%	100%	100%	100%	100%	98%	100%	80%	
Average Daily Use (1000 GPD)	89	71	30	90	80	129			
Maximum Daily Demand (1000 GPD)	115	101	50	150	120	225	••	2,000 3,000	
Percapita Daily Use (GPD)	92	89	100	100	67	104	150		
Minimum Residential Rate	\$21.00 / 1000 gallons	\$17.50 / 3000 gallons	\$14.00 / 2000 gallons	\$13.00 / 2000 gallons	\$34.00 / 1000 gallons	\$6.75 / 1000 gailons	\$2.00 / 2000 gallons	** ** ** ** ** ** ** ** ** ** ** ** **	
Minimum Pasture Rate		••			•• Tool gallons	\$6.757 1000 gallons	\$2.00 / 2000 gailons	\$5.50 / 2000 gallons	
Water Supply Type	Soth	Purchased	Both	Supplied	Both	Supplied	Supplied	Both	
Water Supply Description/Amount	GW, Custer City Well, S30 T14N R14W	City of Clinton	RS, Foss Reservoir	GW, Rush Springs Aquifer,	RS. Foss Reservoir	GW, City of Thomas,	GW, Rush Springs Sandstone	0144 040-4	
••••	RWD #3, S5 T13N R14W				NO, FUSS NOSCI YUR	GW, City of Inomas,	Gar, Masii Spillids Sandstone	SW, Clinton Lake	
			City of Hobart	S30 T14N R14W	- City of Hobart	024 T4KN D44W			
	Custer City PWA 320 A.F.		City of Hobart	S30 T14N R14W	City of Hobart	S31 T15N R14W		GW, Wells, near Burnes Flat, OK	
			City of Hobart	\$30 T14N R14W	City of Hobart	S31 T15N R14W			
Water Rights			City of Hobart	\$30 T14N R14W	City of Hobart	•		GW, Wells, near Burnes Flat, OK	
Water Rights Allocated Acre Feet			N	\$30 T14N R14W	N	Y	Y	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y	
Allocated Acre Feet	Custer City PWA 320 A.F.	N	N	\$30 T14N R14W Y 320	City of Hobart N	Y 160	Y 3,282	GW, Wells, near Burnes Flat, OK	
Allocated Acre Feet Standby Source	Custer City PWA 320 A.F.	N	N N	\$30 T14N R14W Y 320 N	N	Y 160 N	 Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y	
Allocated Acre Feet Standby Source Name of Standby Source	Custer City PWA 320 A.F. Y 400 Y	N	N	\$30 T14N R14W Y 320 N	N N	Y 160 N	Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons)	Custer City PWA 320 A.F. Y 400 Y Custer City PWA	N N	N N	\$30 T14N R14W Y 320 N	N	Y 160 N	 Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y	
Allocated Acre Feet Standby Source Name of Standby Source	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y	N N	N	\$30 T14N R14W Y	N N N	Y 160 N	Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells 700 Y	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers > 100,000 Gallons/Month	Custer City PWA 320 A.F. Y 400 Y Custer City PWA	N N	N N	\$30 T14N R14W Y 320 N	N N N	Y 160 N	Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >100,000 Gallons/Month Customer Name/Gallons Provided	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000	N N N	N N N	S30 T14N R14W Y	N N N N	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School	3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells 700 Y Town of Arapaho 28,809,000	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >100,000 Gallons/Month Customer Name/Gallons Provided	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000 Excellent	N N N	N N N N	S30 T14N R14W Y	N N N N 0000	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School Good	Y 3,282 N Y 156,000 Country West Homeowners Assn. 365,000 124,000	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >100,000 Gallons/Month Customer Name/Gallons Provided Treatment System Rating Treatment System Inadequacies	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000 Excellent	N N N	N N N N	S30 T14N R14W Y	N N N 0000	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School Good	Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells 700 Y Town of Arapaho 28,809,000 Good Excessive Trihalomethanes	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >109,000 Gallons/Month Customer Name/Gallons Provided Treatment System Rating Treatment System Inadequacies Water Treatment Capacity (GPD)	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000 Excellent	N N N	N N N	S30 T14N R14W Y	N N N N	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School Good 250,000	3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells 700 Y Town of Arapaho 28,809,000 Good Excessive Trihalomethanes 2,600,000	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >100,000 Gallons/Month Customer Name/Gallons Provided Treatment System Rating Treatment System Inadequacies Water Treatment Capacity (GPD) Treated Storage Capacity (Gallons)	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000 Excellent	N N N	N N N N	S30 T14N R14W Y	N N N 12,000,000	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School Good 250,000 350,000	Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells 700 Y Town of Arapaho 28,809,000 Good Excessive Trihalomethanes	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >109,000 Gallons/Month Customer Name/Gailons Provided Treatment System Rating Treatment System Inadequacies Water Treatment Capacity (GPD)	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000 Excellent	N N N	N N N	S30 T14N R14W Y	N N N N	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School Good 250,000	3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells 700 Y Town of Arapaho 28,809,000 Good Excessive Trihalomethanes 2,600,000	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >109,000 Gallons/Month Customer Name/Gallons Provided Treatment System Rating Treatment System Inadequacies Water Treatment Capacity (GPD) Treated Storage Capacity (Gallons) Raw Water Storage Capacity (Gallons)	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000 Excellent	N N N 200,000	N N N N 120,000	\$30 T14N R14W Y 320 N Y Custer Co. RWD #3 1,078	N N N 12,000,000 150,000	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School Good 250,000 350,000	Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >100,000 Gallons/Month Customer Name/Gallons Provided Treatment System Rating Treatment System Inadequacies Water Treatment Capacity (GPD) Treated Storage Capacity (Gallons) Raw Water Storage Capacity (Gallons) Distribution System Rating	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000 Excellent 200,000 80,000	N N N 200,000 0	N N N N 120,000 150,000	S30 T14N R14W Y 320 N Y Custer Co. RWD #3 1,078	N N N 12,000,000	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School Good 250,000 350,000	Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y	
Allocated Acre Feet Standby Source Name of Standby Source Amount of Standby (Gallons) Customers >109,000 Gallons/Month Customer Name/Gallons Provided Treatment System Rating Treatment System Inadequacies Water Treatment Capacity (GPD) Treated Storage Capacity (Gallons) Raw Water Storage Capacity (Gallons)	Custer City PWA 320 A.F. Y 400 Y Custer City PWA 100,000 Y Cherokee Restaurant 114,000 Excellent	N N N 200,000	N N N N 120,000	\$30 T14N R14W Y 320 N Y Custer Co. RWD #3 1,078	N N N 12,000,000 150,000	Y 160 N Y Hamm & Phillips Thomas Hospital Thomas School Good 250,000 350,000	Y 3,282 N	GW, Wells, near Burnes Flat, OK Foss Master Cons. Dist. 555,000.00 Y 3,980 Y Water Wells 700 Y Town of Arapaho 28,809,000 Good Excessive Trihalomethanes 2,600,000 9,000,000	


en de la companya de Ny faritra de la companya de la com



Rural Water Systems in O	klahoma			WASHIT	A COUNTY				Water System Information
RURAL WATER SYSTEM NAME	Washita Co. RWD #2	City of Bessie	Burns Flat Util. Auth.	City of Canute	City of Cordell	City of Dill City	Foss Public Water Works	City of Rocky	Sentinel PWA
Year Survey Completed	1995	1995	1995	1995	1995	1995	1995	1995	1995
ear Map Completed	1995	0	1995	1995	1995	1995	1995	1995	1995
lanager Name	Kevin Internann	Carl Holliman	Joel Newberry	Jimmy Hassell	Jerry L. Berry	Michael Allen	Terry V. Price	Venoy Foust	Curtis Chandler Jr.
Manager Phone Number	(405) 337-6322	(405) 337-6677	(405) 562-3144	(405) 472-3111	(405) 832-3825	(405) 674-3376	(405) 592-4513	(405) 666-2211	(405) 393-2171
ear System Began Operation	1976	1959	1985	1956	1920	1926	1907		1988
opulation Served	1,000	300	200	548	2,903	600	150	260	950 0
laster Meters	1	0	3	2	4	2	54	105	433
esidential Meters	335	105	90	250	500	205	2	105	13
ommercial Meters	0	0	0	31	40	9	ń	'n	8
ndustriai Meters	0	0	15	u	25 0	0	6	ň	Ŏ
ther Meters	202	0	0	0 100%	96%	100%	100%	%	100%
ercentage of System Metered	100%	100%	100%	50	324	50	13		
verage Daily Use (1000 GPD)	158		23	95	600	80	13	••	· •
Maximum Daily Demand (1000 GPD)	183 158		35 115	91	112	83	87	••	••
Percapita Daily Use (GPD)		\$10.00 / 1000 gallons	\$10.25 / 2000 gallons	\$10.35 / 2000 gallons	\$10.00 Minimum	\$17.50 / 2000 gallons	\$8.00 / 2000 gallons		\$12.00 / 1000 gallons
Minimum Residential Rate	\$14.00 / 1000 gallons	\$10.00 / 1000 gailons	\$10.25 / 2000 gallons	• • • • • • • • • • • • • • • • • • •		• • • • • • • • • • • • • • • • • • •		••	••
Winimum Pasture Rate	Supplied	Purchased	Supplied	Both	Both	Purchased	Supplied	Purchased	Purchased
Nater Supply Type Nater Supply Description/Amount	GW, Wells, S25 T10N R14W	RS, Foss Reservoir		GW -		GW	GW, Well #1, South	Beckham Co. RWD #1	Beckham Co. RWD -
Water Supply Description Amount	GW, Wells, S23 T12N R14W	Washita Co. Rural Water		L.M. Davis 2,000,000/Mo	. Foss Water System	Orval McMannaman	GW, Well #2, North	• •	
	,, 020 11214 1(1411	***************************************		• •	<u>-</u>				
							• • • • • • • • • • • • • • • • • • • •	and the second second second second	
Water Rights	Υ	N	Υ '	Y	Υ	N	Υ	N	N
Allocated Acre Feet	390	••	447.4	157	2,371		459	••	••
Standby Source	Y	Y	Y	Υ	Y	N	Y Franking Davi Avith	Y Standaine	N
Name of Standby Source	5 wells	Water tower	Well, 50B	City wells	Foss Lake		Frontier Dev. Auth.	Standpipe 100,000	••
Amount of Standby (Gallons)	90 gal./min., each well	103,000	250 gal./min.	201,600			N C.	100,000	
Customers >100,000 Gallons/Month	Y	N	· N	N 1911 - 2011 - 30	N .	N	The state of the s	유리왕: 🏲 - 사고 사고 - 1000	
Customer Name/Gallons Provided	Ray Brown 2,909,000							A Company of the Comp	
							:		
	C		Good	Excellent	Good	Excellent	Excellent	· · ·	••
reatment System Rating	Good	Do not treat water			••		••	Do not treat water	••
reatment System Inadequacies	130,000	Do not treat water	35,000	201,600	324,000	50,000	13,000	••	••
Vater Treatment Capacity (GPD) Treated Storage Capacity (Gallons)	217,000	103,000	48,000	136,000	1,600,000	233,000	55,000		350,000
Raw Water Storage Capacity (Gallons)		103,000	48,000	0	1,600,000	0	0		0
(aw Water Storage Capacity (Canons)	217,000		1.0				W		
							_* .	and the second of the second	
Distribution System Rating	Excellent	Good	Excellent	Good	Good	Excellent	Good	Good	Good
Distribution System Inadequacies	••	••	• •		••		•• '. '	, y"	ran et en
Percentage of Water Lost	16%	%	14%	8%	%	5%	10%	%	16%
•									
RURAL WATER SYSTEM NAME	Town of Corn						the second of th		
					to the second			어려는 사람은 그렇게 하는데 뭐 하다.	그 기사 등 이 사람들은 사람들이 되었다.
door Russey Completed	1995								
/ear Survey Completed /ear Map Completed Manager Name	1995 1995 Willard Couch	S S S S S S S S S S S S S S S S S S S					다음 전 경우 전 경		

				4. 18.5
Year Survey Completed	1995			
Year Map Completed	1995			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Manager Name	Willard Couch			
Manager Phone Number	(405) 343-2255			
Year System Began Operation	1954			
Population Served	560			
Master Meters	1			
Residential Meters	201			
Commercial Meters	18			
Industrial Meters	0	.54		
Other Meters	12	414.1		
Percentage of System Metered	100%	**		
Average Daily Use (1000 GPD)	92		,	
Maximum Daily Demand (1000 GPD)	193			
Percapita Daily Use (GPD)	164			
Minimum Residential Rate	\$7.00 / 3000 gallons			
Minimum Pasture Rate				
Water Supply Type	Supplied			
Water Supply Description/Amount	GW .			
(M)				
				1.21
Water Rights	Y			
Allocated Acre Feet	236			
Standby Source	N			
Name of Standby Source	• •			
Amount of Standby (Gallons)	• •			
Customers >100,000 Gallons/Month	Y	*,		
Customer Name/Gallons Provided	Corn Heritage Village	200,000		*,
Treatment System Rating	Good	4.93.4		* * *
Treatment System Inadequacies				
Water Treatment Capacity (GPD)	193,000			
Treated Storage Capacity (Gallons)	230.000			
Treated Storage Capacity (Gallons)	230,000			

Raw Water Storage Capacity (Gallons)



PB88-237961

TECHNICAL PAPER NO. 40

RAINFALL FREQUENCY ATLAS OF THE UNITED STATES

for Durations from 30 Minutes to 24 Hours and Return Periods from 1 to 100 Years




WASHINGTON, D.C.

May 1961

Repaginated and Reprinted January 1963

REPRODUCED BY
U.S. DEPARTMENT OF COMMERCE
NATIONAL TECHNICAL
INFORMATION SERVICE
SPRINGFIELD VA 22161



SOIL SURVEY OF

Custer County, Oklahoma



United States Department of Agriculture Soil Conservation Service

In cooperation with Oklahoma Agricultural Experiment Station

Contents

	Page		Page
Index to mapping units	ii	Pasture and hayland	24
Summary of tables	iii	Management and maintenance	24
How this survey was made	1	Pasture and hayland suitability	
General soil map	2	groups	24
1. Shellabarger-Pratt association	2	Range	25
2. Cordell association	2	Range sites and condition classes	$\overline{25}$
3. Woodward-Quinlan association	3	Descriptions of the range sites	26
4. Carey-St. Paul association	3	Tree plantings	29
5. Lucien-Rock outcrop-Cornick		Preparation and planting	29
association	3	Descriptions of tree suitability	20
6. Pond Creek-Grant-Minco		groups	29
association	3	Wildlife habitat	31
7. Clairemont-Dale association	3	Recreational development	33
Descriptions of the soils	4		
Carey series	4	Engineering uses of the soils	34
Clairemont series	5	Engineering soil classification	0.5
Cordell series	7	systems	35
Cornick series	7	Soil properties significant to	0.5
Crisfield series	7	engineering	35
Dale series	8	Engineering interpretations	39
Devol series	8	of soils	
Dill series	9	Soil test data	45
Fluvents	9	Formation and classification of the soils	46
Gracemore series	11	Factors of soil formation	46
Grant series	11	Parent material	46
Hardeman series	12	Climate	46
Lucien series	12	Plants and animals	46
Minco series	13	Relief	46
Pond Creek series	13	Time	46
Pratt series	14	Processes of soil formation	47
Quinlan series	15	Classification of soils	47
Rock outcrop	16	General facts about the county	48
Shellabarger series	16	Relief and drainage	48
St. Paul series	16	Settlement and development	48
Tivoli series	17	Natural resources	48
Woodward series	19	Transportation and industry	49
Yahola series	21	Farming	49
Use and management of the soils	21	Climate	49
Crops	21	Glossary	51
Capability grouping	21	•	
Predicted vields	23	Guide to mapping units Followin	o 52

SOIL SURVEY OF CUSTER COUNTY, OKLAHOMA

BY ODOS G. HENSON, SOIL CONSERVATION SERVICE

UNITED STATES DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, IN COOPERATION WITH OKLAHOMA AGRICULTURAL EXPERIMENT STATION

CUSTER COUNTY is in the west-central part of Oklahoma (fig. 1). Arapaho is the county seat. The county has an area of 640,640 acres, or 1,001 square miles. It lies within Central Rolling Red Plains physiographic region.

Farming is the principal source of income. About 50 percent of the county is rangeland. The rest is cropland used mainly for growing small grain, cotton, grain sorghum, and alfalfa.

How This Survey Was Made

Soil scientists made this survey to learn what kinds of soil are in Custer County, where they are located, and how they can be used. The soil scientists went into the county knowing they likely would find many soils they had already seen and perhaps some they had not. They observed the steepness, length, and shape of slopes, the size and speed of streams, the kinds of native plants or crops, the kinds of rock, and many facts about the soils. They dug many holes to expose soil profiles. A profile is the sequence of natural layers, or horizons, in a soil; it extends from the surface down into the parent material that has not been changed much by leaching or by the action of plant roots.

The soil scientists made comparisons among the profiles they studied, and they compared these profiles with those in counties nearby and in places more distant. They classified and named the soils according to nationwide, uniform procedures. The soil series and the




Figure 1.-Location of Custer County in Oklahoma.

soil phase are the categories of soil classification most used in a local survey.

Soils that have profiles almost alike make up a soil series. Except for different texture in the surface layer, all the soils of one series have major horizons that are similar in thickness, arrangement, and other important characteristics. Each soil series is named for a town or other geographic feature near the place where a soil of that series was first observed and mapped. Cordell and Cornick, for example, are the names of two soil series. All the soils in the United States having the same series name are essentially alike in those characteristics that affect their behavior in the undisturbed landscape.

Soils of one series can differ in texture of the surface layer and in slope, stoniness, or some other characteristic that affects use of the soils by man. On the basis of such differences, a soil series is divided into phases. The name of a soil phase indicates a feature that affects management. For example, Carey silt loam, 1 to 3 percent slopes, is one of several phases within the Carey series.

After a guide for classifying and naming the soils had been worked out, the soil scientists drew the boundaries of the individual soils on aerial photographs. These photographs show woodlands, buildings, field borders, trees, and other details that help in drawing boundaries accurately. The soil map at the back of this publication was prepared from aerial photographs.

The areas shown on a soil map are called mapping units. On most maps detailed enough to be useful in planning the management of farms and fields, a mapping unit is nearly equivalent to a soil phase. It is not exactly equivalent, because it is not practical to show on such a map all the small, scattered bits of soil of some kind that have been seen within an area that is dominantly of a recognized soil phase.

Some mapping units are made up of soils of different series, or of different phases within one series. Two such kinds of mapping units are shown on the soil map of Custer County: soil complexes and undifferentiated groups.

A soil complex consists of areas of two or more soils, so intricately intermingled or so small in size that they cannot be shown separately on the soil map. Each area of a complex contains some of each of the two or more dominant soils, and the pattern and relative propor-

Representative profile of Tivoli loamy fine sand in an area of Pratt and Tivoli soils, 8 to 12 percent slopes (W), 1,575 feet south and 75 feet west of the northeast corner of sec. 10, T. 15 N., R. 14 W.:

A1—0 to 6 inches, brown (10YR 5/3) loamy fine sand, brown (10YR 4/3) when moist; single grained; very friable: neutral: gradual, wavy boundary.

friable; neutral; gradual, wavy boundary. C-6 to 72 inches, light-brown (7.5YR 6/4) fine sand, brown (7.5YR 5/4) when moist; single grained; loose;

neutral.

The A1 horizon is brown, grayish-brown, light brownishgray, or pale-brown loamy fine sand or fine sand. It is neutral to mildly alkaline. The C horizon is light brown, brown, strong brown, reddish yellow, reddish brown, or light reddish brown. It is neutral to mildly alkaline.

Tivoli soils in this survey area are mapped only in an

undifferentiated group with Pratt soils.

Woodward Series

The Woodward series consists of moderately deep, well-drained, very gently sloping to strongly sloping soils on uplands. These soils formed in material weathered from sandstone under a cover of native grasses.

In a representative profile the surface layer is 10 inches of reddish-brown silt loam. The subsoil, to a depth of 30 inches, is red silt loam. The underlying material is red partly weathered sandstone.

Permeability is moderate. Available water capacity

is high.

Representative profile of Woodward silt loam in an area of Woodward-Quinlan complex, 5 to 12 percent slopes, 1,080 feet south and 30 feet east of the northwest corner of sec. 4, T. 14 N., R. 20 W.:

A1-0 to 10 inches, reddish-brown (5YR 4/4) silt loam, dark reddish brown (5YR 3/4) when moist; moderate, medium, granular structure; friable; calcareous; moderately alkaline: gradual, smooth boundary.

erately alkaline; gradual, smooth boundary.

B2—10 to 30 inches, red (2.5YR 4/6) silt loam, dark red (2.5YR 3/6) when moist; weak, medium, granular structure; friable; calcareous; moderately alkaline; gradual, wavy boundary.

gradual, wavy boundary.

C-30 to 40 inches, red (2.5YR 4/6) partly weathered sandstone, dark red (2.5YR 3/6) when moist; calcareous; moderately alkaline.

The A1 or Ap horizon is reddish-brown, brown, or red silt loam or loam. It is moderately alkaline to neutral. The B2 horizon is reddish-brown or red silt loam or loam. It is mildly alkaline or moderately alkaline. Depth to sandstone is 20 to 40 inches.

WoB—Woodward silt loam, 1 to 3 percent slopes.

This soil is very gently sloping.

Included with this soil in mapping are areas of a soil that is similar to this Woodward soil, but it is 40 to 60 inches deep over sandstone. This soil makes up about 40 percent of the mapped areas. Also included are areas of Carey and Quinlan soils. Carey soils make up about 5 percent of the unit, and Quinlan soils 3 percent.

Most of this soil is used for wheat. Some areas are in other small grain, grain sorghum, cotton, tame pas-

ture grasses, and native grasses.

The main concerns of management are controlling erosion and maintaining soil structure and fertility. If this soil is well managed, most of the suited crops

can be grown. Returning crop residue to the soil and supplying plant nutrients are good management practices. Terraces with protected outlets, contour farming, and minimum tillage are needed if row crops are grown. Capability unit IIe-1; Loamy Prairie range site; pasture and hayland suitability group 8A; tree suitability group 6.

WoC-Woodward silt loam, 3 to 5 percent slopes.

This soil is gently sloping.

Included with this soil in mapping are areas of Quinlan, Minco, and Carey soils. Quinlan soils make up about 8 percent of the mapped areas, Minco soils 5 percent, and Carey soils 2 percent.

Most of this soil is used for wheat. Some areas are in other small grain, grain sorghum, cotton, tame pas-

ture grasses, and native grasses.

The main concerns of management are controlling erosion and maintaining soil fertility and structure. If row crops are grown, terraces with protected outlets (fig. 7) and contour farming are needed. Where terraces are not used, a cropping system is needed that includes only soil-maintaining crops. Returning large amounts of crop residue to the soil and supplying plant nutrients help to maintain content of organic matter and fertility, to retain structure, and to increase the intake rate of water. Capability unit IIIe-1; Loamy Prairie range site; pasture and hayland suitability group 8A; tree suitability group 6.

WoD-Woodward silt loam, 5 to 8 percent slopes.

This soil is sloping.

Included with this soil in mapping are areas of Quinlan and Minco soils. Quinlan soils make up about 10 percent of the mapped areas, and Minco soils 8 percent.

Most of this soil is used for wheat. Some areas are in other small grain, grain sorghum, tame pasture

grasses, and native grasses.

The main concerns of management are controlling erosion and maintaining soil structure and fertility. Returning crop residue to the soil and supplying plant nutrients are good management practices. Terraces with protected outlets, contour farming, and minimum tillage are needed. Capability unit IVe-1; Loamy Prairie range site; pasture and hayland suitability group

8A; tree suitability group 6.

Wt—Woodward-Clairemont complex. These soils are nearly level to strongly sloping. About 45 percent of the complex is Woodward soils that have slopes of 1 to 12 percent, and 25 percent is Clairemont soils that have slopes of 0 to 1 percent. The Woodward soils have a profile similar to the one described as representative for the Woodward series, but the surface layer is silt loam or loam. The Clairemont soils have a profile similar to the one described as representative for the Clairemont series. Woodward and Clairemont soils are in such an intricate pattern that it is impractical to map them separately. Clairemont soils are frequently flooded

Included with these soils in mapping are areas of Quinlan, Carey, St. Paul, and Yahola soils. Quinlan soils make up about 10 percent of the mapped areas, and Carey, St. Paul, and Yahola soils each about 5 percent. Also included are areas of a soil that is similar

20 Soil survey



Figure 7.—Bermudagrass in an outlet in an area of Woodward silt loam, 3 to 5 percent slopes.

to the Clairemont soil, but it is grayer in the uppermost 10 inches. This soil makes up about 5 percent of the mapped areas. Spots of Rock outcrop are also included.

Most of this complex is used as range. Some areas are used for tame pasture.

The main concern of management is keeping the grasses growing vigorously. Capability unit VIe-5; Woodward soils in Loamy Prairie range site, Clairemont soils in Loamy Bottomland range site; Woodward soils in pasture and hayland suitability group 8A, Clairemont soils in 2A; tree suitability group 6.

WwC—Woodward-Quinlan complex. 3 to 5 percent slopes. These gently sloping soils are in such an intricate pattern that it is impractical to map them separately. About 50 percent of the complex is Woodward soils, and about 40 percent is Quinlan soils. Both soils have profiles similar to the ones described as representative of their respective series, but their surface layer is silt loam or loam.

Included with these soils in mapping are areas of a soil that is similar to the Woodward soils but is not calcareous at a depth of 25 to 34 inches. This soil makes up about 3 percent of the complex. Also included are areas of a soil that is similar to the Quinlan soils but is less than 10 inches deep over sandstone or is neutral at a depth of 10 to 20 inches. This soil makes up about 7 percent of the mapped areas.

Most of this complex is used for wheat. Some areas are in other small grain, grain sorghum, tame pasture grasses, and native grasses.

The main concerns of management are controlling erosion and maintaining soil structure and fertility.


Returning crop residue to the soil and supplying plant nutrients are good management practices. Terraces with protected outlets, contour farming, and minimum tillage are needed. Capability unit IVe-1; Woodward part in Loamy Prairie range site, Quinlan part in Shallow Prairie range site; Woodward part in pasture and hayland suitability group 8A, Quinlan part not assigned to a pasture and hayland suitability group; tree suitability group 7.

WwE—Woodward-Quinlan complex, 5 to 12 percent slopes. These sloping to strongly sloping soils are in such an intricate pattern that it is impractical to map them separately. About 50 percent of the complex is Woodward soils, and about 43 percent is Quinlan soils. Both soils have profiles similar to the ones described as representative of their respective series, but their surface layer is loam in places.

Included with Woodward and Quinlan soils in mapping is about 7 percent soils that are similar to Woodward soils but are 40 to 60 inches thick over sandstone. Also included are spots of Rock outcrop and of soils that are similar to Quinlan soils but are less than 10 inches thick over sandstone.

Most of this complex is used as range. The Woodward soils are also used for tame pasture.

The main concern of management is keeping the grasses growing vigorously. Capability unit VIe-6; Woodward part in Loamy Prairie range site, Quinlan part in Shallow Prairie range site; Woodward part in pasture and hayland suitability group 8A, Quinlan part not assigned to a pasture and hayland suitability group; tree suitability group 7.



COMMUNICATION REFERENCE

From:

Alvin Knauf, Public Works Director City of Clinton, Oklahoma 580-323-4330, or 580-592-4554, or mobile phone number (b) (6)

To:

Kent Curtis, Environmental Specialist II Cherokee Nation's Office of Environmental Services (OES) P. O. Box 948 Tahlequah, Oklahoma 74465 918-458-5498

Date and Time: Telephone conversation at 0900 hours on 18 June, 2003

Subject: Drinking water system for Clinton, Oklahoma

Alvin told Kent the following:

Clinton Lake is the primary source of drinking water for the city of Clinton. Clinton Lake is located just north of Interstate Highway 40, halfway between Foss and Canute, approximately 15 to 20 miles west of Clinton. Foss Lake is the backup source of drinking water for the city of Clinton. Foss Lake is located six miles north of Clinton Lake. Clinton does not obtain any drinking water from a groundwater well.

The town of Arapaho buys all its drinking water from Clinton.


United States Environmental Protection Agency Office of Solid Waste and Emergency Response

Publication 9345.1-07 PB92-963377 EPA 540-R-92-026 November 1992

Superfund

\$EPA

Hazard Ranking System Guidance Manual



The Hazard Ranking System Guidance Manual

Interim Final


Hazardous Site Evaluation Division
Office of Solid Waste and Emergency Response
U.S. Environmental Protection Agency
Washington, DC 20460

SPECIAL NOTE

This document was prepared primarily by stereoscopic analysis of high altitude aerial photographs. Wetlands were identified on the photographs based on vegetation, visible hydrology, and geography in accordance with Classification of Wetlands and Deepwater Habitats of the United States (FWS/OBS - 79/31 December 1979). The aerial photographs typically reflect conditions during the specific year and season when they were taken. In addition, there is a margin of error inherent in the use of the aerial photographs. Thus, a detailed on the ground and historical analysis of a single site may result in a revision of the wetland boundaries established through photographic interpretation. In addition, some small wetlands and those obscured by dense forest cover may not be included on this document.

Federal, State and local regulatory agencies with jurisdiction over wetlands may define and describe wetlands in a different manner than that used in this inventory. There is no attempt, in either the design or products of this inventory, to define the limits of proprietary jurisdiction of any Federal, State or local government or to establish the geographical scope of the regulatory programs of government agencies. Persons intending to engage in activities involving modifications within or adjacent to wetland areas should seek the advice of appropriate Federal, State or local agencies concerning specified agency regulatory programs and proprietary jurisdictions that may affect such activities.

SYMBOLOGY EXAMPLE



NOTES TO THE USER

- Wetlands which have been field examined are indicated on the map by an asterisk (*).
- Additions or corrections to the wetlands information displayed on this map are solicited. Please forward such information to the address indicated.
- Subsystems, Classes, Subclasses, and Water Regimes in Italics were developed specifically for NATIONAL WETLANDS INVENTORY mapping.
- Some areas designated as R4SB, R4SBW, OR R4SBJ (INTERMITTENT STREAMS) may not meet the definition of wetland.
- This map uses the class Unconsolidated Shore (US). On earlier NWI maps that class was designated Beach/ Bar (BB), or Flat (FL). Subclasses remain the same in both



U.S. DEPARTMENT OF THE INTERIOR FISH AND WILDLIFE SERVICE

Prepared by National Wetlands Inventory

1989


AERIAL PHOTOGRAPHY

T - Primarily represents upland areas, but may include unclassified wetlands such as man-modified areas, non photo-identifiable areas and/or unintentional omissions.

DATE: 10 / 81 1:58 000 SCALE: __ TYPE:

								٤ -	- ESTUARINE				_				SYSTEM
	2 — INTER	TIDAL			1 — St	UBTIDAL		-				2 — INT	T TERTIDAL I				SUBSYSTEM
C BED	RF — PECF	RS — ROCKY SHORE	US — UNCONSOLIDA SHORE	TED RB — ROCK BOTTOM	UB — UNCONSOLIDATED	AB — AQUATIC BED	RF REEF (<mark>↑</mark> DW — OPEN WATER/ Unknown Bottom	AB — AQUATIC BED	RF — REEF	SB — STREAMBED	RS ROCKY SHORE	US — UNCONSOLIDAT SHORE	ED EM — EMERGENT	SS — SCRUB-SHRUB	FO FORESTED	CLASS
ular <i>ibmergent</i>	1 Coral 3 Worm	1 Bedrock 2 Rubble	1 Cobbie-Gravel 2 Sand 3 Mud 4 Organic	1 Bedrock 2 Rubble	1 Cobble-Gravel 2 Sand 3 Mud 4 Organic	Aigal Rooted Vascular Floating Vascular Floating Vascular Unknown Submergent Unknown Surface	2 Mollusc 3 Worm		Algai Rooted Vascular Floating Vascular Floating Vascular Unknown Submergent Unknown Surface	2 Mollusc 3 Worm	1 Cobbie-Gravel 2 Sand 3 Mud 4 Organic	1 Bedrock 2 Rubble	1 Cobbie-Gravel 2 Sand 3 Mud 4 Organic	2 Nonpersistent	1 Broad-Leaved Decidious 2 Needle-Leaved Decidious 3 Broad-Leaved Evergreen 4 Needle-Leaved Evergreen 5 Dead 6 Decidious 7 Evergreen	1 Broad-Leaved Deciduous 2 Needle-Leaved Deciduous 3 Broad-Leaved Evergreen 4 Neecle-Leaved Evergreen 5 Dead 6 Deciduous 7 Evergreen	Subclass
									L — LACUSTRIN	E			_				SYSTEM
ENNIA	A	NTERMITTENT	5 — UNKNO	T WN PERENNIAL		1 - LIMNETIC						2 — LI	TTORAL				SUBSYSTEM
HORE	US UNCON SHORE	SOLIDATED **EM	EMERGENT C		RB — ROCK UB —	UNCONSOLIDATED AB -	AQUATIC BED	OW OPEN WATER Unknown Bottom	RB — ROCK BOTTOM	UB — UNCONSC BOTTOM		QUATIC ED	RS — ROCKY US-	- UNCONSOLIDATED SHORE	EM - EMERGENT	OW — OPEN WATER/ Unknown Bottom	CLASS
	1 Cobble-Grav 2 Sand 3 Mud 4 Organic 5 Vegetated	al 2 Nonpe	rsistent		I Bedrock 1 Cobb 2 Rubble 2 Sann 3 Mud 4 Orga	d 3 Roote anic 4 Float 5 Unkr	l atic Moss ed Vascular eing Vascular nown Submerger nown Surface	nt	1 Bedrock 2 Rubble	1 Cobble-Gravel 2 Sand 3 Mud 4 Organic	4 Floatin 5 <i>Unkno</i>	c Moss I Vascular Ig Vascular	2 Rübble 2 Sa 3 M 4 O		2 Nonpersistent		Subclass
JBSYSTEM EMS.							soil, o	In order to mor r special modifiers may	e adequately describe wat be applied at the class or	iand and deepw	DDIFIERS vater habitats one or he hierarchy. The far	more of the wate	er regime, water chemistry, ralso be applied to the ecolo	gical system.			
						w	ATER REG	IME			WATER	CHEMISTRY	7	SOIL	SPECIAL MOI	DIFIERS	_
	EM — EMERGE 1 Persistent 2 Nonpersisten	1 Broad-Leaved	1 Broad-Leaved Decid 2 Needle-Leaved Decid 3 Broad-Leaved Decid 3 Broad-Leaved Every 4 Needle-Leaved Ever 5 Dead 6 Deciduous 7 Evergreen	duous reen	A Temporarily Floode B Saturated C Seasonally Floodec Well Drained E Seasonally Floodec Saturated F Sempermanently I G intermittently Expo	d K Artificially Floo d/ W Intermittently Flooded/Temp d/ Y Saturated/Ser Seasonal Z Intermittently	Flooded oded orary orary nipermanent/	K Artificially Floode L Subtidal M Irregularly Exposed N Regularly Flooded P Irregularly Flooded	*R Seasonal-Tidal	1 Hyperhal 2 Euhaline 3 Mixohali 4 Polyhalin 5 Mesohal 6 Oligohali 0 Fresh	tine 7 Hype 8 Eusa 9 Mixo ne 0 Fresi	ersaline sline a ssaline t		Mineral d A	leaver artially Drained/Ditched armed	h Diked/Impounded r Artificial Substrate s Spoil x Excavated	

tidally influenced, freshwater systems



Other information including a narrative report concerning the wetland resources depicted on this document may be available. For information, contact:

Regional Director (ARDE) Region II U.S. Fish and Wildlife Service P.O. Box 1306 Albuquerque, New Mexico 87103

SPECIAL NOTE


This document was prepared primarily by stereoscopic analysis of high altitude aerial photographs. Wetlands were identified on the photographs based on vegetation, visible hydrology, and geography in accordance with Classification of Wetlands and Deepwater Habitats of the United States (FWS/OBS - 79/31 December 1979). The aerial photographs typically reflect conditions during the specific year and season when they were taken. In addition, there is a margin of error inherent in the use of the aerial photographs. Thus, a detailed on the ground and historical analysis of a single site may result in a revision of the wetland boundaries established through photographic interpretation. In addition, some small wetlands and those obscured by dense forest cover may not be included on this document.

Federal, State and local regulatory agencies with jurisdiction over wetlands may define and describe wetlands in a different manner than that used in this inventory. There is no attempt, in either the design or products of this inventory, to define the limits of proprietary jurisdiction of any Federal, State or local government or to establish the geographical scope of the regulatory programs of government agencies. Persons intending to engage in activities involving modifications within or adjacent to wetland areas should seek the advice of appropriate Federal, State or local agencies concerning specified agency regulatory programs and proprietary jurisdictions that may affect such activities.

SYMBOLOGY EXAMPLE

6254 IV SW

- The 1985 A. T. C.




NOTES TO THE USER


- Wetlands which have been field examined are indicate on the map by an asterisk (*).
- Additions or corrections to the wetlands information displayed on this map are solicited. Please forward suc information to the address indicated.


- Subsystems, Classes, Subclasses, and Water Regimes in *Italics* were developed specifically for NATIONAL WETLANDS INVENTORY mapping.
- Some areas designated as R4SB, R4SBW, OR R4SBJ (INTERMITTENT STREAMS) may not meet the definition of wetland.
- This map uses the class Unconsolidated Shore (US).
 On earlier NWI maps that class was designated Beach.
 Bar (BB), or Flat (FL). Subclasses remain the same in both

AERIAL PHOTOGRAPHY

T — Primarily represents upland areas, but may include unclassified wetlands such as man-modified areas, non photo-identifiable areas and/or unintentional omissions.








MODIFIERS


In order to more adequately describe wetland and deepwater habitats one or more of the water regime, viscoil, or special modifiers may be applied at the class or lower level in the hierarchy. The farmed modifier may also be applied to the class or lower level in the hierarchy. The farmed modifier may also be applied at the class or lower level in the hierarchy.


WATER REGIME			W	ATER CHEMIST	RY	
No	n-Tidal	Tid	al	Coastal Halinity	Inland Salinity	
A Temporarity Flooded B Saturated C Seasonally Flooded D Seasonally Flooded/ Well Drained E Seasonally Flooded/ Saturated	H Permanently Flooded J Intermittently Flooded K Artifically Flooded W Intermittently Flooded/Temporary Y Saturated/Semipermanent/ Seasonal	K Artificially Flooded L Subtidal M Irregularly Exposed N Regularly Flooded P Irregularly Flooded	*S Temporary-Tidal *R Seasonal-Tidal *T Semipermanent-Tidal *V Permanent-Tidal *U Unknown	1 Hyperhaline 2 Euhaline 3 Mixohaline (Brackish) 4 Polyhaline 5 Mesohaline 6 Oligohaline 0 Fresh	7 Hypersaline 8 Eusaline 9 Mixosaline 0 Fresh	all Fresh ⁵ a Acid t Circumneutra i Alkaline
F Semipermanently Flooded G Intermittently Exposed	Z Intermittently Exposed/Permanent U Unknown		regimes are only used in need, freshwater systems			

NATIONAL WETLANDS INVENTORY

UNITED STATES DEPARTMENT OF THE INTERIOR







REFERENCE 21

ons or president for a construction of the con

Species presence based on records in the Oklahoma Natural Heritage Inventory, database

County
Organism

	Federal	State	Scientific Name	Common Name
ADAIR				
MUSSELS	С	E	LAMPSILIS RAFINESQUEÁNA	NEOSHO MUCKET
AMPHIBIANS		CS SS2	TYPHLOTRITON SPELAEUS	GROTTO SALAMANDER
		CS SS2	EURYCEA TYNERENSIS	OKLAHOMA SALAMANDER
BIRDS	T	E	HALIAEETUS LEUCOCEPHALUS	BALD EAGLE
MAMMALS	E	E	MYOTIS SODALIS	INDIANA MYOTIS
	E	Æ	CORYNORHÏNUS TOWNSENDII INGENS	OZARK BIG-EARED BAT
	Ε	E	MYOTIS GRISESCENS	GRAY MYOTIS
ALFALFA				
FISH	Т	T	NOTROPIS GIRARDI	ARKANSAS RIVER SHINER
BIRDS	Ť	Ε	HALIAEETUS LEUCOCEPHALUS	BALD EAGLE
	E	E	STERNA ANTILLARUM	LEAST TERN
	T	SS2	CHARADRIUS ALEXANDRINUS	SNOWY PLOVER
ATOKA				
REPTILES		CS SS2	MACROCHELYS TEMMINCKII	ALLIGATOR SNAPPING TURTLE
BIRDS		SS2	AIMOPHILA AESTIVALIS	BACHMAN'S SPARROW
MAMMALS		SS2	PUMA CONCOLOR	MOUNTAIN LION
BEAVER				4
FISH	Т	T	NOTROPIS GIRARDI	ARKANSAS RIVER SHINER
	С	SS2	ETHEOSTOMA CRAGINI	ARKANSAS DARTER
REPTILES		CS SS2	PHRYNOSOMA CORNUTUM	TEXAS HORNED LIZARD
BIRDS		SS1	FALCO MEXICANUS	PRAIRIE FALCON
	,	SS1	BUTEO REGALIS	FERRUGINOUS HAWK
		SS1	AQUILA CHRYSAETOS	GOLDEN EAGLE
	C		TYMPANUCHUS PALLIDICINCTUS	LESSER PRAIRIE-CHICKEN
	E	E	GRUS AMERICANA	WHOOPING CRANE
	Ε	E	STERNA ANTILLARUM	LEAST TERN

County Organism

	Federa	l State	Scientific Name	Common Name
MAMMALS		SS2	DIPODOMYS ELATOR	TEXAS KANGAROO RAT
CRAIG				
INSECTS		SS2	GRYLLOTALPA MAJOR	PRAIRIE MOLE CRICKET
FISH	С	SS2	ETHEOSTOMA CRAGINI	ARKANSAS DARTER
REPTILES		CS SS2	MACROCHELYS TEMMINCKII	ALLIGATOR SNAPPING TURTLE
WILDFLOWER	ST		PLATANTHERA PRAECLARA	WESTERN PRAIRIE FRINGED ORCHID
CREEK				
INSECTS		SS2	GRYLLOTALPA MAJOR	PRAIRIE MOLE CRICKET
FISH	Ť	Т	NOTROPIS GIRARDI	ARKANSAS RIVER SHINER
BIRDS	E	E	STERNA ANTILLARUM	LEAST TERN
		SS2	AIMOPHILA AESTIVALIS	BACHMAN'S SPARROW
MAMMALS		SS2	MARMOTA MONAX	WOODCHUCK
CUSTER				
FISH ·	T	Т	NOTROPIS GIRARDI	ARKANSAS RIVER SHINER
REPTILES		CS SS2	PHRYNOSOMA CORNUTUM	TEXAS HORNED LIZARD
BIRDS	Т	Ε	HALIAEETUS LEUCOCEPHALUS	BALD ÉAGLE
DELAWAR	E			
MUSSELS	С	E	LAMPSILIS RAFINESQUEANA	NEOSHO MUCKET
CRUSTACEAN	IS	Ε	CAMBARUS TARTARUS	OKLAHOMA CAVE CRAYFISH
INSECTS		SS2	GRYLLOTALPA MAJOR	PRAIRIE MOLE CRICKET
FISH.		SS2	MOXOSTOMA MACROLEPIDOTUM	SHORTHEAD REDHORSE
	Т	T	AMBLYOPSIS ROSAE	OZARK CAVEFISH
	С	SS2	ETHEOSTOMA CRAGINI	ARKANSAS DARTER
AMPHIBIANS		CS	EURYCEA LUCIFUGA	CAVE SALAMANDER
		CS SS2	TYPHLOTRITON SPELAEUS	GROTTO SALAMANDER
		CS SS2	EURYCEA TYNERENSIS	OKLAHOMA SALAMANDÉR
BIRDS	T	E	HALIAEETUS LEUCOCEPHALUS	BALD EAGLE
		SS2	AIMOPHILA AESTIVALIS	BACHMAN'S SPARROW
MAMMALS	E	E	MYOTIS GRISESCENS	GRAY MYOTIS
DEWEY				
FISH	Т	T	NOTROPIS GIRARDI	ARKANSAS RIVER SHINER
BIRDS		SS2	ATHENE CUNICULARIA	BURROWING OWL

REFERENCE 22



USGS Digital or thophoto quads

REFERENCE 23

U.S. Census Bureau

State and County QuickFacts

QuickFacts Main | FAQs | What's New



Custer County, Oklahoma

Oklahoma counties - view map

Select a county

Select a state USA QuickFacts

Locate a county by place name

Follow the **1** link for definition and source information.

Browse more data sets for Custer County, Oklahoma

People QuickFacts	Custer County	Oklahoma
Population, 2001 estimate	25,358	3,460,09
Population percent change, April 1, 2000-July 1, 2001	-3.0%	0.3%
Population, 2000	26,142	3,450,654
Population, percent change, 1990 to 2000	-2.8%	9.7%
Persons under 5 years old, percent, 2000	6.1%	6.8%
Persons under 18 years old, percent, 2000	24.3%	25.9%
Persons 65 years old and over, percent, 2000	13.7%	13.29
Female persons, percent, 2000	51.3%	50.9%
White persons, percent, 2000 (a)	81.4%	76.29
Black or African American persons, percent, 2000 (a)	2.9%	7.6%
American Indian and Alaska Native persons, percent, 2000 (a)	5.8%	7.9%
Asian persons, percent, 2000 (a)	0.9%	1.49
Native Hawaiian and Other Pacific Islander, percent, 2000 (a)	Z	0.19
Persons reporting some other race, percent, 2000 (a)	5.8%	2.49
Persons reporting two or more races, percent, 2000	3.2%	4.5%
Persons of Hispanic or Latino origin, percent, 2000 (b)	9.0%	5.2%
White persons, not of Hispanic/Latino origin, percent, 2000	79.3%	74.19
Living in same house in 1995 and 2000, pct age 5+, 2000	50.0%	51.3%
Foreign born persons, percent, 2000	3.4%	3.8%
Language other than English spoken at home, pct age 5+, 2000	9.0%	7.4%
High school graduates, percent of persons age 25+, 2000	81.2%	80.6%
Bachelor's degree or higher, pct of persons age 25+, 2000	22.8%	20.3%
Persons with a disability, age 5+, 2000	4,221	676,09
Mean travel time to work, workers age 16+ (minutes), 2000	15.7	21.
Housing units, 2000	11,675	1,514,40
Homeownership rate, 2000	63.6%	68.49
Housing units in multi-unit structures, percent, 2000	15.7%	15.2%
Median value of owner-occupied housing units, 2000	\$67,800	\$70,70
Households, 2000	10,136	1,342,29
Persons per household, 2000	2.45	2.49

Median household money income, 1999	\$28,524	\$33,400
Per capita money income, 1999	\$15,584	\$17,646
Persons below poverty, percent, 1999	18.5%	14.7%

	Business QuickFacts Cus	ster County	Oklahoma
0	Private nonfarm establishments, 1999	827	84,854
0	Private nonfarm employment, 1999	8,004	1,171,356
0	Private nonfarm employment, percent change 1990-1999	5.6%	24.5%
0	Nonemployer establishments, 1999	1,707	217,991
0	Manufacturers shipments, 1997 (\$1000)	D	37,453,197
0	Retail sales, 1997 (\$1000)	234,992	27,065,555
0	Retail sales per capita, 1997	\$9,197	\$8,166
0	Minority-owned firms, percent of total, 1997	F	10.2%
0	Women-owned firms, percent of total, 1997	31.8%	24.0%
0	Housing units authorized by building permits, 2000	45	11,148
0	Federal funds and grants, 2001 (\$1000)	124,799	22,671,563
0	Local government employment - full-time equivalent, 1997	1,348	129,462

	Geography QuickFacts	Custer County	Oklahoma
0	Land area, 2000 (square miles)	987	68,667
0	Persons per square mile, 2000	26.5	50.3
0	Metropolitan Area	None	·····

Download delimited tables | Download Excel tables

(a) Includes persons reporting only one race.

(b) Hispanics may be of any race, so also are included in applicable race categories.

FN: Footnote on this item for this area in place of data

NA: Not available

D: Suppressed to avoid disclosure of confidential information

X: Not applicable

S: Suppressed; does not meet publication standards

Z: Value greater than zero but less than half unit of measure shown

F: Fewer than 100 firms

Data Quality Statement

What do you think of QuickFacts?

Source U.S. Census Bureau: State and County QuickFacts. Data derived from Population Estimates, 2000 Census of Population and Housing, 1990 Census of Population and Housing, Small Area Income and Poverty Estimates, County Business Patterns, 1997 Economic Census, Minority- and Women-

Owned Business, Building Permits, Consolidated Federal Funds Report, 1997 Census of Governments

Last Revised: Wednesday, 07-May-2003 16:48:35 EDT

Browse more data sets for Custer County, Oklahoma

Census 2000 | Subjects A to Z | Search | Product Catalog | Data Tools | FOIA | Quality |
Privacy · Policies | Contact Us | Census Home

U.S. Census Bureau



American FactFinder

Main | Search | Feedback | FAQs | Glossary | Help



Quick Tables

DP-1. Profile of General Demographic Characteristics: 2000
Data Set: Census 2000 Summary File 1 (SF 1) 100-Percent Data

Geographic Area: Custer County, Oklahoma

NOTE: For information on confidentiality protection, nonsampling error, and definitions, see http://factfinder.census.gov/home/en/datanotes/expsf1u.htm.

SEX AND AGE Male 12 Female 13 Under 5 years 15 10 to 14 years 25 10 to 14 years 20 20 to 24 years 25 25 to 34 years 25 35 to 44 years 35 45 to 54 years 35 55 to 59 years 60 60 to 64 years 36 85 years and over 36 Median age (years) 38 18 years and over 11 Maie 9 Female 11 21 years and over 46 36 years and over 46 36 years and over 46 36 years and over 26 Waite and over 27 Maie 28 Female 21 Packe 22 One race 22 White 22 Black or African American 22 Asian Indian 36 Asian Indian 36 <th>Number</th> <th>Perce</th>	Number	Perce
SEX AND AGE 12 12 13 14 15 15 15 15 15 15 15	20,440	400
Male	26,142	100
Index 5 years	12,728	48
Inder 5 years 10 9 years 10 10 14 years 5 10 19 years 10 10 24 years 5 10 19 years 10 10 24 years 5 10 34 years 5 10 34 years 5 10 44 years 5 10 59 years 10 10 64 years 5 10 59 years 10 10 64 years 5 10 10 49 years 5 10 10 49 years 10 10 64 years 5 10 10 49 years 5 10 10 49 years 10 10 64 years 5 10 10 49 years 10 10 64 years 11 10 10 10 10 10 10 10 10 10 10 10 10 1	13,414	51
10 9 years	13,414	
10 9 years	1,589	
0 to 14 years 5 10 19 years 2 5 to 19 years 3 2 5 to 34 years 3 5 5 to 44 years 5 5 5 to 59 years 3 0 to 64 years 5 5 to 74 years 5 5 to 74 years 5 5 to 84 years 5 5 to 84 years 5 5 years and over 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6 4 6	1,643	
5 to 19 years 0 to 24 years 5 to 34 years 3 5 to 44 years 3 5 to 54 years 3 5 to 54 years 3 5 to 74 years 5 5 to 74 years 5 5 to 84 years 5 5 to 84 years 5 5 years and over 4 Median age (years) 4 8 years and over 1 Male 5 Female 1 1 years and over 1 2 years and over 2 5 years and over 2 6 years and over 2 7 years and over 2 8 years and over 2 9 years and over 2 9 years and over 2 10 years 2 11 years 2 12 years and over 2 2 years and over 2 2 years and over 2 2 years and over	1,823	7
0 to 24 years 3 5 to 34 years 2 5 to 54 years 3 5 to 54 years 3 5 to 59 years 0 0 to 64 years 5 5 to 74 years 5 5 to 84 years 5 5 years and over 15 Median age (years) 15 Male 9 Female 10 1 years and over 11 2 years and over 12 3 years and over 12 4 years and over 12 4 years and over 12 5 years and over 12 4 years and over 2 5 years and over 2 Male 2 Female 2 Male 2 Female 2 White 2 White 2 White 2 White 2 Black or African American 2 Asian Indian 3 Chinese Filipino Japanese 3 </td <td>2,704</td> <td>10</td>	2,704	10
5 to 34 years 5 5 to 44 years 3 5 to 59 years 3 0 to 64 years 5 5 to 74 years 5 5 to 84 years 5 5 years and over 4 Median age (years) 15 8 years and over 15 Male 9 Female 10 1 years and over 11 Male 15 Female 16 Male 16 Female 2 Male 16 Female 2 Male 16 Female 2 Male 2 Female 2 Male 3 Male 4 Male 4 <	3,140	12
5 to 44 years 3 5 to 54 years 3 5 to 59 years 3 5 to 74 years 5 5 to 74 years 5 5 to 84 years 5 5 years and over 4 Male 9 Female 16 1 years and over 11 2 years and over 4 5 years and over 5 Male 6 Female 6 ACE 6 White 2 White 2 Black or African American 2 American Indian and Alaska Native 2 Asian Indian Asian Indian Chinese Filipino Japanese Japanese Korean Vietnamese Other Asian I Native Hawaiian and Other Pacific Islander Native Hawaiian and Other Pacific Islander Native Hawaiian Gumanalan or Chamorro Samoan Other Pacific Islander 2	2,819	10
5 to 54 years 5 5 to 59 years 5 0 to 64 years 5 5 to 74 years 5 5 to 84 years 5 5 years and over 4 Median age (years) 19 Male 9 Female 10 1 years and over 11 2 years and over 2 5 years and over 4 Male 5 Female 2 Acce 2 Diversion of the following of the followi	3,576	13
5 to 59 years 0 to 64 years 5 to 74 years 5 to 74 years 5 to 84 years 5 years and over Median age (years) 18 8 years and over 19 Male 5 Female 10 1 years and over 11 2 years and over 2 Male 5 Female 2 Male 2 White 2 Black or African American 2 Marcican Indian and Alaska Native 3 Asian 4 Asian Indian 4 Chineral 4 Vietnamese 0 Other Asian 1 0 Native Haw	3,065	1
0 to 64 years 5 to 74 years 5 to 74 years 5 to 84 years 5 to 84 years 5 to 84 years and over 1 to 84 years and over 18 Male 9 18 to 84 years and over 19 10 to 84 years and over 11 to 84 years and over 11 to 84 years and over 12	1,186	
5 to 74 years 5 to 84 years 5 years and over 19 Median age (years) 19 Male 19 Female 10 1 years and over 11 2 years and over 2 Male 5 Female 2 MACE 20 White 2 Black or African American 2 American Indian and Alaska Native Asian Asian Asian Indian Chinese Fillpino Japanese Korean Vietnamese Other Asian 1 Native Hawaiian and Other Pacific Islander Native Hawaiian and Other Pacific Islander Native Hawaiian or Chamorro Samoan Other Pacific Islander 2 2	1,1004	
5 to 84 years and over ledian age (years) 8 years and over 11 Male 5 remale 11 years and over 12 years and over 3 years and over 4 Asian and Alaska Native Asian Asian Indian Chinese Fillpino Japanese Korean Vietnamese Other Asian 1 Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2	1,772	
fedian age (years) 8 years and over 19 Male Female 10 1 years and over 2 years and over 5 years and over Male Female 10 11 2 years and over 2 years and over 3 female 12 Male Female 13 Male Female 22 Male Female 23 White Black or African American American Indian and Alaska Native Asian Asian Indian Chinese Filipino Japanese Korean Vietnamese Other Asian Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2	1,772	
ledian age (years) 8 years and over Male Female 10 1 years and over 2 years and over 5 years and over Male Female ACE Me race White Black or African American American Indian and Alaska Native Asian Asian Indian Chinese Fillpino Japanese Korean Vietnamese Other Asian i Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	542	
8 years and over 11 Male 2 Female 1 1 years and over 2 2 years and over 3 5 years and over 4 Male 5 Female 6 Male 7 Female 7 Male 7 Male 7 Female 7 Male 7 Mal	342	
8 years and over 11 Male 2 Female 10 1 years and over 11 2 years and over 2 5 years and over 3 Male 5 Female 4 Male 6 Female 7 Male 7 Male 7 Female 7 Male 7 Male 7 Female 7 Male	32.7	
Male Female 10 1 years and over 11 2 years and over 5 years and over Male Female ACCE One race Diagram American American Indian and Alaska Native Asian Asian Asian Indian Chinese Fillipino Japanese Korean Vietnamese Other Asian Native Hawaiian and Other Pacific Islander Native Hawaiian and Other Pacific Islander Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2	52.1	
Male Female 10 1 years and over 11 2 years and over 2 years and over Male Female ACE Mene race Mite Black or African American American Indian and Alaska Native Asian Asian Indian Chinese Filipino Japanese Korean Vietnamese Other Asian Native Hawaiian and Other Pacific Islander Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2	19,790	7:
Temale	9,484	30
1 years and over 1 2 years and over 2 5 years and over 3 Male 5 Female 2 MACE 7 Mite 8 Mite 9 Mite	10,306	3:
2 years and over 5 years and over Male Female ACE One race White Black or African American American Indian and Alaska Native Asian Asian Indian Chinese Filipino Japanese Korean Vietnamese Other Asian 1 Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2	17,559	6
5 years and over Male Female CACE One race One	4,166	1:
Male Female ACE One race One	3,593	1:
RACE One race Other Asian Other Pacific Islander	1,483	
ACE One race	2,110	
One race 25 White 27 Black or African American American Indian and Alaska Native Asian Asian Indian Chinese Filipino Japanese Korean Vietnamese Other Asian 1 Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2	2,110	
One race 25 White 27 Black or African American American Indian and Alaska Native Asian Asian Indian Chinese Filipino Japanese Korean Vietnamese Other Asian 1 Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2		
White 2: Black or African American American Indian and Alaska Native Asian Asian Indian Chinese Filipino Japanese Korean Vietnamese Other Asian 1 Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2	25,306	9
Black or African American American Indian and Alaska Native Asian Asian Indian Chinese Filipino Japanese Korean Vietnamese Other Asian Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	21,283	8
American Indian and Alaska Native Asian Asian Indian Chinese Fillpino Japanese Korean Vietnamese Other Asian Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander Other Pacific Islander 2		
Asian Asian Indian Chinese Fillpino Japanese Korean Vietnamese Other Asian Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2		
Asian Indian Chinese Filipino Japanese Korean Vietnamese Other Asian Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander 2	229	
Chinese Filipino Japanese Korean Vietnamese Other Asian ¹ Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	76	
Filipino Japanese Korean Vietnamese Other Asian ¹ Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	30	
Japanese Korean Vietnamese Other Asian ¹ Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	28	
Korean Vietnamese Other Asian ¹ Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	13	· · · · · · · · · · · · · · · · · · ·
Vietnamese Other Asian ¹ Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	14	
Other Asian ¹ Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	45	
Native Hawaiian and Other Pacific Islander Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²	23	(
Native Hawaiian Guamanian or Chamorro Samoan Other Pacific Islander ²		
Guamanian or Chamorro Samoan Other Pacific Islander ²	1	
Samoan Other Pacific Islander ²		
Other Pacific Islander ²	3	
Some other race	1,515	
wo or more races	836	

Subject	Number	Percent
White	21,998	84.1
Black or African American	915	3.5
American Indian and Alaska Native	2,036	7.8
Asian	298	1.1
Native Hawaiian and Other Pacific Islander	25	0.1
Some other race	1,743	6.7
Como duna rucc	1,740	0.7
HISPANIC OR LATINO AND RACE		
Total population	26,142	100.0
Hispanic or Latino (of any race)	2,361	9.0
Mexican	1,906	7.3
Puerto Rican	24	0.1
Cuban	24	0.0
Other Hispanic or Latino	429	1.6
Not Hispanic or Latino	23,781	91.0
White alone		79.3
Write alone	20,743	79.3
RELATIONSHIP		
	00.440	400.0
Total population	26,142	100.0
In households	24,878	95.2
Householder	10,136	38.8
Spouse	5,231	20.0
Child	7,063	27.0
Own child under 18 years	5,662	21.7
Other relatives	1,172	4.5
Under 18 years	563	2.2
Nonrelatives	1,276	4.9
Unmarried partner	366	1.4
In group quarters	1,264	4.8
Institutionalized population	520	2.0
Noninstitutionalized population	744	2.8
HOUSEHOLDS BY TYPE		
Total households	10,136	100.0
Family households (families)	6,581	64.9
With own children under 18 years	3,063	30.2
Married-couple family	5,231	51.6
With own children under 18 years	2,295	22.6
Female householder, no husband present	962	9.5
With own children under 18 years	576	5.7
Nonfamily households	3,555	35.1
Householder living alone	2,817	27.8
Householder 65 years and over	1,095	10.8
Households with individuals under 18 years	3,366	33.2
Households with individuals 65 years and over	2,399	23.7
Average household size	2.45	(X)
Average family size	3.05	(X
HOUSING OCCUPANCY		
Total housing units	11,675	100.0
Occupied housing units	10,136	86.8
Vacant housing units	1,539	13.2
For seasonal, recreational, or occasional use	175	1.5
Homeowner vacancy rate (percent)	2.9	(X
Rental vacancy rate (percent)	11.3	(X
HOUSING TENURE		
Occupied housing units	10,136	100.0
Owner-occupied housing units	6,449	63.6
Renter-occupied housing units	3,687	36.4
Average household size of owner-occupied unit	2.57	(X

- (X) Not applicable
 Other Asian alone, or two or more Asian categories.
 Other Pacific Islander alone, or two or more Native Hawaiian and Other Pacific Islander categories.
- ³ In combination with one or more other races listed. The six numbers may add to more than the total population and the six percentages may add to more than 100 percent because individuals may report more than one race. Source: U.S. Census Bureau, Census 2000 Summary File 1, Matrices P1, P3, P4, P8, P9, P12, P13, P17, P18, P19, P20, P23, P27, P28, P33, PCT5, PCT8, PCT11, PCT15, H1, H3, H4, H5, H11, and H12.

U.S. Census Bureau

State and County QuickFacts





Washita County, Oklahoma



Oklahoma counties - view map

Select a county Go

Select a state USA QuickFacts

Locate a county by place name

Follow the **1** link for definition and source information.

Browse more data sets for Washita County, Oklahoma

People QuickFacts	Washita County	Oklahoma
Population, 2001 estimate	11,473	3,460,09
Population percent change, April 1, 2000-July 1, 2001	-0.3%	0.3%
Population, 2000	11,508	3,450,654
Population, percent change, 1990 to 2000	0.6%	9.7%
Persons under 5 years old, percent, 2000	6.1%	6.8%
Persons under 18 years old, percent, 2000	26.3%	25.9%
Persons 65 years old and over, percent, 2000	18.8%	13.29
Female persons, percent, 2000	51.6%	50.9%
White persons, percent, 2000 (a)	92.3%	76.2%
Black or African American persons, percent, 2000 (a)	0.4%	7.6%
American Indian and Alaska Native persons, percent, 2000 (a)	3.0%	7.99
🗘 Asian persons, percent, 2000 (a)	0.3%	1.49
Native Hawaiian and Other Pacific Islander, percent, 2000 (a)	Z	0.19
Persons reporting some other race, percent, 2000 (a)	2.2%	2.49
Persons reporting two or more races, percent, 2000	1.8%	4.5%
Persons of Hispanic or Latino origin, percent, 2000 (b)	4.5%	5.29
White persons, not of Hispanic/Latino origin, percent, 2000	90.4%	74.19
Living in same house in 1995 and 2000, pct age 5+, 2000	59.4%	51.3%
Foreign born persons, percent, 2000	1.6%	3.89
Language other than English spoken at home, pct age 5+, 2000	5.0%	7.49
High school graduates, percent of persons age 25+, 2000	79.7%	80.69
Bachelor's degree or higher, pct of persons age 25+, 2000	15.1%	20.39
Persons with a disability, age 5+, 2000	2,175	676,09
Mean travel time to work, workers age 16+ (minutes), 2000	21.2	21.
Housing units, 2000	5,452	1,514,40
Homeownership rate, 2000	74.7%	68.49
Housing units in multi-unit structures, percent, 2000	3.6%	15.29
Median value of owner-occupied housing units, 2000	\$39,800	\$70,70
Households, 2000	4,506	1,342,29
Persons per household, 2000	2.50	2.4

Median household money income, 1999	\$29,562	\$33,400
Per capita money income, 1999	\$15,528	\$17,646
Persons below poverty, percent, 1999	15.5%	14.7%

	Business QuickFacts Washita County	Oklahoma
0	Private nonfarm establishments, 1999 243	84,854
0	Private nonfarm employment, 1999 1,645	1,171,356
0	Private nonfarm employment, percent change 1990-1999 11.0%	24.5%
0	Nonemployer establishments, 1999 748	217,991
0	Manufacturers shipments, 1997 (\$1000) NA	37,453,197
0	Retail sales, 1997 (\$1000) 46,212	27,065,555
0	Retail sales per capita, 1997 \$3,975	\$8,166
0	Minority-owned firms, percent of total, 1997	10.2%
0	Women-owned firms, percent of total, 1997 17.8%	24.0%
0	Housing units authorized by building permits, 2000 1	11,148
0	Federal funds and grants, 2001 (\$1000) 85,993	22,671,563
0	Local government employment - full-time equivalent, 1997 518	129,462

	Geography QuickFacts	Washita County	Okiahoma
0	Land area, 2000 (square miles)	1,003	68,667
0	Persons per square mile, 2000	11.5	50.3
0	Metropolitan Area	None	

Download delimited tables | Download Excel tables

(a) Includes persons reporting only one race.

(b) Hispanics may be of any race, so also are included in applicable race categories.

FN: Footnote on this item for this area in place of data

NA: Not available

D: Suppressed to avoid disclosure of confidential information

X: Not applicable

S: Suppressed; does not meet publication standards

Z: Value greater than zero but less than half unit of measure shown

F: Fewer than 100 firms

Data Quality Statement

What do you think of QuickFacts?

Source U.S. Census Bureau: State and County QuickFacts. Data derived from Population Estimates, 2000 Census of Population and Housing, 1990 Census of Population and Housing, Small Area Income and Poverty Estimates, County Business Patterns, 1997 Economic Census, Minority- and Women-

Owned Business, Building Permits, Consolidated Federal Funds Report, 1997 Census of Governments

Last Revised: Wednesday, 07-May-2003 16:48:39 EDT

Browse more data sets for Washita County, Oklahoma

Census 2000 | Subjects A to Z | Search | Product Catalog | Data Tools | FOIA | Quality |
Privacy Policies | Contact Us | Census Home

U.S. Census Bureau

American FactFinder

Main | Search | Feedback | FAQs | Glossary | Help



Quick Tables

DP-1. Profile of General Demographic Characteristics: 2000 Data Set: Census 2000 Summary File 1 (SF 1) 100-Percent Data

Geographic Area: Washita County, Oklahoma

NOTE: For information on confidentiality protection, nonsampling error, and definitions, see http://factfinder.census.gov/home/en/datanotes/expsf1u.htm.

Subject	Number	Perce
Total population	11,508	100
SEX AND AGE	71,508	100
Male	5,572	48
emale	5,936	51
enale	5,930	31
Inder 5 years	704	E
to 9 years	759	è
0 to 14 years	936	
5 to 19 years	945	
0 to 24 years	552	
5 to 34 years	1,180	10
35 to 44 years	1,721	15
5 to 54 years	1,418	12
55 to 59 years	606	5
0 to 64 years	527	4
5 to 74 years	1,026	
5 to 84 years	807	7
5 years and over	327	2
Median age (years)	39.2	(
8 years and over	8,486	73
Male	4,001	34
Female	4,485	39
21 years and over	8,046	69
32 years and over	2,455	21
65 years and over Male	2,160	18
Female	882	7
remate	1,278	11
RACE		
One race	11,299	98
White	10,623	92
Black or African American	50	0
American Indian and Alaska Native	342	3
Asian	30	Č
Asian Indian	11	
Chinese	4	(
Filipino	8	C
Japanese	3	C
Korean	2	(
Vietnamese	2	(
Other Asian ¹	0	
Native Hawaiian and Other Pacific Islander	3	C
Native Hawaiian	3	
Guamanian or Chamorro	0	(
Samoan	0	(
Other Pacific Islander ²	0	(
Some other race	251	2
wo or more races	209	1
Race alone or in combination with one or more other races ³		

Subject	Number	Percen
White	10,825	94.1
Black or African American	66	0.6
American Indian and Alaska Native	488	4.2
Asian	40	0.3
Native Hawaiian and Other Pacific Islander	9	0.1
Some other race	294	2.6
HISPANIC OR LATINO AND RACE		
Total population	11,508	100.0
Hispanic or Latino (of any race)	516	4.5
Mexican	382	3.3
Puerto Rican	8	0.1
Cuban	6	0.1
Other Hispanic or Latino	120	1.0
Not Hispanic or Latino	10,992	95.5
White alone	10,406	90.4
RELATIONSHIP		
Total population	11,508	100.0
In households	11,277	98.0
Householder	4,506	39.2
Spouse	2,748	23.9
Child	3,408	29.6
Own child under 18 years	2,793	24.3
Other relatives	360	3.1
Under 18 years	180	1.6
Nonrelatives	255	2.2
Unmarried partner	123	1,1
In group quarters	231	2.0
Institutionalized population	231	2.0
Noninstitutionalized population	q	0.0
HOHOEHOLDS BY TYPE		
HOUSEHOLDS BY TYPE	4 500	400.6
Total households Family households (families)	4,506	100.0
	3,265	72.5
With own children under 18 years Married-couple family	1,513	33.6 61.0
With own children under 18 years	2,748 1,187	26.3
Female householder, no husband present	382	8.5
With own children under 18 years	248	5.5
Nonfamily households	1.044	
Householder living alone	1,241	27.5 25.3
Householder 65 years and over	604	13.4
riodadirodadi do yeara ana over	- 004	10.4
Households with individuals under 18 years	1,631	36.2
Households with individuals 65 years and over	1,399	31.0
The state of the s	1,355	31.0
Average household size	2.50	(X)
Average family size	3.00	(X
HOUSING OCCUPANCY		
Total housing units	5,452	100.0
Occupied housing units	4,506	82.6
Vacant housing units	946	17.4
For seasonal, recreational, or occasional use	60	1.1
Homeowner vacancy rate (percent)	7.7	(X
Rental vacancy rate (percent)	13.0	(X
HOUSING TENURE		
Occupied housing units	4,506	100.0
Owner-occupied housing units	3,366	74.7
	1,140	25.3
Renter-occupied housing units	.,	
renter-occupied nousing units		
Renter-occupied housing units Average household size of owner-occupied unit	2.47	(X)

Page 3 of 3 American FactFinder

- (X) Not applicable ¹ Other Asian alone, or two or more Asian categories.
- Other Pacific Islander alone, or two or more Native Hawaiian and Other Pacific Islander categories.
 In combination with one or more other races listed. The six numbers may add to more than the total population and the six percentages may add to more than 100 percent because individuals may report more than one race.

 Source: U.S. Census Bureau, Census 2000 Summary File 1, Matrices P1, P3, P4, P8, P9, P12, P13, P17, P18, P19, P20, P23, P27, P28, P33, PCT5, PCT8, PCT11, PCT15, H1, H3, H4, H5, H11, and H12.

REFERENCE 24

PRELIMINARY ASSESSMENT RAY WICHERT PROPERTY CL. TON, OKLAHOMA

July 29, 1992

OKLAHOMA STATE DEPARTMENT OF HEALTH

Prepared By

Tim Daly, University of Oklahoma Intern

Reviewed & Approved By

Richard L. Brooks, Sr. Environmental Specialist

Kell J. Buch

Reviewed By

DATE____

Table of Contents

	Topic	1 4805(5)
I.	Introduction	3
II.	Site Characteristic, Operational History, and Waste Characteristics	3 - 5
III.	Pathway and Environmental Hazard Assessment	6 - 8
IV.	Summary and Conclusion	8
		:9
V.	Figures	10
	Figure 1: Vicinity Map	11
	Figure 2: Site Map	
VI.	Photodocumentation	12 - 18
		19-20
VII.	List of References	
3.7777	Deferences	21

I. Introduction

The Oklahoma State Department of Health OSDH) is tasked by the U.S. Environmental Protection Agency (EPA), as authorized by CERCLA and as amended by SARA, under the Multi-Site Cooperative Agreement (CA# V-00645-01) to conduct a preliminary assessment (PA) of the Ray Wichert Property (CERCLIS ID# not yet assigned). As depicted in Figure 1 (Reference 1), this site is approximately a one mile south of the City of Clinton, Custer County, Oklahoma. The primary purpose for this PA is to assess the immediate or potential threat of wastes at the site that may have an impact on public and environmental health and to collect information sufficient to support a decision regarding the need for further action under CERCLA/SARA. The scope of this investigation includes the review of available information from the OSDH files and conducting a comprehensive target survey.

II. Site Description, Operational History, and Waste Characteristics

Site Description

The Ray Wichert Property is primarily located in the NE4 SEC27 T12N R17W I.M. CUSTER COUNTY OK (Reference 1, 2). The two (2) acre site has the coordinates of 35° 29° 24.38" north latitude and 98° 58' 41.03" west longitude (Reference 2). The site is a little less than one (1) mile south of the City of Clinton. The dump is not active and is currently owned by the Oklahoma Bank and Trust Company of Clinton, Oklahoma. (Reference 3, 4). The Ray Wichert Property had apparently operated as a dump between 1969 to 1987 (Reference 3). The site is in a commercial setting (Reference 3). The nearest residence is approximately one tenth (1/10) of a mile directly west of the site (Reference 1, 3). The nearest active domestic well is approximately two and a half (2 1/2) miles to the northeast of the site (Reference 1).

Operational History

According to the Quit Claim Deed dated 10/12/87 between Ray Wichert, Peggy Jo Wichert, and Wic-Hert Inc., and Oklahoma Band and Trust Company of Clinton, Oklahoma, the property, approximately 2.0 acres with a fill of 6 to 8 feet deep, is now owned by the Oklahoma Bank and Trust Company (Reference 4). The person who apparently owned the property originally was Earl Smith. Mr. Smith went bankrupt and Ray Wichert acquired the property. Mr. Wichert then too went bankrupt and had to relinquish the land. The property was then finally sold at an auction on August 25, 1987 to the Oklahoma Bankand Trust Company of Clinton Oklahoma. They currently retain ownership of the property (Reference 4).

At the time of construction, the site had been excavated and was apparently around fifteen (15) feet lower than the east boundary which runs parallel to the railroad track (Reference 3). The property has been used "in the past" as a disposal site for concrete, construction, and asphalt in the City of Clinton. The site has presumably been contaminated with radium by rubble left from a airplane dial refurbishing plant called Sooner Dial Co. of Clinton which is

approximately one (1) mile from the site. Sooner Dial Co. used paint containing radium due to its luminous characteristics. Mr. Grubb, he owner of the Sooner Dial Co. property claims that he hired Sugar Creek Transport, owned by Bill Warner, to haul the rubble off, and that it was Warner who chose to take it to the Ray Wichert Property. According to Mr. Grubb, the "rubble site" was owned by Earl Smith, who openly allowed people to dump dirt, etc. The drainage of surface water is to the north toward the intermittent water course. Multiple samples were taken from the site at different times to determine the extent of contamination on the property. In all of the tests, the results conveyed that the levels of contamination were high enough to warrant removal (Reference 4).

On September 24, 1990, the OSDH sent a letter to the Oklahoma Bank and Trust Company informing the bank of its responsibility to remediate the radiation waste on the property they own, referred to as the "Sooner Dial Co. Rubble site". However, Al Wood, Vice-President of Oklahoma Bank and Trust, disagrees with the claim that they are responsible for the cost of an environmental assessment without "something more than speculation" as to possible contamination. However, field data taken in the past shows a concern for levels of radiation on site (Reference 4).

Waste Characteristics

There are multiple sources of concern that need to be identified and remediated. The first source is the radium contamination due to its radioactivity and its toxicity. There were numerous areas that had elevated readings of radioactivity (Reference 5). The rubble is located within an approximate one acre area of the site (Reference 3). The majority of the rubble is assumed to be from the Sooner Dial Co. site (Reference 3).

Radium is a radioactive earth metal that is brilliant white and tarnishes in air. It decomposes in water and has a melting point of 700° Fahrenheit and a boiling point of 1737° Fahrenheit. It is highly dangerous, and must be kept heavily shielded and stored away from possible dissemination by explosion, flood, ect. It is considered to be a common air contaminant and a highly radiotoxic element. Inhalation, ingestion, or bodily exposure to radium can lead to lung cancer, bone cancer, osteitis, skin damage and blood dyscrasias (Reference 5). Radium replaces calcium in the bone structure and is a source of irradiation to the blood forming organs. The ingestion of luminous dial paint prepared from radium was the cause of death of many of the early dial painters before the hazard was fully understood. ²²⁶Ra decays to ²²²Rn via alpha waves and therefore is considered the parent of radon (Reference 5).

The next source of concern are drums that were found on sight. There were six (6) unmarked drums. The majority of the drums were obviously under pressure and had expanded, but at least one of the drums had ruptured and had leaked an unknown substance. Stressed vegetation marked the area where the leaking had occurred (Reference 3). The final source of con-

cern is a removed underground storage tank (UST) that was above ground. It was estimated to be a 5000 gallon tank. It is unknown if the tank ever had or does contain any hazardous materials (Reference 3).

III. Pathway and Environmental Hazard Assessment

Groundwater

The site, at the time of construction, had been lowered apparently fifteen feet as compared to the west embankment and been covered with a layer of clay. The depth of the clay has not been determined. Under this clav is a layer known as the Terrace Deposits. Terrace Deposits are stream-laid deposits of sand, silt, clay, gravel, and volcanic ash. Its thickness ranges from 0 to about 120 feet. Underlying the Terrace Deposits is the Cloud Chief Formation. It is characterized as being a reddish-brown to orange-brown shale, interbedded with siltstone and sandstone in the middle part and some dolomite and much gypsum in the lower part of the formation. Its thickness is around 400 feet, thinning northward to about 175 feet. The Whitehorse Group forms the next underlying layer. The Whitehorse Group is predominantly orange-brown, fine-grained sandstone. The Rush Springs Formation and the Marlow Formation comprise the Whitehorse Group. The Rush Springs Formation ranges in thickness from 300 feet, thinning northward to about 186 feet. The Marlow Formation, although not as thick, ranges from 100 to around 130 feet thick, gradually thinning to the north. This formation has 2 gypsum and (or) dolomite beds in the upper 20 feet of the formation. Two thin, pink shales occur. The first is about 1 foot below the top and the second is about 55 feet above the base. In the middle of the formation about 25 feet below the previously mentioned gypsum layers and about 85 to 95 feet above the base is the Verden Sandstone Lenti!. It is a coarse-grained, calcareous, fossiliferous sandstone. (Reference 6)

Aquifers are associated with the Terrace Deposits and the Rush Sandspring Formation, and in the vicinity of the site, they; therefore, will be viewed as one aquifer for the duration of this report. Along large streams, deposits consist of clay and silt at the surface which form the Terrace Deposits. It then grades downward into coarse sand and gravel at the base. Water is available from saturated layers of sand and gravel, and yields are highest where the coarse sand and gravel layers are thickest. In areas where an alluvium or terrace aquifer overlies the Rush Springs Sandstone, water is available from either aquifer. In the vicinity of the site the deposits are thin and yields an average 280 gallons per minute (gpm). The Rush Springs Sandstone consists mainly of fine-grained sandstone with some dolomite, shale, and gypsum beds. The Marlow Formation, which is inclusive with the Rush Springs Formation, consists of fine-grained sandstone with much gypsum and shale. The bedrock aquifer in the vicinity of the site is thick, but is assumed to be relatively close to the surface. In addition, it yields an average of 14 gallons per minute (gpm) at the nearest vicinity of the site (Reference 6).

There are private water wells within the area of interest (Reference 3, 7). Populations served by private wells are described below (References 7). The nearest well used for drinking water is about two and a half (2 1/2) miles to the northeast from the site, serving an estimated population of 2.55 (Reference 3, 7, 8, 9). Based on above information, all groundwater users are considered secondary targets.

Distance from Site (mi)	Estimated Populations Served by Private Wells
On-site On-site	0
0 - 1/4	0
1/1 2	0
1/2 - 1	0
1 - 2	0
2 - 3	2.6
3 - 4	5.1
Total	7.7

Surface Water

The nearest perennial stream is just greater than two miles away from the site following the surface water migration route. Accordingly, there is not considered to be a probable point of entry (PPE). Although the general vicinity of the site is outside the flood plane, the site itself might actually be within the 500 year flood plane due to its lowered elevation (Reference 3, 10, 11). The normal annual total precipitation in the site's region is about 25 inches per year (Reference 6).

There are no active surface water intakes located within the 15 mile target distance. Due to the excavated nature of the site, it is possible for the site to be in the flood plane and therefore could have the endangered species habitats associated with it. Habitats of the endangered/threatened species listed below are known to be in Custer County, however; it is unknown if any of these habitats are actually associated with the surface water migration route (Reference 12).

Federal Status
Endangered
Endangered
Endangered
Endangered
Candidate

Soil Exposure

As per the PA Guidance Document, on-site: I contamination is assumed. The site is non-active. There is no one currently working on site (Reference 3). There are no residences, schools, day-care centers within 200 feet or within the site-boundaries (Reference 1, 3, 4). Due to the lack of information, it is assumed (as per the PA Guidance Document) that all of Custer County's terrestrial endangered/threatened species listed under the surface water pathway are on-site (Reference 12).

Air

Due to the composition of the rubble, the heavy vegetation associated with the area, and the excavated landscape, an air release is not suspected. The estimated population and wetland acreage within 4 miles from the site is described below (References 1, 3, 7, 8, 9, 13). There are no "designated" wetlands on-site (Reference 11). As per the PA Guidance Document, it is assumed that the all of Custer County's endangered/threatened species, listed under the surface water pathway, have habitats on site (Reference 12). In addition the prairie mole cricket, which is located in Washita county, could possibly be as near as 1 3/4 miles from the site (Reference 1,12).

Distance from Site (mi)	Estimated Residing Population	Estimated Wetland Acreage
On-site	0	0
0 - 1/4	71.4	1
1/4 - 1/2	63.8	2.5
1/2 - 1	1969	9
1 - 2	3703	40
2-3	3124	60
3 - 4	140.3 (Custer) 50.6 (Washita)	75
Total	9122.1	187.5

IV. Summary and Conclusion

An excavated area in Custer County, Oklahoma had operated as a dump site apparently between 1969 to 1987. The site is known to contain rubble contaminated with radioactive radium, six unlabeled drums, and an unearthed underground storage tank; therefore, the surface may be adversely effected. The surface water has a potential for contamination via floods which poses a threat to the environment and to human targets through food chain contamination. The site is inactive and is heavily vegetated; therefore, the likelihood of human exposure via soil and air is probably minimal. Additionally, the groundwater pathway is also of minimal concern because the nearest domestic well is over two miles from the site.



Photographer: Richard L. Brooks Witness: Tim Daly Date: July 15, 1992 Direction: northwest




Comments: Photograph #1 (matches slide # 3). Picture is of an unearthed underground storage tank on site.

Photographer: Richard L. Brooks Witness: Tim Daly Date: July 15, 1992 Direction: west



Comments: Photograph #3 (matches slide # 13). Picture is of six (6) unlabeled drums and stressed vegetation associated with a leaked substance from the drums.

Photographer: Richard L. Brooks Witness: Tim Daly Date: July 15, 1992 Direction: south




Comments: Photograph #4 (matches slide # 15). Picture is of three (3) fuel islands and an apparently inactive semi-truck repair and cleaning facility.

Photographer: Richard L. Brooks Witness: Tim Daly Date: July 15, 1992 Direction: northwest



Comments: Photograph #5 (matches slide # 17). Picture is of the nearest residences across Tenth Street and the Burlington Northern Railroad.

Photographer: Richard L. Brooks Witness: Tim Daly Date: July 15, 1992 Direction: southeast



Comments: Photograph #6 (matches slide # 19). Picture is of the nearest apparently active facility 66 Music and Vending Inc.

VII. List of References

- 1. U.S. Geological Survey. 7. minute topographic quadrangle maps of: Clinton, Okla. 1983. Bessie, Okla. 1983. Dill City NE, Okla. 1983. Stafford, Okla. 1983.
- 2. Karen Khalafian. USEPA. Standard Operating Procedure to Determine Site Latitude and Longitude Coordinates. April 28, 1992. Calculation Worksheet for the Ray Wichert Property.
- 3. Tim Daly, University of Oklahoma Intern. *Memorandum:* Reconnaissance of the Ray Wichert Property Clinton, Oklahoma. July 15, 1992.
- 4. Tim Daly, University of Oklahoma Intern. *Memorandum:* Operational History. July 13, 1992l.
- 5. N. Irving Sax. Dangerous Properties of Industrial Materials 6th edition. Copyright 1984.
- 6. Oklahoma Geological Survey. MAPS HA-5 Reconnaissance of the Water Resources of the Water Resources of the Clinton Quadrangle, West-Central Oklahoma. The University of Oklahoma, Norman. 1976.
- 7. Tim Daly, University of Oklahoma Intern. *Memorandum:* To Ray Wichert Property PA Air and Groundwater Targets. July 16, 1992.
- 8. United States Department of Commerce. Selected Population and Housing Characteristics: 1990. Custer and Washita Counties, Oklahoma.
- GEMS-1980 Population Data for Ray Wichert Property. Compiled by RLB, OSDH. May 12,1992.
- 10. Ken Morris, the Oklahoma Water Resources Board to Richard L. Brooks. RE. A request letter dated May 14, 1992 regarding flood planes
- 11. U.S. Department of the Interior. Fish and Wildlife Service. 7.5 minute wetland quadrangle maps of: Clinton, Okla. 1990. Bessie, Okla. 1990. Dill City NE, Okla. 1990. Stafford, Okla. 1990.

- 12. U.S. Fish and Wildlife Service. Oklahoma Federal Listed and Proposed and Candidate Threatened and Endangered Species. Custer County. June 1990.
- 13. Karen Khalafian. Wetland Acreage Worksheet. Sheet: Ray Wichert Property. June 22, 1992.

REFERENCE 25

MEMORANDUM April 23, 1986

TO:

Dale McHard, Chief MM

Radiation and Special Hazards Service

FROM:

Robert L. Craig, Director RLC.

Radiation Protection Division

SUBJECT: Radium Contamination on Ray Wichert Property in Clinton, Oklahoma

On April 15, 1986 I took soil samples on the subject property for the purpose of evaluating the degree of radium contamination. I was accompanied by Terry Thiesson and Bob Giger, Custer County sanitarians. Mr. Wichert was not available to accompany us.

The property is on the south side of Clinton and lies just east of U.S. Highway 83 (map attached). On the west side of the property is a railroad track. On the east side is an intermittent water course which drains to the north. On the south side is a car wash. The level of the property is about six feet below the level of the adjoining property.

The property has been used in the past as a disposal site for concrete, asphalt, and dirt from construction sites in the City of Clinton. This debris is in piles up to three feet high which are fairly evenly distributed over the property. The large pieces of concrete and other construction debris prevented easy access to parts of the site. The drainage of surface water is to the north toward the intermittent water course. The soil is thin, estimated to one or two inches above the underlying sandstone.

The property was surveyed with the 1 X I inch NaI detector and the background radiation was found to be about 10 microrentgen per hour (micro R/hr) which is normal for that area in Oklahoma. There were spots in the area where the radiation levels were found to be in excess of 100 micro R/hr. These levels were found in the vicinity of some piles of debris and in the area over which drainage from the piles would have passed.

A rough sketch of the area is attached. The piles of debris near which elevated external gamma radiation levels were found are identified as A, B, C, D, F, and G. The drainage area which was sampled is identified as E.

Samples were taken with a 3/4 inch diameter core sampler which was 8 inches long. At the location where it was possible to obtain an 8 inch core, the samples were divided into two portions, surface to four inches depth and four to eight inches depth, which were analyzed separately. For purposes of comparison a similar sample was collected from the lawn of the State Health Department.

Memorandum April 23, 1986 Page 2


The results of the analyses were:


Sample Point	Depth (inches)	Radium (p C1/gm)
A	0-4	23
A	4-8	33
В	0-4	49
В	4-8	163
C	0-4	27
D	0-4	149
E	0-1	113
F	0-4	37
F	4-8	67
G	0-4	63
OSDH .	0-4	< 4
Shield Background		< 4

Minimum Detectable Concentrations - 4 pCi/gm

Attachments

cc: Terry Thiesson






Wichert Property Clinton, OK

Sample Collection Points

15-APR-86 RLC

S



Samples taken on 4-13-86 pm is mentioned in 4/23/86 mens from Robert Craig to Dale McHard

RECEIVED

APR 3 0 1986

Radiation & Special Hazards Service

Wichert Property Clinton, DK

Sample Collection Points

15-APR-86 RLC

If I ficted up these two sompies before the drop officer form?

Of the let reighty 40 feet NE from from F

W + BF site are regard 15 feet apart

Tily D. Thursen;

REFERENCE 26

BOB ANTHONY
Commissioner

ED APPLE TO: Vert Cut's

DENISE A. BODE
Commissioner



OKLAHOMA CORPORATION COMMISSION PETROLEUM STORAGE TANK DIVISION

(405) 521-4683 FAX: (405) 521-4945

JI M THORPE BLDG, ROOM 238 • P.O. BOX 52000-2000 • OKLAHOMA CITY, OKLAHOMA 73152-2000

March 25, 1999

Oklahoma Bank & Trust P.O. Box 99 Clinton, OK 73061

Reference:

Petroleum storage tank amended notification form for permanent tank closure of

2-12,000 gallon, and 1-20,000 gallon underground storage tank(s) (UST(s)) located at 1401 Industrial Road, Clinton, Oklahoma. Facility #2014103.

Dear Sir:

Thank you for providing your amended notification form and supporting information documenting the permanent closure of your UST(s) at the above referenced facility to the Oklahoma Corporation Commission (OCC).

Based on the information you have provided regarding current site conditions, the OCC believes that there is no contamination of concern at this site at this time. The subject tank(s) is/are hereby considered permanently closed in accordance with OCC UST regulations. Should future environmental problems occur, which the OCC determines are related to this site, additional investigation and corrective action may be required in accordance with State Law.

If you have any questions regarding this matter, please contact me at (405) 521-6397 (phone) or (405) 636-3501 (pager).

Sincerely yours.

Bryan Morris

Environmental Compliance Analyst

cc: Facility file #2014103
James Roberts

SERVICE • ASSISTANCE • COMPLIANCE EXCELLENCE IS OUR STANDARD

TANK CLOSURE SUMMARY SHEET

FACILITY ID NUMBER: 2016 CASE NUMBER (if applicable):				
Comments:				
				·
Number of USTs at facility (repo Number of USTs at facility (actu Number of USTs being closed:	orted): 3 al): 3			
				PHONE #
UKIARAMA BANK + I TUST, 1.0.	Bax 99, Ca	leaton CK -	3061	
TANK ID #:	TANK NO.			TANK NO.
EST DATE LAST USED		2		
EST DATE DAST USED.	-			
EST TANK CAPACITY (gal):				
FAC DATABASE	12 000	12.000	2000	
AFTER CLSR REVIEW				
	14,000	14,000	20,000	
TANK REMOVED (Date):	12-30-98	12-30-48	12-30-18	
TANK CLSD IN GRD(Date):				
TANK EU VERNIGE				
TANK FILLED WITH:				
SCHEDULED CLOSURE: Yes_	; No			•
•	ED: Yes_X	_; No	_	
TESTING FOIL OR GW:		,		
		ATER MW		
EVIDENCE OF LEAK DETECTE	per of USTs at facility (reported): 3 per of USTs at facility (actual): 3 per of USTs being closed: 3 per of USTs being closed: 3 per of USTs being closed: 3 per/OPERATOR: NAME JOB TITLE ADDRESS PHONE # MARE JOB TITLE JOB TITLE TO TITLE # MARE JOB TITLE JOB TITLE TO			
NUMBER OF NEW TANKS INST	TALLED (see	attached 7530) for details):_	0
Rugy Mari		3	-25-99	
Technical Staff Reviewer			Date	

B

FF

RECEIVED UST/AST Dept. NB

OKLAHOMA CORPORATION COMMISSION FEB 0 9 1999 Fuel Division, UST/AST Program P.O. Box 52000-2000 Commission Oklahoma City, OK 73152-2000 (405) 522-4640

CLOSURE REPORT FOR


PERMANENTLY CLOSED UNDERGROUND STORAGE TANKS

PLEASE SUBMIT THIS COMPLETED FORM ALONG WITH ATTACHMENTS WITHIN 45 DAYS OF THE SCHEDULED CLOSURE.


acı	lity Location Name and Address.
	Unnamed Site (vacant)
	1401 Industrial Road
	Clinton, OK
.	r's Name and Address.
	Oklahoma Bank & Trust
	P.O. Box 99
·	Clinton, OK 7:3061
	CITATON, OR AMBI
Date	Work Accomplished. 12/30/98
Jumb	er and size of tanks remaining at this facility.
	None
	· · · · · · · · · · · · · · · · · · ·
	1 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 -
Jumb	er and size of tanks removed. 1 - 20,000 gal. 2 - 12,000 gal
Numb	er and size of tanks removed. 1 - 20,000 gal. 2 - 12,000 gal
Numb	
(a)	Condition of removed tanks. Are there any holes present?
(a)	
(a)	Condition of removed tanks. Are there any holes present?
(a)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted
(a)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s).
(a)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s). To be hauled off and used as culverts & scrap iron. See
(a)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s).
(a) (b)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s). To be hauled off and used as culverts & scrap iron. See attached certificate of disposal
(a) (b)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s). To be hauled off and used as culverts & scrap iron. See attached certificate of disposal If tank system consisted of pressure piping, were samples take
(a)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s). To be hauled off and used as culverts & scrap iron. See attached certificate of disposal
(a) (b)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s). To be hauled off and used as culverts & scrap iron. See attached certificate of disposal If tank system consisted of pressure piping, were samples take least every 40 feet? No. Piping runs less than 40 feet.
(a) (b)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s). To be hauled off and used as culverts & scrap iron. See attached certificate of disposal If tank system consisted of pressure piping, were samples take
(a) (b) (c)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s). To be hauled off and used as culverts & scrap iron. See attached certificate of disposal If tank system consisted of pressure piping, were samples take least every 40 feet? No. Piping runs less than 40 feet. Was excavated soil removed from the site? No.
(a) (b) (c) (d) (e)	Condition of removed tanks. Are there any holes present? No holes observed. Tanks heavily corroded & pitted Describe the disposal and/or disposition of the tank(s). To be hauled off and used as culverts & scrap iron. See attached certificate of disposal If tank system consisted of pressure piping, were samples take least every 40 feet? No. Piping runs less than 40 feet. Was excavated soil removed from the site? No.


からしていることには、 これのでは、 これの

9.	Assess the site for potential contamination by: Soil samples collected (a) testing the soil or groundwater; or for chemical analysis
	(b) using an external leak detection method such as monitoring wells.
	(c) Were field screening instruments used? Yes
,	(d) If so, what was the type and model number? Thermo Environmental Instruments Model 580B OVM
	NOTE: If soil or ground water samples are used for a site assessment, the person taking the samples must be under the supervision of or be a certified UST Consultant.
10.	Certified UST Consultant responsible for the sampling. I certify the samples were taken at locations where contamination had most likely occurred.
	Name James W. Roberts, Energon Services, Inc.
•	Address 6525 N. Meridian. Suite 214
	Oklahoma City, OK 73116 Phone Number (405) 722-7693
	Certification Number 0293
	Signature of Oklahoma Certified UST Consultant:
•	- Fare 1/25/99
	Janus (Coleire Date 1/25/99
11.	A site sketch shall include:
	(a) North arrow
	(b) Tank pit location
	(c) Proximity of tank pit to roads, buildings, or other
	landmarks measured in feet
	(d) Piping layout and pump island location
	(e) Soil sample locations identifying the sample identification
12.	Site Assessment prepared by:
	Name James W. Roberts, Enercon Services, Inc.
	Address 6525 N. Meridian, Suite 214
	Oklahoma City, OK 73116
	Phone Number (405) 722-7693
٤	Signature of Preparer:
	- Janus Caletie Date 1/20/99
Attac	hments:
	(a) Lab reports or records of external leak detection (b) Site sketch



LABORATORY SERVICES





O.D.E.Q. Cartification No. 9522

JANUARY 4, 1999

Laboratory Report No. 9805107

ENERCON SERVICES 6525 N. MERIDIAN, SUITE 214 OKLAHOMA CITY, OK 73116

PROJECT NAME:

OKLAHOMA BANK & TRUST

PROJECT LOCATION:

CLINTON, OK

PROJECT NO.:

ES116

SAMPLE I.D.:

CTPI

SAMPLE MATRIX:

SOIL DECEMBER 30, 1998

DATE SAMPLED: DATE RECEIVED:

DECEMBER 31, 1998

DATE ANALYZED:

JANUARY 4, 1999

TIME ANALYZED:

20:15 BY RANDY KITSMILLER

METHOD	REF	MDL	PARAMETER	SAMPLE RESULTS
8020	EPA	5 ug/kg	BENZENE	ND
8020	EPA	5 ug/kg	TOLUENE	ND
8020	EPA	5 ng/kg	ETHYLBENZENE	ND
8020	EPA	5 ug/kg	TOTAL XYLENES	ND
8020	EPA	•	SURROGATE (Triffuerotoluene) RECOVERY %	94.3 %
8015 M	ODEQ	l mg/kg	Volatile TPH (Gasoline Range Organics)	ND
8000/8100	ODEQ	l mg/kg	Extractable TPH (Diesel Range Organics)	ND

mg/kg M

Milligrams per Kilogram, equivalent to parts per million. Micrograms per Kilogram, equivalent to parts per billion.

ND None Detected above stated detection limits.

Unless ISOTEK receives prior notification, all sample material not consumed in analysis will be retained for a period of 30 days before disposal.

Randy Kitsmiller
Cortified By: 7

LABORATORY SERVICES

4901 West Reno, Suite 175, Oklahoma City, OK 73127-6320 (405) 948-8880 FAX: (405) 948-6015

O.D.E.Q. Certification No. 9522

JANUARY 4, 1999

Laboratory Report No. 9805108

ENERCON SERVICES 6525 N. MERIDIAN, SUITE 214 OKLAHOMA CITY, OK 73116

PROJECT NAME:

OKLAHOMA BANK & TRUST

PROJECT LOCATION:

CLINTON, OK

PROJECT NO.:

ES116

SAMPLE I.D.: SAMPLE MATRIX: CTP2 SOIL

DATE SAMPLED:

DECEMBER 30, 1998 DECEMBER 31, 1998

DATE RECEIVED: DATE ANALYZED:

JANUARY 4, 1999

TIME ANALYZED:

20:52 BY RANDY KITSMILLER

METHOD	REF	MDL	PARAMETER	Sample Results
8020	EPA	5 ug/kg	BENZENE.	ND
8020	EPA	5 ng/kg	TOLUENE	ND
\$ 020	EPA	5 ug/kg	ETHYLBENZENE	ND
8020	EPA	5 ug/kg	TOTAL XYLENES	ND
8020	EPA	-	SURROGATE (Trifluorotoluene) RECOVERY %	100.6 %
8015 M	ODEQ	I mg/kg	Volatile TPH (Gasoline Range Organics)	ND
8000/8100	ODEQ	l mg/kg	Extractable TPH (Diesel Range Organics)	ND

mg/kg	Milligrams per Kilogram, equivalent to parts per million. Micrograms per Kilogram, equivalent to parts per billion
ND	None Detected above stated detection limits.

Unless (SOTEK receives prior notification, all sample material not consumed in analysis will be retained for a period of 30 days before disposal.

Randy Kitsmiller Certified By.

LABORATORY SERVICES

4901 West Reno, State 175, Oklahomat City, OK. 73127-6320 (405) 948-8880 FAX: (405) 948-6015

O.D.E.Q. Certification No. 9522

JANUARY 4, 1999

Laboratory Report No. 9805109

ENERCON SERVICES 6525 N. MERIDIAN, SUITE 214 OKLAHOMA CITY, OK 73116

PROJECT NAME:

OKLAHOMA BANK & TRUST

PROJECT LOCATION:

CLINTON, OK

PROJECT NO.: SAMPLE I.D.: ES116

SAMPLE MATRIX:

CTP3 SOIL

DATE SAMPLED:

DECEMBER 30, 1998

DATE RECEIVED:

DECEMBER 31, 1998 JANUARY 4, 1999

DATE ANALYZED: TIME ANALYZED:

21:28 BY RANDY KITSMILLER

METHOD	REF	MDL	PARAMETER	SAMPLE RESULTS
8020	EPA	5 ug/kg	BENZENE	ND
8020	EPA	5 ug/kg	TOLUENE	ND
8020	EPA	5 ug/kg	ETHYLBENZENE	ND
8020	EPA	5 ug/kg	TOTAL XYLENES	ND
8020	EPA	- * *	SURROGATE (Triffuorotoluene) RECOVERY %	98.8 %
8015 M	ODEO	l me/ke	Volatile TPH (Gasoline Range Organics)	ND
8000/8100	ODEQ	i mg/kg	Extractable TPH (Diesel Range Organics)	ND

mg/kg	Milligrams per Kilogram, equivalent to parts per million.
ug/kg	Micrograms per Kilogram, equivalent to parts per billion.
ND	None Detected above stated detection limits.

Unless ISOTEK receives prior notification, all sample material not consumed in analysis will be retained for a period of 30 days before disposal.

LABORATORY SERVICES

4901 West Rone, Strike 175, Oklahoma City, OK 73127-6320 (405) 948-8880 FAX: (405) 948-6015

O.D.E.Q. Certification No. 9522

JANUARY 4, 1999

Laboratory Report No. 9805110

ENERCON SERVICES 6525 N. MERIDIAN, SUTTE 214 OKLAHOMA CITY, OK 73116

PROJECT NAME:

OKLAHOMA BANK & TRUST

PROJECT LOCATION:

CLINTON, OK

PROJECT NO.:

ES116

SAMPLE I.D.: SAMPLE MATRIX: CTP4

DATE SAMPLED:

SQIL DECEMBER 30, 1998

DATE RECEIVED:

DECEMBER 31, 1998

DATE ANALYZED:

JANUARY 4, 1999

TIME ANALYZED:

22:05 BY RANDY KITSMILLER

METHOD	REF	MDL	PARAMETER	SAMPLE RESULTS
8020	EPA	5 ug/kg	BENZENE	ND
8020	EPA	5 ug/kg	TOLUENE	ND
8020	EPA	5 ug/kg	ETHYLBENZENE	ND
8020	EPA	5 ug/kg	TOTAL XYLENES	ND
8020	EPA	-	SURROGATE (Triffnorotolnene) RECOVERY %	98.9 %
8015 M	ODEO	1 mg/kg	Volatile TPH (Gasoline Range Organics)	ND
8000/8100	ODEQ	1 mg/kg	Extractable TPH (Diesel Range Organics)	ND


mg/kg	Milligrams per Kilogram, equivalent to parts per million.
ng/kg	Micrograms per Kilogram, equivalent to parts per billion.
ND	None Detected above stated detection limits

Unites ISOTEK receives prior notification, all sample meterial not consumed in analysis will be retained for a period of 30 days before disposal.

Certified By

ANALYSIS REQUEST AND CHAIN OF CUSTODY RECORD

	· · · · · · · · · · · · · · · · · · ·																		Page	2	_!		of
				REPOR	TING LABORAT	'ROR	/: <u> </u>	Zs.	στε	÷K-						-		um e					
	' 1	ENERCON SERVICES	S, INC.	Date: 12-31-98									OKLAHOMA BANKE TRUST										
		6525 N. MERIDIAN, S OKLAHOMA CITY, O	K 73116	Name: ENERCON SERVICES, INC.									1 '										
		(405) 722-7693 (405) 722-7694 FAX		Address: 6525 N. MEGIDINI, SUITE 214									Project/Set Number: E 5 / 1 6										
				Contact	: Jim POBE	ucs		P	hone	: 72	2-7	1693	;	Project Location: Custon, OK									
Sampler	's Name	(PRINT): Jim Ro	BENT	l						5/	5/	77			7		7	7			7		
Sampler	's Affiliat	ion:					,	30			/	Ι,	Ι,	Ζ.	Ι,	/,	/	/.	Ι.	/	/,	/	
PRIME LAB ID NO.	NO, & SIZE OF BOTT.	FIELD IDENTIFICATION/ SAMPLE NO.	DATE	TIME	SAMPLE TYPE (Liquid Sludge, etc)	/				?/ /	/		/		/							/	CONDITION ON RECEIPT
	1-402	СТРІ	12/30/18	2:30pm	Soil	×	×	×															
	1-402	CTPZ	12/30/18	3:30pm	Sol	X	×	×															
	1-402	CTP3	12/20/98	3:30pm	Sac	X	×	X															
	1-402	CTP4	12/30/98	3:20pm	Seic	X	X	X														_	
					· · · · · · · · · · · · · · · · · · ·																		
												·											
	,																	_					
;																							
												П											
			 																				
				visher by: (Sign) Date/Time: Received by: (Sign) Wallette 12-31-98 1:03pm Darian James						_							Data Results To: ENERGON SERVICES						
CARRIER	9 :		Relingu	ished by	: (Sign) Date	Tim	e:		Re	ceiv	edst	W: 1	Sigr	i) Di	ete/	Time	9:		<u>. </u>				
BILL NO	-:		Nais	1	Journa 12	-31-	98	4:57	2	7		1	1	a	10	F	4	'5'	2_	,			



January 12, 1999

James Roberts
Enercon Services Inc.
6525 North Meridian
Suite 214
Oklahoma City, OK 73116

RE: Disposal of Tanks

Dear Mr. Roberts:

I hauled off the following described tanks for use on my farms as culverts and scrap iron use. These tanks will not be used in any way for the storage of any petroleum products.

Neptune Drive and Industrial Road - Clinton, OK

1 - 20,000 gallon UST

2 - 12,000 gallon USTS

If you need any furthur information, please contact me.

Sincerely yours

G. W. Lowry, Jr.

STATE OF OKLAHOMA, CUSTER COUNTY, SS: The foregoing instrument was acknowledged before me this 12th day of January 1999 by G. W. Lowry, Jr.

My Commission Expires: 7-22-00

Rhonda G Boyd

Registration for Underground Storage Tanks	STATE USE ONLY
	ID NUMBER
Oklahoma Corporation Commission	DATE RECEIVED
Underground Storage Tank Program	A. Date Entered Into Computer
P.O. Box 52000-2000, Rm 250	B. Data Entry Clerk Initials
Okiahoma City, OK 73152-2000	C. Owner was Contacted to Clarify Responses
TYPE OF NOTIFICATION	Comments:
A. NEW FACILITY B. AMENDED	
C. CLOSURE	
3 No. of tanks at facilityNo. of continuation	
INSTRUC	,
Please type or print in ink. This form must be completed to more than four (4) tanks are owned at this location, photoc to the form.	r each location containing underground storage tanks. If copy the following sheets, and staple continuation sheets
	formation
Notification is required by Federal and State Law for all underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986.	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or	aubmits false information shall be subject to a civi- penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted.
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity)	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S)
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity) Oklahoma Bank & Trust Company	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable Universed.
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity)	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity) Oklahoma Bank & Trust Company 600 Gary Blvd. / P.O. Box 99 Street Address	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. I. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity) Oklahoma Bank & Trust Company 600 Gary Blvd. / P.Q. Box 99	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity) Oklahoma Bank & Trust Company 600 Gary Blvd. / P.Q. Box 99 Street Address Clinton. OK 73601 City & State Zip Code	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity) Oklahoma Bank & Trust Company 600 Gary Blvd. / P.O. Box 99 Street Address Clinton. OK 73601	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. I. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity) Oklahoma Bank & Trust Company 600 Gary Blvd. / P.Q. Box 99 Street Address Clinton. OK 73601 City & State Zip Code (580) 323-2345 (Area Code) Phone Number	aubmits false information shall be subject to a civil penalty not to exceed \$10,000 for each tank for which notification is not given or for which false information is submitted. II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable
underground tanks that have been used to store regulated substances since January 1, 1974, that are in the ground as of May 8, 1985, or that are brought into use after May 8, 1986. 1. OWNERSHIP OF TANK(S) Owner Name (Corporation, Individual, Public Agency, or Other Entity) Oklahoma Bank & Trust Company 600 Gary Blvd. / P.O. Box 99 Street Address Clinton. OK 73601 City & State (580) 323-2345	II. LOCATION OF TANK(S) Facility Name or Company Site Identifier, as applicable

		· · · · · · · · · · · · · · · · · · ·	·*····································											
III. TYPE OF OWNER		IV. 1	INDIAN LANDS											
☐ Federal Government ☐ Com ☐ State Government ☐ Fam ☐ Local Government ☐ Oth ☐ Ban	er'	Reservation o	ated on land within on other trust law	nds.										
V. CO	NTACT PERS	ON IN CHARGE	OF TANKS											
Name Job Tide G. W. Lowry President	Addres P.O. E Clinto		(580) 323	(include Area Code) 3 -23 4 5										
	VI. FINANCI	AL RESPONSIBI	LITY											
I have met the financial respo CFR Subpart H. (Financial Re	nsibility require	ments in accordance	e with 40											
VII. DESCRIPTION OF UNDERGROUND STORAGE TANKS (COMPLETE FOR EACH TANK AT THIS LOCATION.														
Tank Identification Number	Tank No. 1	Tenk No. 2	Tank No. 3	Tank No.										
1. Status of Tank (mark only one) Currently in Use Temporarily Out of Use (Remember to fill out section VIII) Permanently Out of Use (Remember to fill out section VIII)														
2. Date of installation (mo./year)	Unknown	Unknown	Ľn kn own											
3. Estimated Total Capacity (gallons)	20,000	12,000	12,000											
4. Material of Construction (Mark all that apply) Coated or Bara Steel Cathodically Protected Steel Composite (Steel with Fiberglass) Fiberglass Reinforced Plastic Lined Interior Double Walled Polyethylene Tank Jackst Concrete Excavation Liner Unknown Other, Please specify														

Tank Identification Number	Tank No. 1	Tank No. 2	Tank No3_	Tank No
5. Piping (Material) (Mark all that appy) Steel Fiberglass Reinforced Plastic Copper Cathodically Protected Double Walled Secondary Containment Unknown Other, Please specify		X		
6. Piping (Mark all that apply) Pressure Suction: no valve at tank Suction: valve at tank	×	×	×	
7. Substances Currently or Last Stored in Greatest Quantity. Gasoline Diesel Gasohol Kerosene Heating Oil Used Oil Other, Please specify	×	Ž Ž	Y	
Hazardous Substance CAS Number or CERCLA Name		·		
VIII. TAN	KS OUT OF US	SE, OR CHANGE	IN SERVICE	
1. Closing of Tank A. Estimated date last used	Unknown	<u> Ilnknown</u>	Unknown	
B. Estimate date tank closed or removed. (mo./date/year)	12/30/98	12/30/98	12/30/98	
C. Tank was removed from ground. D. Tank was closed in ground. E. Tank filled with inert material. Describe type of material used. F. Change in service.	X	×	¥ E	
2. Site Assessment Completed	Yes	Yes	Yes	
: Evidence of a leak detected	No	No	_No	

Page 3

REFERENCE 27

MEMORANDUM

June 29, 1990

TO:

H. A. Caves, Chief

Consumer Protection Service

FROM:

Paul H. Brown, Director

Radiation Protection Division

SUBJECT:

Radiation Survey of Sooner Dial

On April 24, 1990, Gary Ammon and I traveled to Clinton for the purpose of conducting a radiation survey of the building, land, and rubble which was associated with the Sooner Dial Facility. The present land owner, Ron Grubb, was contacted (403-323-6400), and we received his permission to survey the site. We were also assisted by our local sanitarian, Terry Thiesson.

Areas surveyed were the original site, which consists of a vacant lot call auto shop located at 1000-1004 10th Street, the adjacent alley, and subjunding property (see attached map). In addition, building rubble had been removed and transported to a dumping area approximately two (2) miles south list of the size... This dump area is an isolated field in which fill material had been requested. No further development of this area is now planned.

A madiation survey was performed at all locations utilizing a Ludlum Micro-K (eter. Gamma readings in excess of 50 micro-R per hour (approximately 7 to 8 times background) were noted and those areas delineated on the map. In addition, soil samples were taken for further analysis. Sample numbers and locations are also noted on the accompanying map.

Procedure for Analyzing Soil Samples.

The radium-226 in soil samples were analyzed by Mark Kurklin of the radiochemistry laboratory in June 1990. They were first air dried and then crushed to a granular consistency. (They were not ground with a mortar and pestle.) Each sample was mixed well and a 25 gram aliquot of the soil was weighed into a plastic bottle that was used as the configuration for calibration. A known radium-226 standard was prepared using 25 grams of low background soil in the same plastic bottle configuration.

H. A. Caves 2 June 29, 1990

A gamma spectrum of each soble, the standard, and a blank was collected for 30 minutes on a Canberra Series 90 Multichannel Analyzer. The area under the radium-226, 186.1 KeV energy peak was determined using the gamma spectrum analysis computer software provided by Canberra Industries. The radio-activity due to radium-226 in each of the samples was calculated as proportional to the number of counts under the 186.1 KeV energy peak of the known standard. There was no apparent interference from uranium-235 which has a gamma peak at 185.7 KeV.

Regulatory Limits

Section 14, Table 3, Column 2 of the Oklahoma Radiation Protection Regulations indicates a release limit for insoluble Ra-226 in water as 3×10^{-5} microCuries/ml (30 pico Curie/ml). No specific table exists for soil contamination. However, it is an acceptable practice to convert this table to soil contamination limits by substituting the pCi/ml to pCi/gram. Therefore, the soil contamination limit should be 30 pCi/gram. (Further rationale to support this assumption can be obtained from Dale McHard).

The survey results and observations for each locale follow:

Dump Site

Again, this is a very isolated area containing numerous piles of building rubble. Gamma surveys were conducted, and three areas with elevated readings were staked, and soil samples collected. The results follow:

<u>Area</u>	Gamma Reading	Soil Depth	Activity/gram
1	350 Micro R/hr	0 - 6 In	385 pCi
2	250 Micro R/hr	0 - 6 In	18 pCi
3	200 Micro R/hr	0 - 6 In	226 pCi

This area does contain building rubble with residual radium in concentrations of concern. Due to its isolated location, at this time I would not recommend any removal. However, the area must be observed for any future development plans.

Auto Shop

Gamma surveys indicated three areas on the floor with measurable readings. However, these areas had been painted and marked. Swipe tests indicated no removal contamination. I consider the floor to be acceptable and no further remedial action is needed.

Vacant Lot

A building formerly located at the rear of the auto body shop had been removed in late 1984, and the rubble transported to the dump area previously mentioned. There appears to be concrete in areas of the lot 4 - 6 inches below the surface. The following sample locations (noted on the map) and readings are associated with this lot and the adjacent areas:

REFERENCE 28

EPA REG	ION 6- H	ΙΙΙΝΛΑΝ	LHEA	17		וחו	IIM-S	PF	CIFIC	S	CREFI	MII	NGIE	VF	:I S
Contaminant	CAS No.	MCL or Action	Basis: C= N= sai ma Risk-E	carcii non-c = soi ix= m Base estior	nogenic effectarcinogenic I saturation of aximum coned Screen, inhalation (es)	cts ceffectionce nicentr	ets entration ation Levels	out de	ermal		Ambient A	ir	Tap Water (Residentia Scenario:		Soil Screening Level- Transfers from Soil to:
		Level	w/o dermal w/o dermal Ing									Ingestion 8		Ground water (DAF=1)	
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg
<u></u>	<u> </u>	1 49//	ing/kg		ı mg/kg		1		1		1				
Acetaldehyde	75-07-0		9.3E+00	С	9.7E+00	С	2.1E+01	С	2.3E+01	С	8.7E-01	С	1.5E+00	С	<u> </u>
Acetochlor	34256-82-1		1.2E+03	N	1.6E+03	N	1.2E+04	N	4.1E+04		7.3E+01	N	7.3E+02		
Acetone	67-64-1		1.5E+03	N	1.6E+03	N	5.8E+03	N	6.2E+03		3.7E+02	N	6.1E+02	N	8.0E-0
Acetonitrile	75-05-8		6.2E+02	N	6.2E+02	N	2.0E+03	N	2.0E+03	N	6.2E+01	N			
Acetophenone	98-86-2		5.0E-01	N	5.0E-01	N	1.6E+00	N	1.6E+00	N	2.1E-02	N	4.2E-02	N	
Acrolein	107-02-8		1.0E-01	N	1.0E-01	N	3.4E-01	N	3.4E-01	N	2.1E-02	N	4.2E-02	Ν	
Acrylamide	79-06-1		1.1E-01	С	1.4E-01	С	3.8E-01	С	1.3E+00	С	1.5E-03	С	1.5E-02	C	
Acrylic acid	79-10-7		2.9E+04	N	3.7E+04	N	1.0E+05	max	1.0E+05		1.0E+00	N	1.8E+04	N	
Acrylonitrile	107-13-1		2.0E-01	С	2.1E-01	С	4.6E-01	C	5.2E-01		2.8E-02	С	3.9E-02	С	
Alachlor	15972-60-8	2.0E+00	6.0E+00	С	8.0E+00	С	2.2E+01	С	7.1E+01		8.4E-02	C	8.4E-01	С	
Alar	1596-84-5		9.1E+03	N	1.2E+04	N	9.3E+04	<u>N</u> _	1.0E+05		5.5E+02	N	5.5E+03	N	
Aldicarb	116-06-3		6.1E+01	_N_	7.8E+01	N	6.2E+02	N	2.0E+03		3.7E+00	N	3.7E+01	N	
Aldicarb sulfone	1646-88-4	7.0E+00	6.1E+01	N	7.8E+01	N	6.2E+02	<u>N</u> _	2.0E+03		3.7E+00	<u>N</u> _	3.7E+01	N	
Aldrin	309-00-2		2.8E-02	С	3.8E-02	С	1.0E-01	C	3.4E-01		3.9E-04	С	4.0E-03		5.9E+02
Allyl chloride	107-05-1		3.0E+03		3.9E+03	N	3.1E+04	<u>N</u> _	9.7E+04	-	1.0E+00	N	1.8E+03	N	ļ
Aluminum	7429-90-5		7.8E+04	N	7.8E+04	N	1.0E+05		1.0E+05				3.7E+04	N	
Amdro	67485-29-4		1.8E+01	N	2.3E+01	N	1.9E+02	N_	6.1E+02		1.1E+00		1.1E+01	N	
4-Aminopyridine	504-24-5		1.2E+00	N	1.6E+00	N	1.2E+01	<u>N</u> _	4.1E+01	N	7.3E-02	N	7.3E-01	N	
Ammonia	7664-41-7										1.0E+02	N	4.05.04		
Aniline	62-53-3		8.5E+01		1.1E+02		3.1E+02		1.0E+03		1.0E+00	N_	1.2E+01		0.05.0
Antimony and compounds	7440-36-0	6.0E+00	3.1E+01		3.1E+01		8.2E+02		8.2E+02				1.5E+01		3.0E-0
Antimony pentoxide	1314-60-9	<u> </u>	3.9E+01		3.9E+01	N	1.0E+03		1.0E+03		<u> </u>		1.8E+01		
Antimony tetroxide	1332-81-6		3.1E+01		3.1E+01		8.2E+02		8.2E+02	_			1.5E+01		
Antimony trioxide	1309-64-4	F 05 - 01	3.1E+01		3.1E+01		8.2E+02		8.2E+02				1.5E+01	N	
Arsenic (noncancer endpoint)	7440-38-2	5.0E+01	2.2E+01		2.3E+01		3.6E+02		6.1E+02						
Arsenic (cancer endpoint)	7440-38-2		3.9E-01	С	4.3E-01	С	2.3E+00	<u>_C</u>	3.8E+00	C	4.5E-04	C	4.5E-02	С	1.0E+00

EPA REG	ION 6- H	IUMAN	Basis: C= N=	carcir	H ME nogenic effe carcinogenic saturation	ects c effec	ts	PE	CIFIC	S	CREE	NI	NG LE	VE	ELS	
			max= maximum concentration Risk-Based Screening Levels													
Contaminant	CAS No.	MCL or Action	Soil (inge	estion e rout	, inhalatio es)	n, with	and witho				Ambient A		Tap Water (Residentia		Level- Transfers from Soil to:	
		Level	Resident	tial	Resident w/o dern		Industria	l	Industrial w/o derm		Scenario)		Scenario: Ingestion & Inhalation)	•	Ground water (DAF=1)	
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg	
										T	F 05 001					
Arsine	7784-42-1		5.55.00		7.05.00		F 05.00		4.05.04	<u> </u>	5.2E-02	N	2.25.00	N.1		
Assure	76578-12-6	2.25.22	5.5E+02	N	7.0E+02	N	5.6E+03		1.8E+04		3.3E+01	<u>N</u>	3.3E+02	N		
Atrazine	1912-24-9	3.0E+00	2.2E+00	C	2.9E+00		7.9E+00		2.6E+01		3.1E-02	<u>C</u>	3.0E-01	č		
Azobenzene	103-33-3	0.05.00	4.4E+00		5.8E+00		1.6E+01	<u>C</u>	5.2E+01		6.2E-02	C	6.1E-01	C	0.05.00	
Barium and compounds	7440-39-3	2.0E+03	5.4E+03	N	5.4E+03	N	1.0E+05		1.0E+05		5.2E-01	N	2.6E+03	N	8.2E+0 ²	
Baygon	114-26-1		2.4E+02	N	3.1E+02	N	2.5E+03	N	8.2E+03	N	1.5E+01	N_	1.5E+02 9.1E+02	N N	 	
Baythroid	68359-37-5		1.5E+03	N	2.0E+03	N	1.6E+04	N	5.1E+04 6.1E+04	N	9.1E+01 1.1E+02	N	1.1E+03	N		
Bentazon	25057-89-0	 	1.8E+03		2.3E+03 7.8E+03	N	1.9E+04 6.2E+04	N	1.0E+05		3.7E+02	<u>N</u> N	3.7E+03	N		
Benzaldehyde	100-52-7	5.0E+00	6.1E+03 6.7E-01	N C	6.8E-01	N	1.4E+00	N	1.5E+00		2.5E-01	C	4.2E-01	C	2.0E-03	
Benzene	71-43-2	5.0E+00	2.1E-03		2.8E-03	<u>C</u>	7.6E-03	C	2.5E-02	0	2.9E-05	$\frac{c}{c}$	2.9E-04	$\frac{c}{c}$	2.0E-00	
Benzidine	92-87-5 65-85-0	<u> </u>	1.0E+05		1.0E+05				1.0E+05		1.5E+04	N	1.5E+05	$\frac{c}{N}$	2.0E+01	
Benzoic acid	100-51-6	<u> </u>	1.8E+04	N	2.3E+04	N	1.0E+05		1.0E+05		1.1E+03	N	1.1E+04	N	2.02.101	
Benzyl alcohol Benzyl chloride	100-31-0		8.3E-01	C	8.9E-01	C	2.0E+00	С	2.3E+00		4.0E-02	C	6.6E-02	C		
Beryllium and compounds	7440-41-7	4.0E+00	1.5E+02	N	1.5E+02	N	2.2E+03	$\frac{c}{c}$	2.2E+03		8.0E-04	č	7.3E+01	$\frac{0}{N}$	3.0E+00	
1,1-Biphenyl	92-52-4	4.02.100	2.5E+03	N	3.0E+03	N	1.8E+04	N	3.0E+04	N	1.8E+02	N	· · · · · · · · · · · · · · · · · · ·	N	0.02.00	
Bis(2-chloroethyl)ether	111-44-4		1.9E-01	Ċ	2.1E-01	Ċ	4.9E-01	C	6.2E-01	C	5.8E-03	Ċ	9.8E-03	Ċ	2.0E-05	
Bis(2- chloroisopropyl)ether	39638-32-9		2.6E+00	С	2.9E+00	C	6.6E+00		8.1E+00		1.9E-01	C	2.7E-01	Č		
Bis(chloromethyl)ether	542-88-1		1.9E-04	С	1.9E-04	С	4.2E-04	С	4.4E-04	С	3.1E-05	C	5.2E-05	С		
Bis(2-ethylhexyl)phthalate (DEHP)	117-81-7	6.0E+00	3.5E+01		4.6E+01		1.2E+02	С	4.1E+02	С	4.8E-01	С	4.8E+00	С		
Boron	7440-42-8		5.5E+03	N	7.0E+03	N	5.6E+04	N	1.0E+05	max	2.1E+01	N	3.3E+03	N		
Boron trifluoride	7637-07-2				1.0E+05						7.3E-01	N				
Bromobenzene	108-86-1		2.8E+01	_	2.8E+01		9.2E+01		9.3E+01		1.0E+01	N	2.0E+01	N		
Bromodichloromethane	75-27-4		9.9E-01		1.0E+00		2.2E+00		2.4E+00		1.1E-01	С	1.8E-01		3.0E-02	
Bromoform	75-25-2		6.1E+01		8.1E+01		2.2E+02		7.2E+02		1.7E+00		8.5E+00		4.0E-02	

EPA REGI	ON 6- H	IUMAN			H ME		UM-S	۲Ŀ	CIFIC	5	UKEE	NI	NG LE	VŁ	<u>:L5</u>
			N= sat	non-c = soil	arcinogenic saturation aximum con	effec	ntration								
		MCL	Risk-E	ase	d Screei	ning	Levels								Soil Screening Level- Transfers
Contaminant	CAS No.	or Action	, ,	Soil (ingestion, inhalation, with and without dermal exposure routes) Residential Residential Industrial Industrial Scenario: Ambient Air (Residential (Residential Scenario))											from Soil to:
		Level	Residential		Resident	Residential w/o dermal		Industrial		Industrial w/o dermal			Scenario: Ingestion & Inhalation)		Ground water (DAF=1)
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg
(/-ib		<u> </u>	T -		r		T 1	_	l		T	Γ-	T		
(tribromomethane)	74-83-9	<u> </u>	3.9E+00	N	3.9E+00	N	1.3E+01	N	1.3E+01	N	5.2E+00	N	8.7E+00	N	1.0E-02
Bromomethane	2104-96-3	 	3.9E+00	N	3.9E+02	N	3.1E+03		1.0E+04		1.8E+01		1.8E+02		1.02 02
Bromophos	1689-84-5		1.2E+03	N	1.6E+03	N	1.2E+04		4.1E+04	N	7.3E+01		7.3E+02	N	
Bromoxynil 1.3-Butadiene	106-99-0	 	6.5E-03	C	6.5E-03	C	1.4E-02	C	1.4E-02	c	6.9E-03		1.1E-02	C	
1-Butanol	71-36-3		6.1E+03	N	7.8E+03	Ň	6.2E+04	N	1.0E+05		3.7E+02	N	3.7E+03	N	9.0E-01
Butylate	2008-41-5		3.0E+03	N	3.9E+03	N	3.1E+04	N	1.0E+05		1.8E+02	N	1.8E+03		
n-Butylbenzene	104-51-8		1.4E+02	N	1.4E+02	Ň	2.4E+02	sat	2.4E+02		3.7E+01	N	6.1E+01	N	
sec-Butylbenzene	135-9-88		1.1E+02	N	1.1E+02	N	2.2E+02	sat	2.2E+02		3.7E+01	N	6.1E+01	N	
tert-Butylbenzene	104-5-18		1.3E+02	N	1.3E+02	N	3.9E+02	sat	3.9E+02		3.7E+01	N	6.1E+01	N	
Butyl benzyl phthalate	85-68-7		2.4E+02	sat	2.4E+02	_	2.4E+02	sat	2.4E+02		7.3E+02	N	7.3E+03	N	8.1E+02
Cadmium and compounds	7440-43-9	5.0E+00	3.9E+01	N	3.9E+01	N	1.0E+03		1.0E+03		1.1E-03	С	1.8E+01	N	4.0E-01
Caprolactam	105-60-2		3.0E+04	N	3.9E+04	N	1.0E+05		1.0E+05	max	1.8E+03	N	1.8E+04	N	
Captan	133-06-2		1.4E+02	С	1.8E+02	С	5.0E+02	С	1.6E+03	С	1.9E+00	С	1.9E+01	С	
Carbaryl	63-25-2		6.1E+03	N	7.8E+03	N	6.2E+04	N	1.0E+05	max	4.0E+02	N	3.7E+03	2	
Carbazole	86-74-8		2.4E+01	С	3.2E+01	С	8.7E+01	С	2.9E+02	C	3.4E-01	С	3.4E+00	С	3.0E-02
Carbofuran	1563-66-2	4.0E+01	3.0E+02	N	3.9E+02	N	3.1E+03	N	1.0E+04	N	1.8E+01	N	1.8E+02	Ν	
Carbon disulfide	75-15-0		3.5E+02	N	3.6E+02	N	7.2E+02	sat	7.2E+02	sat	7.3E+02	N	1.0E+03		2.0E+00
Carbon tetrachloride	56-23-5	5.0E+00	2.4E-01	С	2.4E-01	С	5.2E-01	С	5.3E-01	С	1.3E-01		1.7E-01	C	3.0E-03
Carbosulfan	55285-14-8		6.1E+02	N	7.8E+02		6.2E+03		2.0E+04		3.7E+01		3.7E+02		
Chloral	302-17-0		1.2E+02	N	1.6E+02		1.2E+03		4.1E+03		7.3E+00		7.3E+01		
Chloranil	118-75-2		1.2E+00	С	1.6E+00		4.3E+00		1.4E+01		1.7E-02		1.7E-01		
Chlordane	57-74-9	2.0E+00	1.6E+00	С	1.8E+00	С	8.6E+00		1.6E+01		1.9E-02	С	1.9E-01		5.0E-01
Chlorine	7782-50-5		7.8E+03	N	7.8E+03	N	1.0E+05	max	1.0E+05	max		<u> </u>	3.7E+03	N	ļ
Chlorine dioxide	10049-04-4									L	2.1E-01		ļ		
Chloroacetic acid	79-11-8		1.2E+02		1.6E+02		1.2E+03	_	4.1E+03		7.3E+00		7.3E+01	_	
4-Chloroaniline	106-47-8	_	2.4E+02	2	3.1E+02	N	2.5E+03	N	8.2E+03	N	1.5E+01	<u>N</u>	1.5E+02	N	3.0E-02

			N= sa	non-c	nogenic effe carcinogenic saturation aximum cor	ceffect	ntration								
		MCL	Risk-E	Base	d Scree	ning	Levels								Soil Screening Level- Transfers
Contaminant	CAS No.	or Action		Soil (ingestion, inhalation, with and without dermal exposure routes) Ambient Air (Residential											from Soil to:
	1	Level	Residential		Residential w/o dermal		Industria	l	Industrial w/o derm	w/o dermal			Scenario: Ingestion & Inhalation)		Ground water (DAF=1)
	<u> </u>	ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg
<u></u>	11400 00 7	ү	F 4F . 04	N1	E EE . 04!	N.I.	4 05,00	N.I	1.8E+02	N	2.1E+01	N	3.9E+01	N	7.0E-02
Chlorobenzene	108-90-7		5.4E+01	N C	5.5E+01 2.4E+00	N C	1.8E+02 6.5E+00		2.1E+01	C	2.1E+01 2.5E-02	C		C	7.02-02
Chlorobenzilate	510-15-6	 	1.8E+00	N	1.6E+04	N	1.0E+05		1.0E+05		7.3E+02	N	7.3E+03		
p-Chlorobenzoic acid	74-11-3	 	1.2E+04		1.6E+04	N	1.0E+03		4.1E+04	N	7.3E+01	N	7.3E+02	N	
4-Chlorobenzotrifluoride	98-56-6	 	1.2E+03 3.6E+00	_	3.6E+00		1.2E+04 1.2E+01	N	1.2E+01	N	7.3E+00	N	1.4E+01	N	
2-Chloro-1,3-butadiene	109-69-3		4.8E+02		4.8E+02		4.8E+02		4.8E+02		1.5E+03	N	2.4E+03		
1-Chlorobutane	75-68-3		3.4E+02		3.4E+02	sat	3.4E+02	sat	3.4E+02	sat	5.2E+04	N	8.7E+04	N	
1-Chloro-1,1- difluoroethane	11/5-00-3		3.41.102	Sal	3.42.102	Sat	3.46102	Sat	3.42.02	Jul	0.22.04	''	0.72.01		
Chlorodifluoromethane	75-45-6	 	3.4E+02	sat	3.4E+02	sat	3.4E+02	sat	3.4E+02	sat	5.1E+04	N	8.5E+04	N	
2-Chloroethyl vinyl ether	110-75-8														
Chloroform	67-66-3		2.4E-01	С	2.4E-01	С	5.2E-01	С	5.2E-01	С	8.4E-02	C	1.6E-01	С	3.0E-02
Chloromethane	74-87-3		1.2E+00	С	1.2E+00	С	2.6E+00	С	2.7E+00	С	1.1E+00	С	1.5E+00	С	
4-Chloro-2-methylaniline	95-69-2	1	8.3E-01	С	1.1E+00	С	3.0E+00	С	9.9E+00	C	1.2E-02	С	1.2E-01	С	
beta-Chloronaphthalene	91-58-7	1 -	3.3E+03	N	3.9E+03	N	2.0E+04	N	2.7E+04	N	2.9E+02	Z	4.9E+02	N	
o-Chloronitrobenzene	88-73-3		1.3E+01	С	1.5E+01	С	3.7E+01	С	5.9E+01	С	2.7E-01	U	4.5E-01	С	
p-Chloronitrobenzene	100-00-5		1.7E+01	С	2.0E+01	С	4.9E+01	С	7.6E+01	С	3.7E-01	C	6.2E-01	<u>_C</u>	
2-Chlorophenol	95-57-8		6.1E+01	Ν	6.4E+01	N	2.3E+02	N	2.4E+02	N	1.8E+01	Z	3.0E+01	N	2.0E-01
2-Chloropropane	75-29-6		1.7E+02	N	1.7E+02	N	5.8E+02	N	6.0E+02	2	1.0E+02	N	1.7E+02	<u>N</u>	
o-Chlorotoluene	95-49-8		1.5E+02	N	1.6E+02	Ν	5.1E+02	sat	5.1E+02		7.3E+01	N	1.2E+02	N	
Chlorpyrifos	2921-88-2		1.8E+02	Ν	2.3E+02	N	1.9E+03	Z	6.1E+03	Ν	1.1E+01	Ν	1.1E+02		
Chlorpyrifos-methyl	5598-13-0				7.8E+02		6.2E+03		2.0E+04		3.7E+01	N	3.7E+02		
Chromium III	16065-83-1				1.0E+05				1.0E+05			L	5.5E+04	<u>N</u>	<u> </u>
Total Chromium (1/6 ratio Cr VI/Cr III)	18540-29-9	1.0E+02	2.1E+02	С	2.1E+02	С	4.5E+02	C	4.5E+02	C	1.6E-04	С			2.0E+00
Chromium VI	7440-47-3	1.0E+02	3.0E+01	С	3.0E+01	С	6.4E+01	С	6.4E+01	С	2.3E-05	С	1.8E+02		2.0E+00
Cobalt	7440-48-4		3.4E+03		3.4E+03	N	2.9E+04		2.9E+04		2.1E-02	N	2.2E+03	N	
Coke Oven Emissions	8007-45-2	1	<u> </u>		4.1E+03				8.7E+03	С	3.1E-03	C			

EPA REGI	011 0- 11		Basis: C= N= sa	carcir non-c t= soil	nogenic effe arcinogenic saturation	ects c effect conce	ts ntration					Basis: C=carcinogenic effects N=non-carcinogenic effects sat= soil saturation concentration max= maximum concentration													
		MCL	Risk-E	Base	d Scree	ning	Levels								Soil Screening Level- Transfers										
Contaminant	CAS No.	or Action	Soil (inge		, inhalatio	n, with	and with	out de	ermal		Ambient A		Tap Water (Residentia		from Soil										
		Action Level	Residential		Residen w/o dern		Industrial		Industrial w/o dermal		Scenario)		Scenario: Ingestion & Inhalation)		to: Ground water (DAF=1)										
and the second s		ug/l	mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg												
	U	<u> </u>					I= a= a		7.05.04			г	4 45 . 00	-	<u> </u>										
Copper and compounds	7440-50-8	1.3E+03	2.9E+03		2.9E+03	N	7.6E+04		7.6E+04		2.55.02	_	1.4E+03												
Crotonaldehyde	123-73-9		5.3E-03		5.3E-03	C	1.1E-02		1.1E-02		3.5E-03		5.9E-03												
Cumene	98-82-8		1.6E+02	N	1.6E+02	N	5.2E+02	N	5.2E+02	N	4.0E+02	N	6.6E+02	N											
(isopropylbenzene)	21725-46-2		5.8E-01	С	7.6E-01	С	2.1E+00	С	6.8E+00	С	8.0E-03	С	8.0E-02	C											
Cyanazine	n/a		3.0E-U1		7.0⊑-01	<u> </u>	2.15-00	<u> </u>	0.02+00	1 5	0.00-03	-	0.0L-02												
Cyanides Barium cyanide	542-62-1		6.1E+03	N	7.8E+03	N	6.2E+04	N	1.0E+05	may			3.7E+03	N											
Calcium cyanide	592-01-8	ļ	2.4E+03		3.1E+03	N	2.5E+04	-	8.2E+04				1.5E+03												
Copper cyanide	544-92-3		3.0E+02	N	3.9E+02	N	3.1E+03		1.0E+04				1.8E+02	N											
Cyanogen	460-19-5		2.4E+03	N	3.1E+03	N	2.5E+04	N	8.2E+04			_	1.02 02												
Cyanogen bromide	506-68-3		5.5E+03		7.0E+03	N	5.6E+04	N	1.0E+05				3.3E+03	N	<u> </u>										
Cyanogen chloride	506-77-4		3.0E+03		3.9E+03		3.1E+04		1.0E+05				1.8E+03												
Free cyanide	57-12-5	2.0E+02			1.6E+03		1.2E+04		4.1E+04				7.3E+02	N	2.0E+0										
Hydrogen cyanide	74-90-8		1.1E+01	N	1.1E+01	N	3.5E+01	N	3.5E+01	N	3.1E+00	N	6.2E+00	N											
Potassium cyanide	151-50-8		3.0E+03		3.9E+03	N	3.1E+04		1.0E+05	max			1.8E+03	N											
Potassium silver cyanide	506-61-6		1.2E+04	N	1.6E+04		1.0E+05		1.0E+05				7.3E+03	N											
Silver cyanide	506-64-9		6.1E+03	N	7.8E+03		6.2E+04	N	1.0E+05	max			3.7E+03	N											
Sodium cyanide	143-33-9		2.4E+03	N	3.1E+03		2.5E+04	N	8.2E+04	N	7		1.5E+03	N											
Zinc cyanide	557-21-1		3.0E+03	N	3.9E+03	N	3.1E+04	N	1.0E+05	max			1.8E+03	N											
Cyclohexanone	108-94-1		1.0E+05	max	1.0E+05	max	1.0E+05	max	1.0E+05	max	1.8E+04	N	1.8E+05	N											
Cyhalothrin/Karate	68085-85-8		3.0E+02	Ν	3.9E+02	N	3.1E+03	N	1.0E+04	N	1.8E+01	N	1.8E+02												
Cypermethrin	52315-07-8		6.1E+02		7.8E+02		6.2E+03		2.0E+04		3.7E+01		3.7E+02												
Dacthal	1861-32-1		6.1E+02		7.8E+02		6.2E+03		2.0E+04		3.7E+01		3.7E+02												
Dalapon	75-99-0	2.0E+02			2.3E+03		1.9E+04		6.1E+04		1.1E+02		1.1E+03												
DDD	72-54-8		2.4E+00		2.7E+00		1.4E+01		2.4E+01		2.8E-02	_	2.8E-01	С	8.0E-0										
DDE	72-55-9		1.7E+00	-	1.9E+00		1.0E+01		1.7E+01		2.0E-02		2.0E-01		3.0E+0										
DDT	50-29-3	1	1.7E+00	C	1.9E+00	С	1.0E+01	C	1.7E+01	С	2.0E-02	С	2.0E-01	С	2.0E+0										

EPA REGI	ION 6- H	IUMAN					UM-S	PE	CIFIC	S	CREE	NII	NG LE	VE	ELS	
			N= sa	non-e t= soi	nogenic effe carcinogenic I saturation aximum cor	conce	ntration									
		MCL	Risk-E	Base	d Scree	ning	Levels		-					İ	Soil Screening Level- Transfers	
Contaminant	CAS No.	or Action	Soil (ingestion, inhalation, with and without dermal exposure routes) Ambient Air (Residential											al	from Soil to:	
		Level		Residential Residential Industrial Industrial Scenario									Scenario: Ingestion & Inhalation)		Ground water (DAF=1)	
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg	
[B: .	11000 44 5	1	[A 1	7.05.04		Tr 05 : 001		L 4 0E : 001	A.I	2 25 .00	<u> </u>	3.3E+01	N		
Diazinon	333-41-5	 	5.5E+01 2.3E+02	N	7.0E+01	_ <u>N</u>	5.6E+02 2.1E+03		1.8E+03 5.1E+03	N N	3.3E+00 1.5E+01	$\frac{N}{N}$	2.4E+01	$\frac{N}{N}$	 	
Dibenzofuran	132-64-9	<u> </u>	6.1E+02	N	2.9E+02 7.8E+02	N N	6.2E+03		2.0E+04	N	3.7E+01	N	3.7E+02	N	 	
1,4-Dibromobenzene	106-37-6	 	9.7E-01	N C	1.0E+02	C	2.2E+00		2.4E+00	C	8.0E-02	C	1.3E-01	C	2.0E-02	
Dibromochloromethane	124-48-1	- 	3.4E-01	C	4.5E-01	_ C	1.2E+00		4.0E+00	$\frac{c}{c}$	2.1E-01	$\frac{c}{N}$	4.8E-02		2.01-02	
1,2-Dibromo-3- chloropropane	96-12-8		3.4E-01	C	4.56-01	C	1.26+00	C	4.02+00	C	2.1L-01	IN	4.01-02	U	1	
1,2-Dibromoethane	106-93-4	 	5.3E-03	С	6.9E-03	С	1.8E-02	С	4.8E-02	С	8.7E-03	С	7.6E-04	С		
Dibutyl phthalate	84-74-2	 	6.1E+03	Ň	7.8E+03	_ <u>N</u>	6.2E+04		1.0E+05		3.7E+02	N	3.7E+03	N	2.7E+02	
Dicamba	1918-00-9		1.8E+03	N	2.3E+03	N	1.9E+04		6.1E+04	N	1.1E+02	N		N		
1,2-Dichlorobenzene	95-50-1		3.7E+02		3.7E+02	şat	3.7E+02	sat		sat	2.1E+02	N	3.7E+02	N	9.0E-01	
1,3-Dichlorobenzene	541-73-1	6.0E+02	4.1E+01	N	4.1E+01	N	1.4E+02	N	1.4E+02	N	8.4E+00	N	1.7E+01	N		
1,4-Dichlorobenzene	106-46-7		3.1E+00	С	3.2E+00	С	7.0E+00	C	7.5E+00	С	2.8E-01	С	4.7E-01	С	1.0E-01	
3,3-Dichlorobenzidine	91-94-1		1.1E+00	С	1.4E+00	С	3.9E+00	С	1.3E+01	С	1.5E-02	С	1.5E-01	С	3.0E-04	
1,4-Dichloro-2-butene	764-41-0		7.6E-03	С	7.9E-03	С	1.7E-02	С	1.8E-02	С	7.2E-04	С	1.2E-03	С		
Dichlorodifluoromethane	75-71-8		9.4E+01	N	9.4E+01	N	3.1E+02	N	3.1E+02	N	2.1E+02	N	3.9E+02	N		
1,1-Dichloroethane	75-34-3		5.8E+02	N	5.9E+02	N	2.0E+03	N	2.1E+03	N	5.2E+02	N	8.1E+02	N	1.0E+00	
1,2-Dichloroethane (EDC)	107-06-2	5.0E+00	3.4E-01	С	3.5E-01	С	7.5E-01	С	7.7E-01	С	7.4E-02	<u>_C</u>	1.2E-01	С	1.0E-03	
1,1-Dichloroethylene	75-35-4	7.0E+00		С	5.4E-02	С	1.2E-01	С	1.2E-01	С	3.8E-02	С	4.6E-02	С	3.0E-03	
1,2-Dichloroethylene (cis)	156-59-2		4.2E+01	N	4.3E+01	N	1.5E+02	N	1.5E+02	N	3.7E+01	N	6.1E+01	N	2.0E-02	
1,2-Dichloroethylene (trans)	156-60-5	1.0E+02	6.3E+01	N	6.3E+01	N	2.1E+02	N	2.1E+02	N	7.3E+01	N	1.2E+02	N	3.0E-02	
2,4-Dichlorophenol	120-83-2	1	1.8E+02	N	2.3E+02	N	1.9E+03	N	6.1E+03	N	1.1E+01	N	1.1E+02	N	5.0E-02	
4-(2,4- Dichlorophenoxy)butyric Acid (2,4-DB)	94-82-6	7.0E+01	4.9E+02		6.3E+02		5.0E+03		1.6E+04		2.9E+01		2.9E+02			
2,4-Db) 2,4-Dichlorophenoxyacetic Acid (2,4-D)	94-75-7		6.8E+02	N	7.8E+02	N	9.6E+03	N	2.0E+04	N	3.7E+01	N	3.7E+02	N		

EPA REG	ION 6- H	IUMAN	I HEA	\L1	ГН МЕ	EDI	UM-S	PE	CIFIC	; S	CREE	NI	NG LE	VE	LS						
			Basis: C= N= sa	carcir non-c t= soil	nogenic effe carcinogeni I saturation aximum co	ects c effec conce	ts ntration														
		MCL	Risk-E	Base	d Scree	ning	Levels					-			Soil Screening Level-						
Contaminant	CAS No.	or Action																	Tap Water (Residentia	al	Transfers from Soil to:
		Level	Residen		Residen w/o derr		Industria	al	Industria w/o derm		Scenario)		Scenario: Ingestion & Inhalation)		Ground water (DAF=1)						
	1	ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg						
	TI=0 0= =	F 05 05	0.55.01		L o == o :		T 7 5 5 6 4		775 64	Ι Δ	0.05.00		1 4 65 641		1.05.00						
1,2-Dichloropropane	78-87-5	5.0E+00			3.5E-01	C	7.5E-01	Ç	7.7E-01		9.9E-02 5.2E-02		1.6E-01 8.1E-02	C	1.0E-03 2.0E-04						
1,3-Dichloropropene	542-75-6		8.2E-02		8.2E-02		1.8E-01		1.8E-01				1.1E+02	$\frac{c}{N}$	2.UE-U4						
2,3-Dichloropropanol	616-23-9		1.8E+02		2.3E+02		1.9E+03		6.1E+03		1.1E+01 2.3E-02				ļ						
Dichlorvos	62-73-7		1.7E+00		2.2E+00		6.0E+00		2.0E+01				2.3E-01	<u>C</u>	 						
Dicofol	115-32-2		1.1E+00		1.5E+00		4.0E+00		1.3E+01		1.5E-02		1.5E-01 4.2E-01	C N	 						
Dicyclopentadiene	77-73-6		5.5E-01	N	5.5E-01	N	1.8E+00		1.8E+00 3.6E-01		2.1E-01 4.2E-04		4.2E-01 4.2E-03	C	2.0E-04						
Dieldrin	60-57-1		3.0E-02	C N	4.0E-02	C N	1.1E-01		1.2E+04		2.1E+01	N	2.1E+02	$\frac{c}{N}$	2.00-04						
Diethylene glycol, monobutyl ether	112-34-5		3.5E+02	IN	4.5E+02	IN	3.6E+03	IN	1.25+04	IN	2.16701	14		1/1							
Diethylene glycol, monoethyl ether	111-90-0		1.0E+05	max	1.0E+05	max	1.0E+05	max	1.0E+05	max	7.3E+03	N	7.3E+04	N							
Di(2-ethylhexyl)adipate	103-23-1	4.0E+02	4.0E+02	С	5.3E+02	ပြ	1.5E+03	С	4.8E+03	С	5.6E+00	С	5.6E+01	С							
Diethyl phthalate	84-66-2	`	4.9E+04		6.3E+04	Z	1.0E+05	max	1.0E+05	max	2.9E+03	N	2.9E+04	N							
Diethylstilbestrol	56-53-1		1.0E-04	С	1.4E-04	С	3.7E-04	C	1.2E-03	С	1.4E-06	С	1.4E-05	С							
Difenzoquat (Avenge)	43222-48-6		4.9E+03	N	6.3E+03	N	5.0E+04	N	1.0E+05	max	2.9E+02	N	2.9E+03	N							
1,1-Difluoroethane	75-37-6		1.0E+05	max	1.0E+05	max	1.0E+05	max	1.0E+05	max	4.2E+04	N	6.9E+04	N							
Diisopropyl methylphosphonate	1445-75-6		4.9E+03	N	6.3E+03	Ν	5.0E+04	N	1.0E+05	max	2.9E+02	N	2.9E+03	N							
3,3'-Dimethoxybenzidine	119-90-4		3.5E+01	С	4.6E+01	ပြ	1.2E+02	С	4.1E+02	С	4.8E-01	С	4.8E+00	С							
Dimethylamine	124-40-3		6.4E-02	N	6.7E-02	Ν	2.4E-01	N	2.5E-01	N	2.1E-02	N	3.5E-02	N							
N-N-Dimethylaniline	121-69-7		1.2E+02		1.6E+02	N	1.2E+03	N	4.1E+03	N	7.3E+00	N	7.3E+01	N							
2,4-Dimethylaniline	95-68-1		6.4E-01		8.5E-01		2.3E+00		7.6E+00	С	9.0E-03		9.0E-02	С							
2,4-Dimethylaniline hydrochloride	21436-96-4		8.3E-01		1.1E+00		3.0E+00		9.9E+00		1.2E-02	С	1.2E-01	С							
3,3'-Dimethylbenzidine	119-93-7		5.3E-02	С	7.0E-02	С	1.9E-01	С	6.2E-01	С	7.3E-04	С	7.3E-03	С							
1,1-Dimethylhydrazine	57-14-7		1.9E-01		2.5E-01		6.7E-01		2.2E+00		1.9E-03		2.6E-02								
1,2-Dimethylhydrazine	540-73-8	1	1.3E-02		1.7E-02		4.7E-02		1.5E-01		1.8E-04		1.8E-03								

EPA REG	ION 6- H	IUMAN	Basis: C= N=	carcir	H ME nogenic effe carcinogenic saturation	cts c effec	ts	PE	CIFIC	S	CKEE	NII	NG LE	VE	:LS
		MCL	ma	ix= m	aximum cor d Scree	ncentra	ation								Soil Screening Level- Transfers
Contaminant	CAS No.	or Action	Soil (inge		i, inhalatior es)	n, with	and withou	out de	ermal		Ambient A (Residenti		Tap Water (Residentia	ıl	from Soil to:
		Level	Resident		Resident w/o dern		Industria	l	Industrial w/o derma		Scenario)		Scenario: Ingestion 8 Inhalation)		Ground water (DAF=1)
	<u> </u>	ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg
	TT:	· · · · · · · · · · · · · · · · · · ·	0.45.61		7.05.61		In of . col		L 0.05.001		0.75.00	<u> </u>	1 275,041	NI.	
Dimethylphenethylamine	122-09-8	ļ	6.1E+01	N	7.8E+01	<u>N</u>	6.2E+02	<u>N</u>	2.0E+03		3.7E+00 7.3E+01		3.7E+01 7.3E+02	N N	4.0E-01
2,4-Dimethylphenol	105-67-9		1.2E+03	N	1.6E+03	N	1.2E+04	N N	4.1E+04 1.2E+03		2.2E+00		2.2E+01	N	4.0E-01
2,6-Dimethylphenol	576-26-1	 	3.6E+01 6.1E+01	N	4.7E+01 7.8E+01	N N	3.7E+02 6.2E+02	N N	2.0E+03		3.7E+00		3.7E+01	N	<u> </u>
3,4-Dimethylphenol	95-65-8		1.0E+05		1.0E+01		1.0E+05		1.0E+05		3.7E+04	N	3.7E+05	N	
Dimethyl phthalate	131-11-3		1.0E+03	N	1.6E+02	N	1.2E+03	N	4.1E+03		7.3E+00	N	7.3E+01	N	
4,6-Dinitro-o-cyclohexyl	131-09-3		1.2L+02	IN	1.01.702	IN	1.22.03	11	4.12.03	14	7.5E.00	1.4	7.52.01	•	
1,2-Dinitrobenzene	528-29-0		2.4E+01	N	3.1E+01	N	2.5E+02	N	8.2E+02	N	1.5E+00	N	1.5E+01	N	
1,3-Dinitrobenzene	99-65-0	 	6.1E+00	N	7.8E+00	- N	6.2E+01	N	2.0E+02	N	3.7E-01	N		N	
1,4-Dinitrobenzene	100-25-4		2.4E+01	N	3.1E+01	N	2.5E+02	N	8.2E+02	N	1.5E+00	N	1.5E+01	N	
2,4-Dinitrophenol	51-28-5	Ī	1.2E+02	N	1.6E+02	N	1.2E+03	N	4.1E+03	N	7.3E+00	N	7.3E+01	N	1.0E-02
Dinitrotoluene mixture	25321-14-6		7.1E-01	С	9.4E-01	C	2.6E+00	С	8.4E+00	С	9.9E-03	C	9.9E-02	С	4.0E-05
2,4-Dinitrotoluene	121-14-2		1.2E+02	N	1.6E+02	N	1.2E+03	N	4.1E+03	N	7.3E+00	N	7.3E+01	N	4.0E-05
2,6-Dinitrotoluene	606-20-2		6.1E+01	N	7.8E+01	N	6.2E+02	N	2.0E+03	N	3.7E+00	N	3.7E+01	N	3.0E-05
Dinoseb	88-85-7	7.0E+00	6.1E+01	N	7.8E+01	N	6.2E+02	N	2.0E+03	N	3.7E+00	N	3.7E+01	N	
di-n-Octyl phthalate	117-84-0		1.2E+03	N	1.6E+03	N	1.2E+04	N	4.1E+04	N	7.3E+01	N	7.3E+02	N	1.0E+04
1,4-Dioxane	123-91-1		4.4E+01	С	5.8E+01	С	1.6E+02	С	5.2E+02	С	6.1E-01	С	6.1E+00	С	
Dioxin (2,3,7,8-TCDD)	1746-01-6		3.9E-06	С	4.3E-06	С	2.3E-05	С	3.8E-05	С	4.5E-08	C	4.5E-07	С	
Diphenylamine	122-39-4		1.5E+03	N	2.0E+03	N	1.6E+04	N	5.1E+04	Ν	9.1E+01	N	9.1E+02	N	
1,2-Diphenylhydrazine	122-66-7		6.0E-01	С	8.0E-01		2.2E+00	С	7.2E+00		8.7E-03	<u></u>	8.4E-02	С	
Diphenyl sulfone	127-63-9		5.5E+02		7.0E+02		5.6E+03		1.8E+04		3.3E+01		3.3E+02		
Diquat	85-00-7	2.0E+01	1.3E+02		1.7E+02		1.4E+03		4.5E+03		8.0E+00		8.0E+01		
Disulfoton	298-04-4				3.1E+00		2.5E+01		8.2E+01		1.5E-01		1.5E+00		
1,4-Dithiane	505-29-3		6.1E+02		7.8E+02		6.2E+03	N	2.0E+04		3.7E+01		3.7E+02		
Diuron	330-54-1		1.2E+02	N	1.6E+02	<u>N</u> _	1.2E+03	N_	4.1E+03		7.3E+00		7.3E+01	_	<u> </u>
Endosulfan	115-29-7		3.6E+02		4.7E+02		3.7E+03	N	1.2E+04		2.2E+01			N	9.0E-01
Endothall	145-73-3	1.0E+02	1.2E+03	N	1.6E+03	N	1.2E+04	N	4.1E+04	<u>N</u>	7.3E+01	N	7.3E+02	N	

EPA REG	ION 6- H	UMAN	HEA	\L1	Н МЕ	DI	UM-S	PE	CIFIC	S	CREE	NII	NG LE	VE	LS
			Basis: C= N= sa	carcir non-c t= soil	nogenic effectoriogenic saturation aximum co	ects c effec conce	ts ntration								
		MCL	Risk-E	Base	d Scree	ning	Levels								Soil Screening Level- Transfers
Contaminant	CAS No.	or	Soil (inge		, inhalation	n, with	and with	out de	ermal		Ambient A		Tap Water (Residentia		from Soil to:
		Action Level	Resident		Residen w/o dern		Industria	ıl	Industrial w/o derm		Scenario)	1	Scenario: Ingestion & Inhalation)	,	Ground water (DAF=1)
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg
													1 45.04		50500
Endrin	72-20-8	2.0E+00	1.8E+01	N	2.3E+01	N	1.9E+02		6.1E+02	N	1.1E+00		1.1E+01		5.0E-02
Epichlorohydrin	106-89-8		7.5E+00	N	7.6E+00		2.5E+01	N	2.6E+01	N	1.0E+00	-	2.0E+00		
Ethion	563-12-2		3.0E+01	N	3.9E+01	N	3.1E+02		1.0E+03	N	1.8E+00		1.8E+01		
2-Ethoxyethanol	110-80-5		2.4E+04	N	3.1E+04	N	1.0E+05		1.0E+05		2.1E+02		1.5E+04	N	
2-Ethoxyethanol acetate	111-15-9		1.8E+04	N	2.3E+04	N	1.0E+05		1.0E+05		1.1E+03		1.1E+04	N	
Ethyl acetate	141-78-6		1.7E+04	N	1.9E+04		3.7E+04	_	3.7E+04		3.3E+03	N	5.5E+03	N	7.05.04
Ethylbenzene	100-41-4	7.0E+02	2.3E+02		2.3E+02		2.3E+02		2.3E+02	sat	1.1E+03	N	1.3E+03	N	7.0E-01
Ethyl chloride	75-00-3		1.6E+03		1.6E+03		1.6E+03		1.6E+03	sat	1.0E+04	N	8.6E+03		
Ethylene diamine	107-15-3		1.2E+03		1.6E+03		1.2E+04		4.1E+04		7.3E+01	N	7.3E+02	N	
Ethylene glycol	107-21-1		1.0E+05	_	1.0E+05		1.0E+05		1.0E+05	_	7.3E+03	-	7.3E+04	N	
Ethylene glycol, monobutyl ether	111-76-2		3.5E+02	N	4.5E+02	N	3.6E+03		1.2E+04	N	2.1E+01	N	2.1E+02	N	
Ethylene oxide	75-21-8		1.3E-01	С	1.4E-01	С	3.1E-01		3.6E-01	С	1.9E-02		2.4E-02	С	
Ethylene thiourea (ETU)	96-45-7		4.4E+00	С	5.8E+00	С	1.6E+01		5.2E+01	ပ	6.1E-02	С	6.1E-01	С	
Ethyl ether	60-29-7		1.8E+03		1.8E+03	sat	1.8E+03		1.8E+03	sat	7.3E+02	N	1.2E+03		
Ethyl methacrylate	97-63-2		1.4E+02	sat	1.4E+02	sat	1.4E+02		1.4E+02	sat	3.3E+02	N	5.5E+02		
Fenamiphos	22224-92-6		1.5E+01	N	2.0E+01	N	1.6E+02		5.1E+02	N	9.1E-01	N	9.1E+00		
Fluometuron	2164-17-2		7.9E+02	N	1.0E+03		8.1E+03		2.7E+04	N	4.7E+01	N	4.7E+02	N	
Fluoride	16984-48-8		3.6E+03	N	4.7E+03		3.7E+04		1.0E+05				2.2E+03		
Fomesafen	72178-02-0		2.5E+00		3.4E+00		9.2E+00		3.0E+01		3.5E-02		3.5E-01		ļ
Fonofos	944-22-9		1.2E+02		1.6E+02		1.2E+03		4.1E+03		7.3E+00		7.3E+01		ļ
Formaldehyde	50-00-0		9.1E+03		1.2E+04		9.3E+04		1.0E+05		1.5E-01		5.5E+03		
Formic Acid	64-18-6				1.0E+05				1.0E+05		7.3E+03		7.3E+04		
Furan	110-00-9		2.5E+00		2.5E+00		8.5E+00		8.6E+00		3.7E+00		6.1E+00		<u> </u>
Furazolidone	67-45-8		1.3E-01		1.7E-01		4.6E-01		1.5E+00		1.8E-03		1.8E-02		ļ
Furfural	98-01-1		1.8E+02		2.3E+02		1.9E+03		6.1E+03		5.2E+01	_	1.1E+02		
Glycidaldehyde	765-34-4	<u> </u>	2.4E+01	N	3.1E+01	N	2.5E+02	N_	8.2E+02	N	1.0E+00	LN_	1.5E+01	N	L

EPA REG	ION 6- H	IUMAN	N HEA	۱L	ГН МЕ	EDI	UM-S	PE	CIFIC	S	CREE	NI	NG LE	VE	ELS
			N: sa	=non- it= so	nogenic efficarcinogeni I saturation I aximum co	c effec	entration								
		MCL	Risk-E	3ase	ed Scree	ning	, Levels								Soil Screening Level- Transfers
Contaminant	CAS No.	or Action	Soil (inge		n, inhalatio tes)	n, witl	h and with	out d	ermal		Ambient A		Tap Water (Residentia		from Soil
		Level	Residen		Residen w/o derr		Industria	al	Industria w/o derm		Scenario)		Scenario: Ingestion 8 Inhalation)	×	to: Ground water (DAF=1)
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		mg/kg		
Churhanata	H4074 00 0	7.05.00	0.45.00	1 61	7.05.00		IC 05 : 01		1 4 05 : 05	1	0.75.65		1 0 75 00	••	
Glyphosate	1071-83-6 76-44-8	7.0E+02 1.0E-01	6.1E+03 1.1E-01		7.8E+03 1.4E-01		6.2E+04 3.9E-01		1.0E+05				3.7E+03		4.05.06
Heptachlor	1024-57-3					C			1.3E+00		1.5E-03		1.5E-02	C	1.0E+00
Heptachlor epoxide Hexabromobenzene	87-82-1	2.0E-01	0E-01 5.3E-02 C 7.0E-02 C 1.9E-01 C 6.3E-01 C 7.4E-04 C 7.4E-03 C										3.0E-02		
Hexachlorobenzene	118-74-1	1.051.00	1.2E+02 3.0E-01	N C	1.6E+02 4.0E-01	N C	1.2E+03 1.1E+00		4.1E+03		7.3E+00		7.3E+01	N	4.05.04
Hexachlorobutadiene	87-68-3	1.05+00	6.2E+00		8.2E+00	0	2.2E+01	C	3.6E+00 7.3E+01	C	4.2E-03 8.7E-02		4.2E-02 8.6E-01	C	1.0E-01
HCH (alpha)	319-84-6		9.0E-02	C	1.0E-01	C	4.8E-01	C	9.1E-01	C	1.1E-02		1.1E-02	$\frac{c}{c}$	1.0E-01 3.0E-05
HCH (beta)	319-85-7		3.1E-01	c	3.6E-01	C	1.7E+00		3.2E+00	C	3.7E-03		3.7E-02	$\frac{c}{c}$	1.0E-04
HCH (gamma) Lindane	58-89-9	2.0E-01	4.4E-01	C	4.9E-01	$\frac{c}{c}$	2.3E+00		4.4E+00	C	5.2E-03		5.2E-02	$\frac{c}{c}$	5.0E-04
HCH-technical	608-73-1	2.0L-01	3.1E-01	c	3.6E-01	C	1.7E+00		3.2E+00		3.8E-03		3.7E-02	$\frac{c}{c}$	1.0E-04
Hexachlorocyclo-	77-47-4	5.0E+01		l ŏ	5.4E+02	N	4.2E+03		1.3E+04	N	7.3E-02	N	2.6E+02	$\frac{\sigma}{N}$	2.0E+01
pentadiene	'' ''' '	0.02.01	7.22.02	'`	0.42.02	•	4.21.00	'*	1.02.04	'`	7.5L-02	''	2.02.02	14	2.02.01
Hexachlorodibenzo-p- dioxin mixture (HxCDD)	19408-74-3		7.8E-05	С	1.0E-04	С	2.8E-04	С	9.2E-04	С	1.5E-06	С	1.1E-05	С	
Hexachloroethane	67-72-1		3.5E+01	С	4.6E+01	С	1.2E+02	С	4.1E+02	С	4.8E-01	С	4.8E+00	С	2.0E-02
Hexachlorophene	70-30-4		1.8E+01	N	2.3E+01	N	1.9E+02	N	6.1E+02	N	1.1E+00	N	1.1E+01	N	
Hexahydro-1,3,5-trinitro- 1,3,5-triazine	121-82-4		4.4E+00	С	5.8E+00	С	1.6E+01	С	5.2E+01	С	6.1E-02	С	6.1E-01	С	
1,6-Hexamethylene diisocyanate	822-06-0		1.7E-01	N	2.2E-01	N	1.8E+00	N	5.8E+00	N	1.0E-02	N	1.0E-01	N	
n-Hexane	110-54-3		1.1E+02	sat	1.1E+02	sat	1.1E+02	sat	1.1E+02	sat	2.1E+02	N	3.5E+02	N	
Hexazinone	51235-04-2		2.0E+03		2.6E+03		2.1E+04		6.7E+04		1.2E+02		1.2E+03		
Hydrazine, hydrazine sulfate	302-01-2		1.6E-01	С	2.1E-01	С	5.8E-01	С	1.9E+00	С	3.9E-04	С	2.2E-02	С	
Hydrogen chloride	7647-01-0		1.0E+05		1.0E+05	max	1.0E+05	max	1.0E+05	max	2.1E+01	N			
Hydrogen sulfide	7783-06-4		1.8E+02		2.3E+02		1.9E+03		6.1E+03		1.0E+00		1.1E+02	N	
p-Hydroquinone	123-31-9		2.4E+03	N	3.1E+03	N	2.5E+04	N	8.2E+04	N	1.5E+02	N	1.5E+03	N	

EPA REG	ION 6- F	IUMAN	N HEA	\L7	ГН МЕ	DI	UM-S	PE	CIFIC	S	CREE	NI	NG LE	VE	ELS
			Basis: C= N= sa	carci non- t= soi	nogenic effe carcinogenic I saturation aximum cor	cts ceffect conce	cts entration								
		MCL	Risk-E	3ase	ed Scree	ning	j Levels								Soil Screening Level- Transfers
Contaminant	CAS No.	or Action	Soil (inge		n, inhalation	ı, wit	h and with	out de	ermal		Ambient A		Tap Water (Residentia		from Soil to:
		Level	Residen		Resident w/o derm		Industria	al	Industria w/o dern		Scenario)		Scenario: Ingestion 8 Inhalation)	·	Ground water (DAF=1)
	<u> </u>	ug/l	mg/kg mg/kg mg/kg ug/m3 ug/l											mg/kg	
<u></u>	117400 00 0	T	0.05.04		0.05.04		14.05.05	I	1 4 05 : 05		1		445.04	N.1	τ
Iron	7439-89-6		2.3E+04	N	2.3E+04	N N	1.0E+05		1.0E+05		1.1E+03	N	1.1E+04 1.8E+03	N N	
Isobutanol	78-83-1		1.1E+04 5.1E+02	N C	1.3E+04 6.7E+02	C	4.0E+04 1.8E+03		4.0E+04 6.0E+03		7.1E+03		7.1E+01	C	3.0E-02
Isophorone	78-59-1 33820-53-0		9.1E+02	N	1.2E+03	N	9.3E+03		3.1E+04		5.5E+01	N	5.5E+02	N	3.00-02
Isopropalin Isopropyl methyl	1832-54-8	<u> </u>	6.1E+03	N	7.8E+03	N	6.2E+04		1.0E+05		4.0E+02	N	3.7E+03	N	
phosphonic acid	11032-34-0		0.12103	14	7.0L103	14	0.26104	14	1.02.103	Illiax	4.01.102	'`	3.72.103	14	
Kepone	143-50-0		2.7E-02	С	3.6E-02	С	9.7E-02	С	3.2E-01	С	3.7E-04	С	3.7E-03	С	
Lead	7439-92-1	1.5E+01	4.0E+02		0.00		2.0E+03					- <u>-</u> -	1.5E+01		
Lead (tetraethyl)	78-00-2		6.1E-03	N	7.8E-03	N	6.2E-02	N	2.0E-01	N			3.7E-03	N	
Lithium	7439-93-2		1.6E+03	N	1.6E+03	N	4.1E+04	N	4.1E+04	N			7.3E+02		
Malathion	121-75-5		1.2E+03	N	1.6E+03	N	1.2E+04	N	4.1E+04	N	7.3E+01	N	7.3E+02	N	
Maleic anhydride	108-31-6		6.1E+03	N	7.8E+03	N	6.2E+04	N	1.0E+05	max	3.7E+02	N	3.7E+03	N	
Manganese and	7439-96-5		3.2E+03	Ν	3.2E+03	N	4.7E+04	N	4.7E+04	N	5.1E-02	N	1.7E+03	N	
compounds	<u> </u>														
Mephosfolan	950-10-7		5.5E+00	Z	7.0E+00	N	5.6E+01	N	1.8E+02		3.3E-01	N	3.3E+00		
Mepiquat	24307-26-4		1.8E+03	N	2.3E+03	N	1.9E+04	N	6.1E+04	N	1.1E+02	N	1.1E+03		
2-Mercaptobenzothiazole	149-30-4		1.7E+01	С	2.2E+01	<u>C</u>	6.0E+01	С	2.0E+02	С	2.3E-01	С	2.3E+00		
Mercury and compounds	7487-94-7	2.0E+00	2.3E+01	N	2.3E+01	<u>N</u>	6.1E+02	N	6.1E+02	N			1.1E+01	N	
Mercury (elemental)	7439-97-6										3.1E-01	N			
Mercury (methyl)	22967-92-6		6.1E+00		7.8E+00	N	6.2E+01	N	2.0E+02				3.7E+00		
Methacrylonitrile	126-98-7		1.9E+00		2.1E+00	N_	8.0E+00		8.8E+00		7.3E-01		1.0E+00		ļ
Methanol	67-56-1		3.0E+04		3.9E+04	N	1.0E+05		1.0E+05		1.8E+03		1.8E+04		
Methidathion	950-37-8	4.05.01	6.1E+01		7.8E+01	N	6.2E+02		2.0E+03		3.7E+00		3.7E+01		0.05.00
Methoxychlor	72-43-5	4.0E+01	3.0E+02	N	3.9E+02	N.	3.1E+03		1.0E+04		1.8E+01		1.8E+02		8.0E+00
Methyl acetate	79-20-9		2.0E+04		2.2E+04	N	8.7E+04		9.6E+04	_	3.7E+03		6.1E+03	*****	
Methyl acrylate	96-33-3		6.9E+01	N	7.0E+01	N	2.3E+02		2.3E+02		1.1E+02		1.8E+02		ļ
2-Methylaniline (o-	95-53-4	1	2.0E+00	С	2.7E+00	<u>_C</u>	7.3E+00	С	2.4E+01	С	2.8E-02	С	2.8E-01	<u>C</u>	<u></u>

EPA REG	ION 6- H	IUMAN	N HEA	L1	Н МЕ	DI	UM-S	PE	CIFIC	S	CREE	NI	NG LE	VE	LS
		MCL	Basis: C= N= sat ma	carcir non-c = soil x= m	nogenic effe carcinogenic saturation aximum cor	cts ceffec conce ncentra	ts ntration ation								Soil Screening Level- Transfers
Contaminant	CAS No.	or			, inhalatior	n, with	and with	out de	ermal		Ambient A		Tap Water		from Soil
		Action Level	Resident		es) Resident w/o derm		Industria	i	Industrial w/o derm		(Residenti Scenario)		(Residentia Scenario: Ingestion & Inhalation)	ί.	to: Ground water (DAF=1)
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg	-	ug/m3		ug/l		mg/kg
									·				·		Т
toluidine)			ļ									- 	1.07.01		ļ
2-Methyl-4-	94-74-6		3.0E+01	Ν	3.9E+01	N	3.1E+02	N	1.0E+03	N	1.8E+00	, N	1.8E+01	Ν	
chlorophenoxyacetic acid	11		1		7.05.00				0.05.04		0.75.04	<u> </u>	0.75.00	N.I.	
4-(2-Methyl-4- chlorophenoxy) butyric acid (MCPB)	94-81-5		6.1E+02	N	7.8E+02	N	6.2E+03	N	2.0E+04	N	3.7E+01	N	3.7E+02	N	
2-(2-Methyl-4- chlorophenoxy) propionic acid	93-65-2		6.1E+01	N	7.8E+01	N	6.2E+02	N	2.0E+03	N	3.7E+00	N	3.7E+01	N	
2-(2-Methyl-1,4- chlorophenoxy) propionic acid (MCPP)	16484-77-8		6.1E+01	N	7.8E+01	N	6.2E+02	N	2.0E+03	N	3.7E+00	Z	3.7E+01	N	
Methylcyclohexane	108-87-2		1.4E+02	sat	1.4E+02	sat	1.4E+02		1.4E+02	sat	3.1E+03		5.2E+03		<u> </u>
4,4'-Methylene bis(2-chloroaniline)	101-14-4		3.7E+00	С	4.9E+00	С	1.3E+01	O	4.4E+01	С	5.2E-02	С	5.2E-01	С	
4,4'-Methylene bis(N,N'-dimethyl)aniline	101-61-1		1.1E+01	С	1.4E+01	С	3.8E+01	С	1.2E+02	С	1.5E-01	С	1.5E+00	C	
Methylene bromide	74-95-3		1.3E+02	N	1.4E+02	N	5.2E+02		5.5E+02	N	3.7E+01	N	6.1E+01	N	
Methylene chloride	75-09-2		8.6E+00	С	8.9E+00	С	1.9E+01	С	2.1E+01	С	4.1E+00		4.3E+00		1.0E-03
4,4'-Methylenediphenyl isocyanate	101-68-8		1.0E+01	N	1.3E+01	N	1.1E+02	N	3.5E+02	N	6.2E-01	N	6.2E+00	N	
Methyl ethyl ketone	78-93-3		7.0E+03	N	7.3E+03	N	2.6E+04	2	2.8E+04		1.0E+03		1.9E+03		
Methyl hydrazine	60-34-4		4.4E-01	С	5.8E-01	С	1.6E+00	С	5.2E+00	С	6.1E-03		6.1E-02		
Methyl isobutyl ketone	108-10-1		7.6E+02	N	7.9E+02	N	2.8E+03		2.9E+03		8.3E+01		1.6E+02		
Methyl mercaptan	74-93-1		3.5E+01	N	4.5E+01	N	3.6E+02		1.2E+03		2.1E+00		2.1E+01		
Methyl methacrylate	80-62-6		2.2E+03		2.2E+03	N	2.7E+03		2.7E+03		7.3E+02		1.4E+03		
2-Methyl-5-nitroaniline	99-55-8		1.5E+01		1.9E+01	С	5.3E+01		1.7E+02		2.0E-01		2.0E+00		
Methyl parathion	298-00-0		1.5E+01	N	2.0E+01	N	1.6E+02	N	5.1E+02	N	9.1E-01	N	9.1E+00	<u>N</u> _	<u> </u>

EPA REG	ION 6- H	UIVIAN	Basis: C= N= sai	carcir non-c	nogenic effectarcinogenic saturation aximum cor	cts ceffec conce	ts ntration	<u>rc</u>	CIFIC	3	SKEE	INII	NG LL	V L	LO
		MCL	Risk-E	Base	d Scree	ning	Levels				Aughiant A	7	Tan Motor		Soil Screening Level- Transfers
Contaminant	CAS No.	or Action Level	Soil (inge exposure Resident	rout	i, inhalation es) Resident w/o derm	ial	Industrial		Industrial w/o derm		Ambient A (Residenti Scenario)	ial	Tap Water (Residentia Scenario: Ingestion & Inhalation)		from Soil to: Ground water
		ua/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		(DAF=1) mg/kg
		ug/l	i nig/kg		i ing/kg		i ing/ikg		1				1 <u></u>		
2-Methylphenol	95-48-7		3.0E+03	N	3.9E+03	N	3.1E+04	N	1.0E+05	max	1.8E+02	N	1.8E+03	N	8.0E-01
3-Methylphenol	108-39-4		3.0E+03	N	3.9E+03	N	3.1E+04	N	1.0E+05		1.8E+02	N	1.8E+03	N	
4-Methylphenol	106-44-5		3.0E+02	N	3.9E+02	N	3.1E+03	N	1.0E+04	N	1.8E+01	N	1.8E+02	N	
Methyl phosphonic acid	993-13-5		1.2E+03	N	1.6E+03	N	1.2E+04	N	4.1E+04	N	7.3E+01	N	7.3E+02	N	
Methyl styrene (mixture)	25013-15-4		1.2E+02	N	1.3E+02	N	5.1E+02	N	5.6E+02	N	4.2E+01	N	6.0E+01	N	
Methyl styrene (alpha)	98-83-9		6.8E+02	sat	6.8E+02	sat	6.8E+02	sat	6.8E+02	sat	2.6E+02	Z	4.3E+02	N	
Methyl tertbutyl ether (MTBE)	1634-04-4										3.1E+03	N	2.0E+01		
Metolaclor (Dual)	51218-45-2		9.1E+03	N	1.2E+04	N	9.3E+04	N .	1.0E+05	max	5.5E+02	N	5.5E+03	N	
Mirex	2385-85-5		2.7E-01	С	3.6E-01	С	9.7E-01	С	3.2E+00	С	3.7E-03	С	3.7E-02	_C	
Molybdenum	7439-98-7		3.9E+02	N	3.9E+02	N	1.0E+04	Ν	1.0E+04	Ν			1.8E+02	<u>N</u>	
Monochloramine	10599-90-3		6.1E+03	N	7.8E+03	N	6.2E+04	N	1.0E+05	max	3.7E+02	N	3.7E+03	N	
Naled	300-76-5		1.2E+02	N	1.6E+02	N	1.2E+03	Ν	4.1E+03		7.3E+00	N	7.3E+01	N	
Nickel and compounds	7440-02-0	1.0E+02	1.6E+03	Ν	1.6E+03	N	4.1E+04	N	4.1E+04	N			7.3E+02	N	7.0E+00
Nickel refinery dust	n/a		1.1E+04		1.1E+04	<u>C</u>	2.2E+04	С	2.2E+04	С	8.0E-03	_			
Nickel subsulfide	12035-72-2		5.2E+03	С	5.2E+03	С	1.1E+04	C	1.1E+04	C	4.0E-03	С			
Nitrate	14797-55-8	1.0E+04											1.0E+04		
Nitric Oxide	10102-43-9		6.1E+03	N	7.8E+03	N	6.2E+04	N	1.0E+05	max			3.7E+03	<u> N</u>	
Nitrite	14797-65-0	1.0E+03								<u> </u>		<u> </u>	1.0E+03		
2-Nitroaniline	88-74-4		3.6E+00		4.7E+00		3.7E+01	N	1.2E+02		2.1E-01	-	2.2E+00		7.55
Nitrobenzene	98-95-3		1.7E+01		2.0E+01		9.1E+01		1.1E+02		2.1E+00		3.4E+00		7.0E-03
Nitrofurantoin	67-20-9		4.2E+03		5.5E+03		4.4E+04		1.0E+05		2.6E+02		2.6E+03		
Nitrofurazone	59-87-0		3.2E-01		4.3E-01		1.2E+00		3.8E+00		7.2E-04	С	4.5E-02		
Nitrogen dioxide	101102-44-0		6.1E+04		7.8E+04		1.0E+05		1.0E+05		0.05.00	 	3.7E+04		
4-Nitrophenol	100-02-7		3.8E+03		4.8E+03		3.9E+04		1.0E+05		2.3E+02		2.3E+03		
2-Nitropropane	79-46-9		5.1E-02		6.8E-02		1.9E-01		6.1E-01		7.2E-04		1.2E-03		
N-Nitrosodi-n-butylamine	924-16-3	<u> </u>	2.3E-02	С	2.4E-02	С	5.4E-02	<u> </u>	6.2E-02	C	1.2E-03	<u>C</u>	2.0E-03		<u> </u>

EPA REGI	ON 6- H	UMAN					UM-S	PE	CIFIC	S	CREE	NII	NG LE	VE	ELS
			N= sa	non-d t= soi	nogenic effe carcinogenic I saturation aximum cor	ceffec	entration								
		MCL	Risk-E	Base	d Scree	ning	Levels		==						Soil Screening Level- Transfers
Contaminant	CAS No.	or Action	Soil (inge		n, inhalation	n, with	n and witho	out de	ermal		Ambient A		Tap Water (Residentia	al	from Soil to:
		Level	Resident		Resident w/o derm		Industria	I	Industria w/o derm		Scenario)		Scenario: Ingestion 8 Inhalation)	t	Ground water (DAF=1)
	<u> </u>	ug/l	mg/kg		mg/kg mg/kg mg/kg ug/m3 ug/l										mg/kg
		_	1 4 77 = 04		0.05.041		T 0 0 F 041	_	0.05.00		0.45.02		1 0 4E 001	С	T
N-Nitrosodiethanolamine	1116-54-7		1.7E-01	C	2.3E-01	<u> </u>	6.2E-01	C	2.0E+00		2.4E-03 4.5E-05		2.4E-02 4.5E-04		
N-Nitrosodiethylamine	55-18-5		3.2E-03		4.3E-03	<u>C</u>	1.2E-02 3.4E-02	C	3.8E-02 1.1E-01	C	1.4E-04		1.3E-03		
N-Nitrosodimethylamine	62-75-9		9.5E-03	$\frac{1}{2}$	1.3E-02	C	3.4E-02	C	1.1E-01 1.2E+03		1.4E+00		1.4E+01	$\frac{c}{c}$	6.0E-02
N-Nitrosodiphenylamine N-Nitroso di-n-	86-30-6 621-64-7	<u> </u>	9.9E+01 6.9E-02	0	1.3E+02 9.1E-02	C	2.5E-01	С	8.2E-01	C	9.6E-04		9.6E-03		2.0E-0
propylamine	1021-04-7		0.96-02		9.11-02	C	2.0L-01	U	U.ZL-01		3.0L-04		J.0L-03	J	2.02 00
N-Nitroso-N-	10595-95-6		2.2E-02	C	2.9E-02	С	7.9E-02	С	2.6E-01	С	3.1E-04	С	3.1E-03	С	
methylethylamine					-:		1.0 - 0 -								
N-Nitrosopyrrolidine	930-55-2		2.3E-01	С	3.0E-01	С	8.3E-01	С	2.7E+00	С	3.1E-03	С	3.2E-02	С	
m-Nitrotoluene	99-08-1		6.1E+02	N	7.8E+02	N	6.2E+03	N	2.0E+04	N	3.7E+01	N	3.7E+02	N	
o-Nitrotoluene	99-08-1		6.1E+02	N	7.8E+02	N	6.2E+03	N	2.0E+04	N	3.7E+01	N	3.7E+02	N	
p-Nitrotoluene	99-99-0		6.1E+02	N	7.8E+02	N	6.2E+03	N	2.0E+04	N	3.7E+01	2	3.7E+02	Ν	
NuStar	85509-19-9		4.2E+01	N	5.5E+01	N	4.4E+02	Ν	1.4E+03		2.6E+00	Ν	2.6E+01	N	
Octahydro-1357-tetranitro- 1357- tetrazocine (HMX)	2691-41-0		3.0E+03	N	3.9E+03	N	3.1E+04	N	1.0E+05	max	1.8E+02	N	1.8E+03	N	
Oryzalin	19044-88-3		3.0E+03	N	3.9E+03	N	3.1E+04	Z	1.0E+05	max	1.8E+02	N	1.8E+03		
Oxadiazon	19666-30-9		3.0E+02	N	3.9E+02	N	3.1E+03	N	1.0E+04	N	1.8E+01	N	1.8E+02	N	
Oxamyl	23135-22-0	2.0E+02	1.5E+03	N	2.0E+03	N	1.6E+04	N	5.1E+04	N	9.1E+01	N	9.1E+02	N	<u> </u>
Oxyfluorfen	42874-03-3		1.8E+02	N	2.3E+02	N	1.9E+03	N	6.1E+03		1.1E+01	N	1.1E+02	N	
Paraquat	4685-14-7		2.7E+02	N	3.5E+02	N	2.8E+03	N	9.2E+03		1.6E+01	N	1.6E+02		
Parathion	56-38-2		3.6E+02		4.7E+02	~~~	3.7E+03		1.2E+04		2.2E+01	_	2.2E+02		
Pentachlorobenzene	608-93-5		4.9E+01		6.3E+01	N	5.0E+02		1.6E+03		2.9E+00		2.9E+01		
Pentachloronitrobenzene	82-68-8		1.9E+00				6.7E+00		2.2E+01		2.6E-02		2.6E-01		
Pentachlorophenol	87-86-5	1.0E+00	2.9E+00		5.3E+00	С	7.1E+00		4.8E+01		5.6E-02	С	5.6E-01		1.0E-03
Perchlorate	7601-90-3		3.9E+01	N	3.9E+01	N	1.0E+03		1.0E+03				1.8E+01		<u> </u>
Permethrin	52645-53-1	_	3.0E+03		3.9E+03	N	3.1E+04		1.0E+05				1.8E+03		F 05 0
Phenol	108-95-2]	3.6E+04	N	4.7E+04	N	1.0E+05	max	1.0E+05	max	2.2E+03	N_	2.2E+04	N	5.0E+00

EPA REGI	ION 6- H	IUMAN	I HEA	\L7	ГН МЕ	EDI	UM-S	PE	CIFIC	S	CREE	NI	NG LE	VE	ELS
		MCL	N= sa ma	non-c t= soil ax= m	nogenic effectarcinogenic saturation aximum co	c effect conce ncentr	ntration ation								Soil Screening Level-
Contaminant	CAS No.	or	, , –		, inhalatio	n, with	and with	out de	ermal		Ambient A		Tap Water		Transfers from Soil
		Action Level	exposure Resident		es) Residen w/o derr		Industria	ıl	Industria w/o derm		(Resident Scenario)		(Residential Scenario: Ingestion & Inhalation)	<u> </u>	to: Ground water (DAF=1)
	<u> </u>	ug/l	mg/kg		mg/kg		mg/kg		mg/kg	_	ug/m3		ug/l		mg/kg
	11		1				1. 2= 2=1		1		= a= a=		1		
Phenothiazine	92-84-2	ļ	1.2E+02	N	1.6E+02	N	1.2E+03		4.1E+03	1	7.3E+00		7.3E+01	N	
m-Phenylenediamine	108-45-2		3.6E+02		4.7E+02		3.7E+03		1.2E+04		2.2E+01		2.2E+02	N	
p-Phenylenediamine	106-50-3		1.2E+04	N	1.5E+04		1.0E+05		1.0E+05		6.9E+02	_	6.9E+03		
Phenylmercuric acetate	62-38-4		4.9E+00		6.3E+00		5.0E+01	N	1.6E+02		2.9E-01	N	2.9E+00		
2-Phenylphenol	90-43-7		2.5E+02	C	3.3E+02		9.0E+02		2.9E+03		3.5E+00		3.5E+01	C	
Phosphine	7803-51-2	 	1.8E+01	N	2.3E+01	N	1.9E+02	N	6.1E+02	N	3.1E-01	N	1.1E+01	N	
Phosphoric acid	7664-38-2 7723-14-0		1.65.00	N.I.	1.65.00	N.I.	4.1E+01	- NI	4.1E+01	N	1.0E+01	N	7.3E-01	N	
Phosphorus (white)	100-21-0	 	1.6E+00 6.1E+04	N	1.6E+00 7.8E+04	N	1.0E+01	N	1.0E+05		3.7E+03	N	3.7E+04	N	<u> </u>
p-Phthalic acid	85-44-9		1.0E+05		1.0E+04	N	1.0E+05		1.0E+05		1.2E+02	N	7.3E+04	N	
Phthalic anhydride	100-44-9		5.4E-02	C	7.2E-02		2.0E-01	С	6.4E-01		7.6E-04	C	7.6E-03		
Polybrominated biphenyls Polychlorinated biphenyls (PCBs)	1336-36-3	5.0E-01	2.2E-01	С	3.2E-01	C	6.8E-01		2.9E+00		3.4E-03	C	3.4E-02	C	
Aroclor 1016	12674-11-2		3.9E+00	N	5.5E+00	N	3.4E+01	N	1.4E+02	N	2.6E-01	N	2.6E+00	N	
Aroclor 1254	11097-69-1		1.1E+00	N	1.6E+00		9.8E+00		4.1E+01		7.3E-02	N	7.3E-01	N	
Polynuclear aromatic hydro	<u> </u>						1 1 1								
Acenaphthene	83-32-9		2.8E+03	N	3.7E+03	N	2.0E+04	N	3.8E+04	N	2.2E+02	N	3.7E+02	N	2.9E+01
Anthracene	120-12-7		1.6E+04	N	2.2E+04	N	1.0E+05		1.0E+05		1.1E+03	N	1.8E+03	N	5.9E+02
Benz[a]anthracene	56-55-3		6.2E-01	С	8.8E-01	С	2.0E+00		7.8E+00		2.2E-02	С	9.2E-02	С	8.0E-02
Benzo[b]fluoranthene	205-99-2		6.2E-01	С	8.8E-01	С	2.0E+00	С	7.8E+00	С	2.2E-02	С	9.2E-02	С	2.0E-01
Benzo[k]fluoranthene	207-08-9		6.2E+00	С	8.8E+00	С	2.0E+01	С	7.8E+01	С	2.2E-01	С	9.2E-01	С	2.0E+00
Benzo[a]pyrene	50-32-8	2.0E-01			8.8E-02	С	2.0E-01	С	7.8E-01	С	2.2E-03	С	9.2E-03	С	4.0E-01
Chrysene	218-01-9		6.2E+01		8.8E+01		2.0E+02		7.8E+02		2.2E+00		9.2E+00		8.0E+00
Dibenz[ah]anthracene	53-70-3		6.2E-02	С	8.8E-02	С	2.0E-01	С	7.8E-01	С	2.2E-03	С	9.2E-03		8.0E-02
Fluoranthene	206-44-0		2.3E+03		3.1E+03		2.1E+04		8.2E+04	N	1.5E+02	Ν	1.5E+03		2.1E+02
Fluorene	86-73-7		2.0E+03		2.6E+03		1.5E+04		3.3E+04		1.5E+02		2.4E+02		2.8E+01
Indeno[1,2,3-cd]pyrene	193-39-5		6.2E-01	С	8.8E-01	С	2.0E+00	С	7.8E+00	С	2.2E-02	С	9.2E-02	С	7.0E-01

EPA REC	GION 6- H	IUMAI	N HEAL	TH MED	UM-SPE	CIFIC S	CREENI	NG LEVE	ELS
			Basis: C=carci N=non- sat= so	nogenic effects carcinogenic effe il saturation conc aximum concent	cts entration				
		MCL	Risk-Base	ed Screening	g Levels				Soil Screening Level- Transfers
Contaminant	CAS No.	or Action	Soil (ingestion exposure rou	•	h and without de	ermal	Ambient Air (Residential	Tap Water (Residential	from Soil to:
		Level	Residential	Residential w/o dermal	Industrial	Industrial w/o dermal	Scenario)	Scenario: Ingestion & Inhalation)	Ground water (DAF=1)
		ug/l	mg/kg	mg/kg	mg/kg	mg/kg	ug/m3	ug/l	mg/kg
			Tere of N	Is on the N	14.0F.00L N	1 4 05 .001 N	1 2 4E 100 N	6.2E+00 N	4.0E+00
Naphthalene	91-20-3	ļ	5.5E+01 N	5.6E+01 N	1.9E+02 N	1.9E+02 N	3.1E+00 N 1.1E+02 N	1.8E+02 N	2.1E+02
Pyrene	129-00-0		1.7E+03 N	2.3E+03 N	1.5E+04 N	5.4E+04 N		5.5E+02 N	2.12702
Prometon	1610-18-0		9.1E+02 N	1.2E+03 N	9.3E+03 N	3.1E+04 N	5.5E+01 N	1.5E+02 N	
Prometryn	7287-19-6	<u> </u>	2.4E+02 N	3.1E+02 N	2.5E+03 N	8.2E+03 N	1.5E+01 N 4.7E+01 N	4.7E+02 N	
Propachlor	1918-16-7		7.9E+02 N	1.0E+03 N	8.1E+03 N	2.7E+04 N 1.0E+04 N	4.7E+01 N 1.8E+01 N	1.8E+02 N	
Propanil	709-98-8		3.0E+02 N	3.9E+02 N	3.1E+03 N	1.0E+04 N 4.1E+04 N	7.3E+01 N	7.3E+02 N	
Propargite	2312-35-8	-	1.2E+03 N	1.6E+03 N	1.2E+04 N 1.2E+03 N	4.1E+04 N 4.1E+03 N	7.3E+00 N	7.3E+01 N	
Propargyl alcohol	107-19-7		1.2E+02 N	1.6E+02 N		4.1E+03 N 4.1E+04 N	7.3E+00 N	7.3E+02 N	
Propazine	139-40-2	_	1.2E+03 N	1.6E+03 N	1.2E+04 N	2.7E+04 N	4.7E+01 N	4.7E+02 N	
Propiconazole	60207-90-1		7.9E+02 N	1.0E+03 N	8.1E+03 N	3.9E+02 sat	3.7E+01 N	6.1E+01 N	
iso-Propylbenzene	104-5-18	<u> </u>	1.3E+02 N	1.3E+02 N	3.9E+02 sat	2.4E+02 sat	3.7E+01 N	6.1E+01 N	
n-Propylbenzene	104-51-8	 	1.4E+02 N	1.4E+02 N	2.4E+02 sat	1.0E+05 max	7.3E+04 N	7.3E+05 N	
Propylene glycol	57-55-6		1.0E+05 max	· I · · · · · · · · · · · · · · · · · ·	1.0E+05 max			2.6E+04 N	
Propylene glycol, monoethyl ether	111-35-3		4.2E+04 N	5.5E+04 N					
Propylene glycol, monomethyl ether	107-98-2		4.2E+04 N	5.5E+04 N	1.0E+05 max	1.0E+05 max		2.6E+04 N	
Propylene oxide	75-56-9		1.6E+00 C	1.9E+00 C	4.9E+00 C	9.1E+00 C	5.2E-01 C	2.2E-01 C	
Pursuit	81335-77-5		1.5E+04 N	2.0E+04 N	1.0E+05 max	1.0E+05 max	9.1E+02 N	9.1E+03 N	
Pyridine	110-86-1		6.1E+01 N	7.8E+01 N	6.2E+02 N	2.0E+03 N	3.7E+00 N	3.7E+01 N	
Quinoline	91-22-5		4.0E-02 C	5.3E-02 C	1.5E-01 C	4.8E-01 C	5.6E-04 C	5.6E-03 C	
RDX (Cyclonite)	121-82-4		4.4E+00 C	5.8E+00 C	1.6E+01 C	5.2E+01 C	6.1E-02 C	6.1E-01 C	
Resmethrin	10453-86-8		1.8E+03 N	2.3E+03 N	1.9E+04 N	6.1E+04 N	1.1E+02 N	1.1E+03 N	
Ronnel	299-84-3		3.0E+03 N	3.9E+03 N	3.1E+04 N	1.0E+05 max		1.8E+03 N	
Rotenone	83-79-4		2.4E+02 N	3.1E+02 N		8.2E+03 N	1.5E+01 N	1.5E+02 N	
Selenious Acid	7783-00-8		3.0E+02 N	3.9E+02 N		1.0E+04 N		1.8E+02 N	
Selenium	7782-49-2	5.0E+01	3.9E+02 N	3.9E+02 N	1.0E+04 N	1.0E+04 N	<u> </u>	1.8E+02 N	3.0E-01

EPA REGI	ON 6- H	UMAN	HEA	<u>L</u> 1	Н МЕ	DI	UM-S	PΕ	CIFIC	S	CREE	NII	NG LE	VE	LS
LIARLO			Basis: C= N= sat	carcir non-c = soil	nogenic effectarcinogenic saturation of aximum con	cts effec conce	ts ntration								
		MCL			d Screei						,				Soil Screening Level- Transfers
Contaminant	CAS No.	or Action	Soil (inge		, inhalation es)	ı, with	and witho	ut de	ermal		Ambient A (Residenti		Tap Water (Residentia	il	from Soil to:
		Level	Resident		Resident w/o derm		Industrial		Industrial w/o derm		Scenario)		Scenario: Ingestion & Inhalation)		Ground water (DAF=1)
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg
		T			0 0 0 0 0 0		14.05.04		1.05.04	N.I	T		1.8E+02	N	2.0E+00
Silver and compounds	7440-22-4		3.9E+02		3.9E+02	<u>N</u>	1.0E+04	<u>N</u>	1.0E+04		5.6E-02	С	5.6E-01	C	2.02.400
Simazine	122-34-9	4.0E+00	4.0E+00		5.3E+00	C	1.5E+01	<u>C</u>	4.8E+01 8.2E+03		1.5E+01	N	1.5E+02	N	
Sodium azide	26628-22-8		2.4E+02		3.1E+02	N	2.5E+03	N C	2.1E+01	C	2.5E-02		2.5E-01	C	
Sodium	148-18-5		1.8E+00	С	2.4E+00	С	6.5E+00	C	2.15701		2.56-02		2.02-01	U	
diethyldithiocarbamate	100 710		4.05.00	N.	1.6E+00	N.I.	1.2E+01		4.1E+01	N	7.3E-02	N	7.3E-01	N	
Sodium fluoroacetate	62-74-8		1.2E+00	N N	7.8E+01	N N	6.2E+02	- <u>N</u>	2.0E+03		3.7E+00		3.7E+01	N	
Sodium metavanadate	13718-26-8		6.1E+01		4.7E+04	N	1.0E+05		1.0E+05		3.7L.100		2.2E+04	N	
Strontium, stable	7440-24-6		4.7E+04 1.8E+01		2.3E+01	N	1.9E+02	N	6.1E+02		1.1E+00	N	1.1E+01	N	
Strychnine	57-24-9	4.05.00			1.7E+03	sat			1.7E+03		1.1E+03	N	1.6E+03	N	2.0E-01
Styrene	100-42-5	1.0E+02			4.3E-06	C	2.3E-05	C	3.8E-05		4.5E-08		4.5E-07	Ċ	2.02.0
2,3,7,8-TCDD (dioxin)	1746-01-6	3.0E-05	1.8E+01		2.3E+01	N	1.9E+02	_ <u>U</u> _	6.1E+02		1.1E+00		1.1E+01	N	
1,2,4,5-	95-94-3		1.05701	IN	2.35701	IN	1.92	IN	0.11.102	'	1.12.00	l '`		••	
Tetrachlorobenzene	630-20-6		2.9E+00	С	3.0E+00	С	6.6E+00	_ <u>C</u>	7.1E+00	c	2.6E-01	c	4.3E-01	C	
1,1,1,2-Tetrachloroethane	79-34-5		3.7E-01		3.8E-01	c	8.4E-01	_ č	9.0E-01	c	3.3E-02		5.5E-02	C	2.0E-04
1,1,2,2-Tetrachloroethane Tetrachloroethylene (PCE)		5.0E+00	4.9E+00		5.7E+00	Ċ	1.3E+01	_	1.9E+01		3.3E+00		1.1E+00	C	3.0E-03
2,3,4,6-Tetrachlorophenol	58-90-2	J.0L.100	1.8E+03		2.3E+03	N	1.9E+04	_ <u>N</u>	6.1E+04		1.1E+02		1.1E+03	N	
	5216-25-1	 	2.4E-02		3.2E-02	Ċ	8.7E-02	_ ::	2.9E-01		3.4E-04		3.4E-03	C	
p,a,a,a-Tetrachlorotoluene	961-11-5	 	2.4E-02	C	2.7E+01	$\frac{\sigma}{c}$	7.3E+01	-č -	2.4E+02	_	2.8E-01		2.8E+00	С	
Tetrachlorovinphos	109-99-9	 	5.2E+03		6.7E+03	N	5.3E+04		1.0E+05				3.1E+03		
Tetrahydrofuran Thallic oxide	1314-32-5				5.5E+00		1.4E+02		1.4E+02				2.6E+00		
Thallium acetate	563-68-8	2 0F+00			7.0E+00		1.8E+02		1.8E+02				3.3E+00		4.0E-01
Thallium carbonate	6533-73-9		6.3E+00				1.6E+02						2.9E+00		4.0E-01
	7791-12-0		6.3E+00		6.3E+00		1.6E+02		1.6E+02				2.9E+00		4.0E-01
Thallium chloride Thallium pitrate	10102-45-1		7.0E+00				1.8E+02	_	1.8E+02				3.3E+00		4.0E-01
Thallium nitrate Thallium selenite	12039-52-0		7.0E+00				1.8E+02		1.8E+02				3.3E+00		4.0E-01
Thallium sulfate	7446-18-6		6.3E+00						1.6E+02				2.9E+00		4.0E-01

EPA REGI	ON 6- H	IUMAN	I HEA	\L1	ГН МЕ	EDI	UM-S	PE	CIFIC	S	CREE	NI	NG LE	VE	LS
		MCL	Basis: C= N= sa ma	carcii non-c t= soi ax= m	nogenic effectarcinogenic I saturation aximum con	ects c effect conce ncentra	ts ntration ation	· · · ·						The state of the s	Soil Screening Level-
Contaminant	CAS No.	or	, , –		, inhalatio	n, with	and with	out de	ermal		Ambient A		Tap Water		Transfers from Soil
Jonannan		Action Level	exposure Resident		es) Resident w/o dern		Industria	il	Industrial w/o derm		(Residenti Scenario)		(Residentia Scenario: Ingestion & Inhalation)		to: Ground water (DAF=1)
		ug/l	mg/kg		mg/kg		mg/kg		mg/kg		ug/m3		ug/l		mg/kg
	Hood to 77 5		0.45.00		7.05.00		Ic or . oo	N. 1	0.05.01	1 1	0.75.04	<u> </u>	275.00	h.1	T
Thiobencarb	28249-77-6		6.1E+02	N	7.8E+02	N	6.2E+03		2.0E+04		3.7E+01	N	3.7E+02 3.7E+03	N N	
Thiocyanate	N/A		6.1E+03	N	7.8E+03	N	6.2E+04		1.0E+05 1.0E+05			N	2.2E+04	N	
Tin and compounds	N/A	4.05.00	4.7E+04	N	4.7E+04	N	1.0E+05 5.2E+02		5.2E+02		4.0E+02	N	7.2E+04	N	6.0E-0
Toluene	108-88-3	1.0E+03	5.2E+02	sat	5.2E+02	sat	5.5E-01	sat C	1.8E+00		2.1E-03		2.1E-02	C	0.0E-0
Toluene-2,4-diamine	95-80-7		1.5E-01 3.6E+04	C N	2.0E-01 4.7E+04	C N	1.0E+05		1.0E+05		2.1E-03		2.1E-02 2.2E+04	N	
Toluene-2,5-diamine	95-70-5 823-40-5		1.2E+04	N	1.6E+04	N	1.0E+05		1.0E+05		7.3E+02		7.3E+03	N	
Toluene-2,6-diamine p-Toluidine	106-49-0		2.5E+00	C	3.4E+00	C	9.2E+00		3.0E+01	C	3.5E-02	C	3.5E-01	Ċ	
	8001-35-2	3.0E+00		$\frac{c}{c}$	5.8E-01	-c	1.6E+00	C	5.2E+00	c	6.0E-03		6.1E-02	$\frac{\sigma}{c}$	2.0E+00
Toxaphene 1,2,4-Tribromobenzene	615-54-3	3.02+00	3.0E+02	N	3.9E+02	$\frac{\sigma}{N}$	3.1E+03	N	1.0E+04	N	1.8E+01	N	1.8E+02	$\frac{\sigma}{N}$	2.02.00
Tributyltin oxide (TBTO)	56-35-9	-	1.8E+01	N	2.3E+01	N	1.9E+02	N	6.1E+02	N	1.02.01		1.1E+01	N	
2,4,6-Trichloroaniline	634-93-5	 -	1.4E+01	C	1.9E+01	C	5.1E+01	C	1.7E+02	c	2.0E-01	С	2.0E+00	C	
1,2,4-Trichlorobenzene	120-82-1	7.0E+01	5.2E+02	N	6.5E+02	N	3.0E+03		3.0E+03	sat	2.1E+02	N	1.9E+02	Ň	3.0E-01
1,1,1-Trichloroethane	71-55-6		7.1E+02	N	7.7E+02	N	1.4E+03		1.4E+03	sat	1.0E+03	N	7.9E+02	N	1.0E-0 ⁻
1,1,2-Trichloroethane	79-00-5	5.0E+00		C	8.4E-01	C	1.8E+00	C	1.9E+00	С	1.2E-01	С	2.0E-01	С	9.0E-04
Trichloroethylene (TCE)	79-01-6		2.7E+00	С	2.8E+00	С	6.0E+00	С	6.1E+00	С	1.1E+00	С	1.6E+00	С	3.0E-03
Trichlorofluoromethane	75-69-4		3.8E+02	N	3.9E+02	N	1.3E+03	N	1.3E+03	N	7.3E+02	N	1.3E+03	N	
2,4,5-Trichlorophenol	95-95-4		6.1E+03	N	7.8E+03		6.2E+04	N	1.0E+05		3.7E+02	N	3.7E+03	N	1.4E+01
2,4,6-Trichlorophenol	88-06-2		4.4E+01	С	5.8E+01	С	1.6E+02	С	5.2E+02	С	6.2E-01	С	6.1E+00	С	8.0E-03
2,4,5-	93-76-5		6.1E+02	N	7.8E+02	N	6.2E+03	N	2.0E+04	N	3.7E+01	N	3.7E+02	N	
Trichlorophenoxyacetic															
2-(2,4,5-Trichlorophenoxy) propionic acid	93-72-1		4.9E+02	N	6.3E+02	N	5.0E+03	Ν	1.6E+04	N	2.9E+01	N	2.9E+02	N	
1,1,2-Trichloropropane	598-77-6		1.5E+01	N	1.5E+01	N	5.1E+01	N	5.1E+01	N	1.8E+01	N	3.0E+01	N	
1,2,3-Trichloropropane	96-18-4		1.4E-03		1.4E-03		3.1E-03		3.1E-03	С	9.6E-04	С	1.6E-03	С	
1,2,3-Trichloropropene	96-19-5		1.1E+01		1.2E+01	N	3.8E+01		3.9E+01		1.8E+01	N	3.0E+01	N	

EPA REG	ION 6- H	IUMAN	I HEA	11.	ГН МЕ	-DI	UM-S	PF	CIFIC	: 5	CRFF	NI	NGIF	VF	=1 S
			Basis: C= N= sa	=carci =non-o it= soi	nogenic effe carcinogeni I saturation aximum co	ects c effect conce	ets entration								
		MCL	Risk-l	3ase	ed Scree	ning	Levels								Soil Screening Level- Transfers
Contaminant	CAS No.	or			•	n, with	n and with	out de	ermal		Ambient A		Tap Water		from Soil
		Action Level	exposure routes) (Residential Scenario) (Residential Scenario) Residential Woo dermal Industrial Woo dermal Scenario) Ingestion & Industrial Industrial Scenario Industrial Woo dermal Ingestion & Industrial Industrial Woo dermal Ingestion & Industrial Indus										to: Ground water (DAF=1)		
		ug/l	mg/kg mg/kg mg/kg ug/m3 ug/l												mg/kg
				·										,	
1,1,2-Trichloro-1,2,2-	76-13-1		5.6E+03	sat	5.6E+03	sat	5.6E+03	sat	5.6E+03	sat	3.1E+04	N	5.9E+04	N	
trifluoroethane			ļ <u> </u>				ļ						ļ	<u> </u>	
Triethylamine	121-44-8	,	2.2E+01	N	2.3E+01	N	8.4E+01	N	8.8E+01	N	7.3E+00	N	1.2E+01	N	
1,2,4-Trimethylbenzene	95-63-6		5.2E+01	N	5.2E+01	N	1.7E+02	N	1.7E+02	N	6.2E+00	N	1.2E+01	N	
1,3,5-Trimethylbenzene	108-67-8		2.1E+01	N	2.1E+01	N	7.0E+01	N	7.0E+01	N	6.2E+00	N	1.2E+01	N	
Trimethyl phosphate	512-56-1		1.3E+01	С	1.7E+01	С	4.7E+01	С	1.5E+02	С	1.8E-01	C	1.8E+00		
1,3,5-Trinitrobenzene	99-35-4		1.8E+03		2.3E+03	N	1.9E+04		6.1E+04	N	1.1E+02	N	1.1E+03		
Trinitrophenylmethyl- nitramine	479-45-8		6.1E+02	N	7.8E+02	N	6.2E+03	N	2.0E+04	N	3.7E+01	N	3.7E+02	N	
2,4,6-Trinitrotoluene	118-96-7		1.6E+01	С	2.1E+01	С	5.8E+01	С	1.9E+02	C	2.2E-01	С	2.2E+00	С	
Vanadium	7440-62-2		5.5E+02	N	5.5E+02	N	1.4E+04	N	1.4E+04	N			2.6E+02	N	3.0E+02
Vanadium pentoxide	1314-62-1		7.0E+02	N	7.0E+02	N	1.8E+04	N	1.8E+04	N			3.3E+02	N	3.0E+02
Vanadium sulfate	13701-70-7		1.6E+03	N	1.6E+03	N	4.1E+04	N	4.1E+04	N			7.3E+02	N	3.0E+02
Vinclozolin	50471-44-8		1.5E+03	N	2.0E+03	N	1.6E+04	N	5.1E+04	N	9.1E+01	N	9.1E+02	N	
Vinyl acetate	108-05-4		4.3E+02	N	4.3E+02	N	1.4E+03	N	1.4E+03	N	2.1E+02	N	4.1E+02	N	8.0E+00
Vinyl bromide	593-60-2		1.9E-01	С	1.9E-01	С	4.1E-01	С	4.2E-01	С	6.1E-02	С	1.0E-01	С	
Vinyl chloride	75-01-4	2.0E+00	2.1E-02	С	2.2E-02	С	4.7E-02	С	4.9E-02	C	2.2E-02	С	2.0E-02	С	7.0E-04
Warfarin	81-81-2		1.8E+01	N	2.3E+01	N	1.9E+02	N	6.1E+02	N	1.1E+00	N	1.1E+01	N	
m-Xylene	108-38-3		2.1E+02	sat	2.1E+02		2.1E+02	sat	2.1E+02	sat	7.3E+02	N	1.4E+03	N	1.0E+01
o-Xylene	95-47-6		2.8E+02	sat	2.8E+02	sat	2.8E+02	sat	2.8E+02	sat	7.3E+02	N	1.4E+03	N	9.0E+00
p-Xylene	106-42-3		3.7E+02		3.7E+02		3.7E+02	sat	3.7E+02						1.0E+01
Zinc	7440-66-6		2.3E+04		2.3E+04	N	1.0E+05		1.0E+05				1.1E+04	N	6.2E+02
Zinc phosphide	1314-84-7		2.3E+01	N	2.3E+01		6.1E+02	N	6.1E+02	N			1.1E+01	N	
Zineb	12122-67-7		3.0E+03	N	3.9E+03	N	3.1E+04	N	1.0E+05	max	1.8E+02	N	1.8E+03	N	

(from EPA/NRC MOU) pci/g = picocuries per gram

MOU Table 1: Consultation Triggers for Residential and Commercial/Industrial Soil Contamination

Except for radium-226, thorium-232, or total uranium, concentrations should be aggregated using a sum of the fraction approach to determine site specific consultation trigger concentrations. This table is based on single contaminant concentrations for residential and commercial/industrial land use when using generally accepted exposure parameters. Table users should select the appropriate column based on the site's reasonably anticipated land use.

Radionuclide	Residential Soil Concentration	Industrial/Commercial Soil Concentration				
H-3	228 pCi/g	423 pCi/g				
C-14	46 pCi/g	123,000 pCi/g				
Na-22	9 pCi/g	. 14 pCi/g				
S-35	19,600 pCi/g	32,200,000 pCi/g				
Cl-36	6 pCi/g	10,700 pCi/g				
Ca-45	13,500 pCi/g	3,740,000 pCi/g				
Sc-46	105 pCi/g	169 pCi/g				
Mn-54	69 pCi/g	112 pCi/g				
Fe-55	269,000 pCi/g	2,210,000 pCi/g				
Co-57	873 pCi/g	1,420 pCi/g				
Co-60	4 pCi/g	6 pCi/g				
Ni-59	20,800 pCi/g	1,230,000 pCi/g				
Ni-63	9,480 pCi/g	555,000 pCi/g				
Sr-90÷D	23 pCi/g	1,070 pCi/g				
Nb-94	2 pCi/g	3 pCi/g				
Tc-99	25 pCi/g	89,400 pCi/g				
I-129	60 pCi/g	1,080 pCi/g				
Cs-134	16 pCi/g	26 pCi/g				
Cs-137+D	6 pCi/g	11 pCi/g				
Eu-152	4 pCi/g	7 pCi/g				
Eu-154	5 pCi/g	8 pCi/g				

MOU Table 1: Consultation Triggers for Residential and Commercial/Industrial Soil Contamination

Except for radium-226, thorium-232, or total uranium, concentrations should be aggregated using a sum of the fraction approach to determine site specific consultation trigger concentrations. This table is based on single contaminant concentrations for residential and commercial/industrial land use when using generally accepted exposure parameters. Table users should select the appropriate column based on the site's reasonably anticipated land use.

Radionuclide	Residential Soil Concentration	Industrial/Commercial Soil Concentration				
Ir-192	336 pCi/g	544 pCi/g				
Pb-210+D	15 pCi/g	123 pCi/g				
Ra-226	5 pCi/g	5 pCi/g				
Ac-227+D	10 pCi/g	21 pCi/g				
Th-228+D	15 pCi/g	25 pCi/g				
Th-232	5 pCi/g	5 pCi/g				
U-234	401 pCi/g	3,310 pCi/g				
U-235÷D	20 pCi/g	39 pCi/g				
U-238+D	74 pCi/g	179 pCi/g				
total uranium	47 mg/kg	1230 mg/kg				
Pu-238	297 pCi/g	, 1,640 pCi/g				
Pu-239	259 pCi/g	1,430 pCi/g				
Pu-241	40,600 pCi/g	172,000 pCi/g				
Am-241	187 pCi/g	568 pCi/g				
Cm-242	32,200 pCi/g	344,000 pCi/g				
Cm-243	35 pCi/g	67 pCi/g				

	compound not on EPA's	compound to use as a substitute
	compound not on EPA's medium specific screening level list	Substitute
. ,	chloroethane	
	cyclohexane.	
	methylcyclohexane	
		1 2-dichlorospone
	cis-I,3-dichloropropene trans-1,3-dichloropropene	(542-75-6)
	2-hexanone (buty/methy/ke	etone)
	isopropulbenzene	
	2-mitrophenol	4-Nitrophenol
	{	e bis (2-Chloroethyl) ether
	naphthalene	(3- Methylphenol)
	4-chloro-3-methylphenol	(p-chloro M-cresol)
	2-methylnaphthalene	1) P
	acenaphthylene acenaph 3-nitroanilene	thylene Pyrene
	acenaphthene	
- Approximate and the second s	fluorene	
	4-chlorophenylpheylether	
	H-nitminilano	
	4,6-dintro-2-methylphen	0
	4-bromophenyl phenylether	
	phenanthrene	Pyrene
	anthracene	
) ibutyl Phthalate
	fluoranthene	n
	benzo (g,h,i) perylene deHa-BHC (HCH)	Pyrene Plat pur
		Alpha-BAC Endosulfan
	Endosulfan I Endosulfan II	Endosulfon
	Endosulfan sulfate	Endosulfen
	Endrin Ketone	Endrin
(Endrin aldehyde	Endrin
	alpha-Chlordane	Chlordone
	gamma-Chlordane	Chlordone

To all the research students, assistants and technicians who have worked with me over the years on this fascinating subject, especially Andrew Jackson for his help with this book, and to my family for their patience and support.

HEAVY METALS IN SOILS

edited by

Dr B.J. ALLOWAY
Senior Lecturer in Environmental Science, Queen Mary and
Westfield College, University of London

Blackie Glasgow and London

John Wiley & Sons, Inc.

Blackie and Son Ltd Bishopbriggs, Glasgow G64 2NZ and 7 Leicester Place, London WC2H 7BP

Distributed in the USA and Canada by John Wiley and Sons, Inc. Orders from the USA only should be sent to John Wiley & Sons, I Wiley Drive, Somerset, New Jersey 08873

> © 1990 Blackie and Son Ltd First published 1990

All rights reserved No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, recording or otherwise, without prior permission of the Publishers.

British Library Cataloguing in Publication Data

Heavy metals in soils. 1. Soils. Chemical properties I. Alloway, B.J. 631.4'1

ISBN 0-216-92698-X

Library of Congress Cataloging-in-Publication Data

Heavy metals in soils / [compiled by] B.J. Alloway.

p. cm. Includes bibliographical references. ISBN 0-470-21598-4

1. Soils—Heavy metal content. 2. Heavy metals—Environmental aspects. 3. Plant-soil relationships. 4. Crops and soils. 5. Soil pollution. I. Alloway, B.J. \$592.6.H43H43 1990

631.4'16-dc20

89-22635

CIP

Phototypesetting by Thomson Press (India) Ltd., New Delhi Printed in Great Britain by Thomson Litho Ltd. East Kilbride. Scotland

Preface

Heavy metals are important in several ways: many are used industrially in technologically advanced countries, some are physiologically essential for plants and animals—and thus have a direct bearing on human health and agricultural productivity—and many are significant as pollutants of ecosystems throughout the world. Heavy metals in soils have received increasing attention in recent years, partly because of the growing scientific and public awareness of environmental issues, and partly because of the development of analytical techniques to measure their concentrations accurately. Atomic absorption spectrophotometry, for example, allows large numbers of samples to be analysed rapidly and accurately and thereby facilitates environmental monitoring.

Surveys carried out since the 1960s have indicated that soils in many parts of the world, especially in urban and industrial areas, contain anomalously high concentrations of heavy metals. Although in most cases the levels are not (yet) high enough to cause acute toxicity problems, increased concentrations in the food chain may cause significant health effects in the long term. Metals which accumulate in the human body, such as Cd and Pb, are a particular cause for concern. There have been reports of deaths and illness related to environmental Cd and Hg poisoning, and elevated levels of Pb in the blood of infants are becoming more common. These findings have provided a stimulus for more comprehensive studies of known or suspected areas of pollution and for complementary investigations of the chemical behaviour of heavy metals in soils and their uptake by plants.

Traditionally research by soil chemists has been concerned primarily with plant macronutrients (N, P and K) and little work was done on many of the heavy metals until recently. Although acute toxic effects of heavy metals on animals and plants have been recognised for a long time, the level of chronic accumulation of many metals in soils and ecosystems has come to be appreciated only in the last twenty years.

Soils are dynamic bodies in equilibrium with the environmental forces acting upon them. Climatic changes will affect the balance of interacting soil processes; the 'greenhouse effect' for example, together with increased acid precipitation ('acid rain'), will cause changes in the bioavailability of metals. The soil is a vital ecological and agricultural resource and needs to be protected against further degradation. The world's increasing population needs an adequate supply of healthy food, and heavy metals can affect both

5 Arsenic

P. O'NEILL

5.1 Introduction

Arsenic has achieved great notoriety because of the toxic properties of a number of its compounds. Fortunately there are great differences in the toxicity of different compounds, and the species that are most commonly found in soils are not the most toxic. The uptake of As by many terrestrial plants is not very great so that, even on relatively high As soils, plants do not usually contain dangerous levels of As.

Arsenic compounds appear to have been used by humans for several thousand years. Kipling [1] provides a general account of the history of As usage (and abusage) and reviews [2, 3, 4] of health effects and metabolic changes in animals, plants and humans give more details than can be provided in this short chapter.

The major present-day uses of As compounds are as pesticides, wood preservatives, and as growth promoters for poultry and pigs.

A recent review [5] of the global cycling of As suggested that natural inputs to the atmosphere were 45 000 t As/yr where as anthropogenic sources added 28 000 t As/yr. In soils the natural levels are dependent on the source rock type, and the normal range is 1-40 mg As/kg with most soils being in the lower half of this range [6, 7, 8, 9]. Levels may be elevated due to mineralisation, contamination from industrial activity (especially Cu smelters) and the use of As-based pesticides.

Arsenic differs from many of the common heavy metals in that the majority of the organo As compounds are less toxic than inorganic As compounds. Whilst having many chemical similarities to P, the soil chemistry of As is much more diverse because it can exist in more than one oxidation state under the normal range of soil conditions and As can form bonds with S and C much more readily than does P.

5.2 Geochemical occurrence

Over 200 As-containing minerals have been identified, with approximately 60% being arsenates, 20% sulphides and sulphosalts and the remaining 20%

ARSENIC

including arsenides, arsenites, oxides and elemental As [6]. The most common of the As minerals is arsenopyrite, FeAsS, and As is found associated with many types of mineral deposits especially those including sulphide mineralisation [7]. The concentration of associated As can range from a few parts per million up to percentage quantities.

There is relatively little difference in the concentration of As in rocks unless the levels have been raised by associated mineralisation. Mean values of the order of 2 mg/kg appear to be those most commonly found for igneous and sedimentary rocks, but the finer grained argillaceous rocks and phosphorites average 10-15 mg As/kg. Higher levels of As are often associated with the presence of sulphide minerals such as pyrites. The As contents of metamorphic rocks reflect those of the original igneous or sedimentary rocks.

Arsenic has often been used as a 'pathfinding' or indicator element when geochemical prospecting methods have been utilised to identify mineral deposits. It is a particularly good indicator because it is associated with a wide variety of mineral deposits; the general background levels of As in rocks are low; it often forms more volatile and soluble phases than the major elements with which it is associated and therefore the As halo is more widely dispersed; sensitive methods of analysis have been developed. It is especially useful for Au and Ag deposits but is also associated with Bi, Cd, Co, Cu, Fe, Hg, Mo, Ni, Pb, Pt metals, Sb, Se, Sn, U, W and Zn deposits.

Whilst the major simple As minerals such as arsenopyrite, orpiment, As₂S₃, realgar, AsS, and enargite, Cu₃AsS₄, have been mined in their own right as sources of As, nowadays most As is produced as a by-product of the extraction of Cu, Pb, Au and Ag from their ores.

5.3 Origin of arsenic in soils

5.3.1 Soil parent materials

There is little difference between the various types of igneous rocks with concentration ranges of < 1-15 mg As/kg. The argillaceous sedimentary rocks (shales, mudstones, slates) have significantly higher As levels (< 1-900 mg/kg), than sandstones and limestones (< 1-20 mg/kg). Phosphate rocks have ranges of < 1-200 m/kg.

The ability of As to bind to S ligands means that it tends to be found associated with sulphide-bearing mineral deposits either as separate As minerals or as a trace or minor constituent of other sulphide minerals. This leads to elevated levels in soils in many mineralised areas.

An overall mean As value for 2691 uncontaminated soils was 10 mg/kg [8]. These values can be compared to those for a mineralised area and its surroundings where the 0-5 cm surface soils had mean concentrations of 424 mg/kg and 29-51 mg/kg for apparently non-mineralised areas also in SW England [10].

It is clear that the general values for uncontaminated soils are significantly higher than for uncontaminated rocks. Whilst it is possible to believe that the weathering of the rocks leads to a relative retention of As in the soils, compared to the leaching out of other elements, the size of this increase is too large when the chemical properties of the relevant As species are considered. Data are generally lacking on As levels in uncontaminated rocks and soils. A survey of As levels in soils in Norway has shown that whilst below the humus layer concentrations are generally below 2 mg/kg the humus layer may contain up to 10 mg/kg which has been interpretated as being due to atmospheric pollution [11]. The effects of atmospheric inputs and extended geochemical anomalies, together with a non-random selection of samples for analysis, could be responsible for the lack of agreement between 'background' rock and soil As concentrations.

5.3.2 Agricultural materials

Arsenic compounds have been widely used as pesticides for over a hundred years, but their use is now declining, having probably halved in the decade from 1970 to 1980. The phytotoxic effects of As compounds made them attractive as herbicides and as desiccants to allow cotton to be easily harvested after defoliation. However, there has been concern about the build-up of As residues in soils and lake sediments which has occurred after the use of large quantities of inorganic As compounds. As a consequence other pesticides have replaced As compounds such as lead arsenate, which was commonly used in orchards to control insect pests, and sodium arsenite, which was extensively employed as a herbicide to clear aquatic weeds and defoliate seed potatoes.

Worldwide usage has been recently estimated to be 8000 t As/yr as herbicide, 12000 t As/yr as cotton desiceant and 16000 t As/yr in wood preservatives [5]. The rate of application of the pesticides is generally in the range of 2-4 kg As/ha, but larger quantities of dimethylarsinic acid may be used with application rates being up to three times greater [2]. In addition, small quantities of organo As compounds are used as animal feed additives, at the rate of 10-50 mg As/kg feed, to promote growth in chickens, turkeys and pigs. The compounds are rapidly excreted, often with little chemical change having apparently taken place.

Soils have generally been less badly affected by As build-up than aquatic sediments unless lead arsenate has been used, when residuals of 100-200 mg As/kg soil with highs of over 2500 mg As/kg have been reported [12]. The lack of long-term build-up of As in soils has been explained by referring to the production of volatile As compounds by microorganisms and leaching. The mobility of the As in aquatic sediments appears to have been reduced by the presence of abundant hydrated iron oxides and/or sulphide [13].

Phosphate fertilisers are a potential source of As. The concentration of As in the fertiliser will vary with the source of the phosphate rock used to produce

Element Concentrations in Soils and Other Surficial Materials of the Conterminous United States

By HANSFORD T. SHACKLETTE and JOSEPHINE G. BOERNGEN

U.S. GEOLOGICAL SURVEY PROFESSIONAL PAPER 1270

An account of the concentrations of 50 chemical elements in samples of soils and other regoliths



ECOLOGO CONTRACTOR

ELEMENT CONCENTRATIONS IN SOILS, CONTERMINOUS UNITED STATES

TABLE 1.—Average or median contents, and range in contents, reported for elements in soils and other surficial materials

[Data are in parts per million; each average represents arithmetic mean; leaders (--) in figure columns indicate no data available. A. average; M. median. <, less than;

>, greater than)

Element	This	report	Rose, and others (1979) (elements useful in	Vinogradov (1959) (presumably,	Jackson (1964)	Mitchell (1964)	Average or range	
	Average	Range	geochemical prospecting)	averages from worldwide sampling)	"Typical", ^l average, or range in values	Range in contents in Scottish sur- face soils		
A1	72,000	700 - <10,000		71,300	10,000 - 60,000			
As	7.2	<0.1 - 97	7.5 (H)	5			5	
Ba	33 580	<20 - 300 10 - 5,000	29 (M) 300 (H)	10	30	400 - 3,000	າ ວ 500	
Be	.92	<1 - 15	0.5 - 4	6		<5 - 5	6	
Br	.85	<0.5 - 11						
C, total	25,000 24,000	600 - 370,000 100 - 320,000		20,000 13,700	7,000			
Ce	75	<150 - 300						
Co	9.1	<3 - 70	10 (H)	8		<2 - 80	10	
Cr	54	. 1 - 2,000	6.3 (M)	200		5 - 3,000	200	
Cu	25	<1 - 700	15 (H)	20	20	<10 - 100	20	
F	430 26.000	<10 - 3,700 100 - >100,000	300 (M) 21.000 (M)	200 38,000	7,000 - 42,000		10,000 - 50,000	
Ga	17	<5 - 70	21,000 (n)	38,000	7,000 - 42,000	15 - 70	20	
Ge	1.2	<0.1 - 2.5		1		*******	. 5	
Hg	.09		0.056 (M)				.01	
I	1.2 15.000	<0.5 - 9.6	11.000 (8)	12.400	400 - 28,000			
La	37	50 - 63,000 <30 - 200	11,000 (M)	13,600	400 - 28,000	<30 - 200		
Li	24	<5 - 140	6.2 (H)	30			30	
Mg	9,000	50 - >100,000	0.2 (H)	6,300	<6,000			
Mn	550	<2 - 7,000	320 (M)	850		200 - 5,000	8 50	
Mo	.97	<3 - 15	2.5 (A)	2		<1 - 5	2.5	
Na	12,000	< 500 - 100,000		6,300				
Nb	11	<10 - 100	15 (A)				15	
Nd N1	46 19	<70 - 300 <5 - 700	17 (M)	40		10 - 800	40	
P	430	(20 - 6,800	300 (H)	800	500	10 - 600		
Pb	19	<10 - 700	17 (H)			<20 - 80	10	
Rb	67	<20 - 210	35 (M)	100				
S, total	1,600	<800 - 48,000	100 - 2,000	850				
Sb	.66 8.9	<1 - 8.8 <5 - 50	2 (A)	7		<3 - 15	.5	
Se	.39	<0.1 - 4.3	0.31 (M)	.001			.5	
Si		16,000 - 450,000		330,000				
Sn	1.3	<0.1 - 10	10 (A)			40 700	10	
Sr Ti	240 2,900	<5 - 3,000 70 - 20,000	67 (M)	300 4,600	1,200 - 6,000	60 - 700	300	
Th	9.4	2.2 - 31		7,000	1,200 - 0,000		13	
U	2.7	0.29 - 11	1 (A)				1	
V	80	<7 - 500	57 (H)	100		20 - 250	100	
Y	25 3.1	<10 - 200 <1 - 50		50		25 - 100		
Zn	60	<5 - 2,900	36 (M)	50			50	
Zr	230	<20 - 2,000	270 (M)	300		200 ~ >1,000		

Author's usage; generally used to indicate the most commonly occurring value.

collected by U.S. Geological Survey personnel along their routes of travel to areas of other types of field studies or within their project areas.

The locations of the routes that were sampled depended on both the network of roads that existed and the destinations of the samplers. Sampling intensity was kept at a minimum by selecting only one sampling site every 80 km (about 50 miles; selected for convenience because vehicle odometers were calibrated in miles) along the routes. The specific sampling sites

were selected, insofar as possible, that had surficial materials that were very little altered from their natural condition and that supported native plants suitable for sampling. In practice, this site selection necessitated sampling away from roadcuts and fills. In some areas, only cultivated fields and plants were available for sampling.

Contamination of the sampling sites by vehicular emissions was seemingly insignificant, even though many sites were within 100 m or less of the roads. Col-

1. unlike the geometric means shown in table 2, are estimates of geochemical abundance (Miesch, 1967). Arithmetic means are always larger than corresponding geometric means (Miesch, 1967, p. B1) and are estimates of the fractional part of a single specimen that consists of the element of concern rather than of the typical concentration of the element in a suite of samples.

Concentrations of 46 elements in samples of this study are presented in table 2, which gives the determination ratios, geometric-mean concentrations and deviations, and observed ranges in concentrations. The analytical data for most elements as received from the laboratories were transformed into logarithms because of the tendency for elements in natural materials, particularly the trace elements, to have positively skewed

TABLE 2.—Mean concent. ations, deviations, and ranges of elements in samples of soils and other surficial materials in the conterminous United States

[Means and ranges are reported in parts per million (µg/g), and means and deviations are geometric except as indicated. Ratio, number of samples in which the element was found in measurable concentrations to number of samples analyzed. <. less than; >, greater than;

Element	Conterminous United States		Western United States (west of 96th meridian)				Eastern United States (east of 96th meridian)						
	Mean	Devia- tion	Estimated arithmetic mean	Ratio	Mean	Devia-	Observed range	Estimated arithmetic mean	Ratio	Mean	Devia- tion	Observed range	Estimated arithmetic mean
Al, percent	4.7	2.48	7.2	661:770	5.8	2.00	1.5 - >11	7.4	450:477	3.3	2.87	3.7 - >10·	5.7
As	5. 2	2.23	7.2	728:730	5. 5	1.98	(0.10 - 97	7.0	521: 527	4.8	2.56	<0.1 - 73	7.4
B	26	1.97	33	506:778	23	1.99	<20 - 300	29	-25: 541	31	1.88	<20 - 150	38
Ba	440	2.14	580	778:778	580	1.72	70 - 5,000	570	541:541	290	2.35	.0 - 1.500	420
Be	.63	2.38	.92	310:778	.68	2.30	<1 - 15	.97	169:525	. 55	2.53	<1 - 7	.85
Br	. 56	2.50	.85	113:220	. 52	2.74	<0.5 - 11	.86	78:128	.62	2.18	<0.5 - 5.3	.85
C, percent-	1.6	2.57	2.5	250:250	1.7	2.37	0.16 - 10	2.5	162:162	-1.5	2.88	0.06 - 37	2.6
Ca, percent	.92	4.00	. 2.4	777:777	1.8	3.05	0.06 - 32	3.3	514: 514	.34	3.08	0.01 - 28	.63
Ce	63	1.78	75	81:683	65	1.71	<150 - 300	75	70:489	63	1.85	<150 - 300	76
Co	6.7	2.19	9.1	698:778	7.1	1.97	<3 - 50	9.0	403: 533	5.9	2.57	<0.3 - 70	9. 2
Cr	37	2.37	54	778:778	41	2.19	3 - 2.000	56	541:541	33	2.60	1 - 1,000	52
Cu	17	2.44	25	778:778	21	2.07	2 - 300	27	523: 533	13	2.80	<1 - 700	22
F	210	3.34	430	598:610	280	2.52	<10 - 1,900	440	390:435	130	4.19	<10 - 3,700	
Fe, percent	1.8	2.38	2.6	776:777	2.1	1.95	· 0.1 - >10	2.6	539: 540	1.4	2.87	0.01 - >10	2. 5
Ga	13	2.03	17	767:776	16	1.68	<5 - 70	19	431:540	9.3	2.38	<5 - 70	14
Ge	1.2	1.37	1.2	224: 224	1.2	1.32	0.58 - 2.5	1.2	130:131	1.1	1.45	<0.1 - 2.0	1.2
Hg	.058	2.52	.089	729:733	046	2.33	<0.01 - 4.6	.065	534:534	.081		0.01 - 3.4	.12
I	.75	2.63	1.2	169: 246	. 79	2.55	<0.5 - 9.6	1.2	90:153	.68	2.81	<0.5 - 7.0	1.2
K, percent ⁱ	1.5	.79	None	777:777	1.8	.71	0.19 - 6.3	None	537:537	1.2	.75	0.005 - 3.7	
La	30	1.92	37	462:777	30	1.89	<30 - 200	37	294: 516	29	1.98	<30 - 200	37
Li	20	1.85	24	731:731	22	1.58	5 - 130	25	479:527	-17	2.16	<5 - 140	22
Mg, percent	. 44	3.28	.90	777:778	.74	2.21	0.03 - >10	1.0	528: 528	. 21	3.55	0.005 - 5	.46
Mn	330	2.77	5 50	777:777	380	1.98	30 - 5 000	480	537:540	260	3.82	<2 - 7,000	540
Mo	. 59	2.72	.97	57:774	.85	2.17	<3 - 7	1.1	32: 524	.32	3.93	<3 - 15	.79
Na, percent	. 59	3.27	1.2	744:744	.97	1.95	C.05 - 10	1.2	363:449	25	4.55	<0.05 - 5	.78
Nb	9.3	1.75	11	418:771	8.7	1.82	<10 - 100	10	322:498	10	1.65	<10 - 50	1 2
Nd -	40	1.68	46	120:538	36	1.76	<70 - 300	43	109:332	46	1.58	<70 - 300	51
N1	13	2.31	19	747: 778	15	2.10	4 ··· <5 − 700	19	443:540	11	2.64	<5 - 700	18
P	260	2.67	430	524: 524	3 20	2.33	40 - 4,500	460	380:382	200	2.95	<20 - 6,800	
Pb	16	1.86	19	712:778	17	1.80	≠m <10 - 700	20 ·	422: 541	14	1.95	<10 - 300	17
Rb	58	1.72	67	221:224	69	1.50	<20 - 210	74	107:131	43	1.94	<20 - 160	53
S, percent-	.12	2.04	.16	34:224	. 1 3	2.37	<0.08 - 4.8	.19	20:131	.10	1.34	<0.08 - 0.31	.11
Sb	.48	2.27	.67	35:223	.47	2.15	<1 - 2.6	.62	31:131	. 52	2.38	<1 - 8.8	.76
Sc	7.5	1.82	8.9	685:778	8.2	1.74	<5 - 50	9.6	389: 526	6.5	1.90	<5 - 30	8.0
Se	. 26	2.46	. 39	590:733	.23	2.43	<0.1 - 4.3	. 34	449:534	.30	2.44	<0.1 - 3.9	.45
Si, percent ^l		6.48	None	250:250	30	5.70	15 - 44	None	156:156	34	6.64	1.7 - 45	
Sn	.89	2.36	1.3	218:224	.90	2.11	<0.1 - 7.4	1.2	123:131	.86	2.81	<0.1 - 10	1.5
S r	1 20	3.30	240	778:778	200	2.16	10 - 3,000	270	501:540	53	3.61	<5 - 700	1 20
Ti, percent	. 24	1.89	. 29	777:777	. 22	1.78	0.05 - 2.0	. 26	540: 540	. 28	2.00	0.007 - 1.5	.35
Th	8.6	1.53	9.4	195:195	9.1	1.49	2.4 - 31	9.8	102:102	7.7	1.58	2.2 - 23	8.6
V	2.3	1.73	2.7	224: 224	2.5	1.45	0.68 - 7.9	2.7	130:130	2.1	2.12	0.29 - 11	2.7
V	58	2.25	80 .	778:778	70	1.95	7 - 500	88	516:541	43	2.51	<7 - 300	66
Y	21	1.78	25	7 59 : 778	22	1.66	<10 - 150	25	477:541	20	1.97	<10 - 200	25
ҮЪ	2.6	1.79	3.1	754:764	2.6	1.63	<1 - 20	3.0	452:486	2.6	2.06	<1 ~ 50	3.3
Zn	48	1.95	60	766:766	55	1.79	10 - 2,100	55 🔹	473:482	40	2.11	<5 - 2,900	
Zr	180	1.91	230	777:778	160	1.77	<20 - 1,500	190	539: 541	220	2.01	<20 ~ 2,000	290

¹ Means are arithmetic, deviations are standard.

HANDBOOK OF ENVIRONMENTAL DATA ON ORGANIC CHEMICALS

SECOND EDITION

Karel Verschueren

Environmental Advisor
Heidemij/Adviesbureau
and
Department of Public Health and Tropical Hygiene
Agricultural University of Wageningen
Netherlands



Copyright © 1983 by Van Nostrand Reinhold

Library of Congress Catalog Card Number 82-10994 ISBN 0-442-28802-6

All rights reserved. Certain portions of this work copyright © 1977 by Van Nostrand Reinhold Company, Inc. No part of this work covered by the copyright hereon may be reproduced or used in any form or by any means—graphic, electronic, or mechanical, including photocopying, recording, taping, or information storage and retrieval systems—without written permission of the publisher.

Manufactured in the United States of America

Van Nostrand Reinhold 115 Fifth Avenue New York, New York 10003

Chapman & Hall 2-6 Boundary Row London SEI 8HN, England

Thomas Nelson Australia 102 Dodds Street South Melbourne, Victoria 3205, Australia

Nelson Canada 1120 Birchmount Road Scarborough, Ontario M1K 5G4, Canada

15 14 13 12 11 10 9 8 7 6 5

Library of Congress Cataloging in Publication Data Verschueren, Karel.

Handbook of environmental data on organic chemicals.

Bibliography: p.

ISBN 0-442-28802-6

1. Organic compounds—Environmental aspects—Handbooks, manuals, etc. I. Title.

[D196.073 V47 1983 363.7'384 82-10994]

CONTENTS

I INTRODUCTION 1

II ARRANGEMENT OF CATEGORIES 1


- A. Properties 1
- B. Air pollution factors 1
- C. Water pollution factors 2
- D. Biological effects 2

III ARRANGEMENT OF CHEMICALS 2


IV EXPLANATORY NOTES 2

- A. Properties 3
 - 1. Boiling points 4
 - 2. Vapor pressure 5
 - 3. Vapor density 6
 - 4. Water solubility 8
 - 5. Octanol/water partition coefficient 14
 - 6. Specific Gravity 36
- B. Air Pollution Factors 40
 - 1. Conversion between volume and mass units of concentration 40
 - 2. Odor 42
 - 3. Atmospheric degradation 59
 - 4. Natural sources 62
 - 5. Manmade sources 63
 - 6. Emission control methods and efficiency 63
 - 7. Sampling and analysis: methods and limits 63
- C. Water Pollution Factors 65
 - 1. Biodegradation 65
 - 2. Oxidation parameters 68
 - 3. Impact on biodegradation processes 72

٧



DISC 6 of 10 AR, KS, MO, OK



Issued December 1997 CD-TGR95-LV3-6

U.S. Environmental Protection Agency U.S. Department of Commerce National Oceanic and Atmospheric Administration BUREAU OF THE CENSUS

LandView® III is a desktop mapping system that includes database extracts from the Environmental Protection Agency, the Bureau of Census, the U.S. Geological Survey, the Nuclear Regulatory Commission, the Department of Transportation, and the Federal Emergency Management Agency. These databases are presented in a geographic context on maps that show jurisdictional boundaries; detailed networks of roads, rivers, and railroads; census block group and tract polygons; and schools, hospitals, churches, cemeteries, airports, dams, and other landmark features.

The minimum configuration required to run this CD-ROM:

PC with a 486-class processor, or Macintosh with a 68020 processor

8 MB of RAM

10 MB of free hard disk space

VGA color display

2X CD-ROM drive

Windows 3.1 (for PC), System 7.0 (for 68K Mac), System 7.1.2 (for Power Mac)